



# The SNS Linac and Storage Ring: Challenges and Progress Towards Meeting Them

N. Holtkamp for the SNS Collaboration \*

Oak Ridge National Laboratory (ORNL), Oak Ridge, TN 37830, USA

# More than 31 SNS Presentations in this conference

---




- THPLE020 - Algorithms for the SNS MEBT Commissioning\*
- WEPRI117 - An Improved Impedance Model of Metallic Coatings
- THPLE013 - Upgrading the SNS Compressor Ring to 3 MW
- THPLE023 - Finite Element Analysis And Frequency Shift Studies for The Bridge Coupler of The Coupled Cavity Linear Accelerator of The Spallation Neutron Source
- THPDO016 - High Power RF Tests on Fundamental Power Couplers for the SNS Project
- TUPLE101 - High Level RF for the SNS Ring
- WEPRI036 - Measurements of the coupling impedance of the SNS extraction kickers
- THPLE016 - Proton Beam Halo Intercept Design in the SNS HEBT Line
- TUPDO037 - A Narrow Quadrupole for the SNS Accumulator Ring
- THPLE017 - SNS Beam in Gap Cleaning and Collimation, S. Cousineau
- THPLE021 - Spallation Neutron Source Application Programming Environment ,
- WEPLE057 - Exploring Transverse Beam Stability in the SNS in the Presence of Space Charge
- TUPLE068 - SNS Extraction Kicker System and First Article BPFN Test
- TUPDO008 - Series Production of Accelerator Cavities for the Spallation Neutron Source
- THPLE011 - Accelerator Physics Model of Expected Beam Loss along the SNS Facility
- WEPLE037 - Coupling Correction for the SNS Accumulator Ring
- THPDO025 - Input Coupling and Higher-Order Mode Analysis of Superconducting Axisymmetric Cavities for the Rare Isotope Accelerator
- TUPDO039 - Elimination of Digitizing Errors in a Rotating Coil Mapper
- TUPDO038 - Characterization of a SNS Transfer Line Dipole
- WEPRI061 - Application of UAL-Based Correction Schemes to the SNS Accumulator Ring
- WEPLE055 - The SNS Ring Dipole Magnetic Field Quality
- THPLE012 - Commissioning of the SNS Front-End Systems at Berkeley Lab
- THPRI079 - Progress in Laser Beam Profile Monitor Development
- TUXGB001 - State of the Art of Multicell SC Cavities and Perspectives
- THPLE019 - Enhancing Surface Ionization and Beam Formation in Volume-type H- Ion Sources
- TUPLE119 - Development of 805-MHz Pulsed Klystrons for SNS
- WEPDO006 - Simulation Results for the Electron Cloud at the PSR and SNS
- THPRI071 - Tune Measurement in the SNS Ring
- MOPLE107 - 1.12 MVA Peak Two Quadrant Pulse Switch Mode Power Supply for SNS Injection Bump Magnet
- THPDO015 - Superconducting Prototype Cavities for the Spallation Neutron Source (SNS) Project
- THPLE024 - Selected Aspects of the SNS-Linac Performance

# The Spallation Neutron Source Partnership




Jan 02: Description	EAC	Accelerat.
Project Support	75.3	
Front End Systems	20.6	20.6
Linac Systems	288.4	288.4
Ring & Transfer System	153.1	153.1
Target Systems	98.1	
Instrument Systems	64.1	
Conventional Facilities	308.9	
Integrated Control Syst	59.6	59.6
BAC	1,068.1	
Contingency	124.6 23.9%***	
TEC	1,192.7	
R&D	102.0	81.6
Pre-Operations	117.0	93.6
TPC	1,411.7	696.9



*~500 People work on the construction of the SNS accelerator*

Oak Ridge, TN ????  
35° 49' N , 83° 59' W

# Development of Neutron Science Facilities



(Updated from *Neutron Scattering*, K. Skold and D. L. Price: eds., Academic Press, 1986)

97-3924E uc/djr

# SNS is the Forefront Facility for Future High Beam Power Accelerators

Highest Beam Power worldwide under construction

Stepping stone to next generation Spallation Sources




$$\overline{P}_{\text{beam}} = E [\text{eV}] \cdot I [\text{A}] \cdot T_{\text{pulse}} [\text{sec}] \cdot f_{\text{rep}} [\text{Hz}]$$

**SNS : Goal is to achieve 1.4 - > 2 ++ MW average power**

- The SNS will begin operation in 2006
- At 1.4 MW it will be ~8x ISIS, the world's leading pulsed spallation source
- The peak thermal neutron flux will be ~50-100x ILL

# Instrument Layout



# The Transformation of Chestnut Ridge into a construction site: More than 600 kH without major Lost workday !!



01-02942A/abh

# Progress on the Construction Site




Front End Building to Linac





# Accelerator Infrastructure



# Linac Tunnel



**March 13, '02**  
**Light at the end of the tunnel  
and through the side penetrations**



**March 13, '02**  
**First inserts in installation  
before the Klystron Building is  
finished**

# High Level Baseline Parameters for the SNS



Proton beam energy on target	1.0	GeV	SC linac output energy	1.0	GeV
Proton beam current on target	1.4	mA	HEBT length	170	m
Power on target	1.4	MW	Accumulator ring circ.	248	m
Pulse repetition rate	60	Hz	Ring fill time	1.0	ms
Beam macropulse duty factor	6.0	%	Ring beam extraction gap	250	ns
Ave. current in macro-pulse	26	mA	RF systems	h=1 +h=2	
H <sup>-</sup> peak current front end	38	mA	RTBT length	150	m
Chopper beam-on duty factor	68	%	Protons per pulse on target	1.5x10 <sup>14</sup>	
RFQ output energy	2.5	MeV	Proton pulse width on target	695	ns
FE + Linac length	335	m	Target material	Hg	
DTL output energy	87	MeV			
CCL output energy	185	MeV			


*AP Issue: Minimize losses along the accelerator chain !!!!*

*→ 1 Watt per meter ( or 1 nA ) apart from collimators*

# Primary Concern: *Uncontrolled Beam Loss*




- Hands-on maintenance: no more than 100 mrem/hour residual activation (4 h cool down, 30 cm from surface)
- 1 Watt/m uncontrolled beam loss for linac & ring
- Less than  $10^{-6}$  fractional beam loss per tunnel meter at 1 GeV;  $10^{-4}$  loss for ring



# SNS Project Commissioning Schedule




- Installation, Testing and Commissioning will happen at the same time



# Layout of Linac RF with NC and SRF Modules

● 402.5 MHz, 2.5 MW klystron	3 Transmitter	3 Modulators
⊖ 805 MHz, 5 MW klystron	4 Transmitter	4 Modulators
⊖ 805 MHz, 0.55 MW klystron	16 Transmitter	8 Modulators





# LBL: The SNS Front End Systems



**Ion Source**  
 Multicusp, rf driven, cesium-enhanced  
 → Create beam of about 50 mA, 65 keV  
 Dump extracted electrons at 5 keV



**SNS Front End (Linac Injector)**  
 Built and commissioned at LBNL Berkeley

**Low-Energy Beam Transport (LEBT)**  
 Fully electrostatic  
 2 Lenses  
 → Match beam into RFQ  
 Precharge into mini pulses  
 Steer beam



**Radio-Frequency Quadrupole (RFQ)**  
 402.5 MHz  
 4-vane structure with  $\pi$ -mode stabilizers

**Medium Energy Beam Transport (MEBT)**




# Front-End Systems Commissioned @ LBNL



- Ion source performance adequate for SNS early operations
  - 50 mA average pulse current achieved
  - Established lifetime exceeds 100 hrs
  - Expected to be much longer with latest antenna design: thicker coated antenna
- Feasibility of fully electrostatic LEBT proven
  - Good match of 40-mA beam into RFQ
- RFQ performs better than planned
  - More than 90% transmission at 40-mA current
- MEBT commissioning started on 4/4/2002
  - A maximum of 36 mA was achieved :
$$\epsilon_{x,y} \approx 0.3 \pi \text{ mm mrad}$$




# MEBT Collimation: Mitigate Halo when it develops!




- MEBT is the biggest contributor to halo formation  $\Rightarrow$  Collimate there!
  - Nonlinear space charge force due to large beam eccentricity (chopper box to anti-chopper box) is responsible for halo formation in MEBT
- Alternative MEBT optics and collimation at the chopper target box preempt halo formation, removing 97% of halo at CCL
- Beam loss potentially jeopardizes quadrupole performance if collimated in the DTL

# Beam Loss Occurs Primarily at Structure Interfaces for Mismatched Beams

Does not yet include MEBT scraping!



# LANL: Design, Accelerator Physics and Linac Components




- DTL is in full production
- First operation this summer

# CCL Construction is Underway

- Contract awarded
- Hot model operated at 130% of peak field and 190% average power




Sample  
Machining




Tuning of hot  
model

7/11/2001



87 MeV



Lathe Machining at  
ACCEL


# LANL: The RF Systems




~ 100 Klystron stations @ SNS

# JLab: The Superconducting Linac

- Emittance Growth and Halo Scraping
- SC cavities have large apertures and high field
  - Saves real estate, operational money, reduces beam loss (since most of it comes from gas stripping or aperture restrictions)




# Varying $\beta$ In Cavity Fixed Geometry



- Distribution assumed as a result of cavity production for  $\beta=0.61$  and  $\beta=0.81$  cavities
- High  $\beta$  cavities will be electropolished

- Surface Field:  $E_{\max}$
- On axis field:  $E_0$
- Accelerating field:  $E_0 T$ 
  - Variation of  $E_0 T$  because of varying  $\beta$  of particles




# Prototype Cavity Performance

$Q_0$  vs.  $E_{acc}$

High  $\beta$  performance

$E_{surf} = 35$  MV/m

▲ T=1.99K 30' RF & He Processing




Performance of 6-cell,  $\beta=0.81$  cavity, stiffening ring at 80 mm.



# High Power Requirements: 25%-50% Power Reserve in high and medium $\beta$





## Example: High $\beta$ cavities



# Development of the SC RF Cryomodules

- Prototype cryomodule (3 x  $\beta=0.61$ ) in test cave
- Piezo tuners: Development underway and in the baseline
- Tuner test ongoing
- Response @ 4 K
- Need 15  $\mu\text{m}$



Response: 60 Hz, 1800 N



# Production Cryomodule subassemblies

- Complete refrigeration system components and start refrigeration installation (ORNL)
- Complete prototype cryomodule testing
- Cryomodule production
  - Full cavity production
  - Start production cryomodule assembly
- Install electropolish cabinet


Schedule is tight!



**15 MV/m achieved in Prototype**

# BNL: Accumulator Ring and Transfer Lines

Nr of injected turns		1060
Ring revolution frequency	MHz	1.058
Ring filling fraction	%	68
<b>Ring transverse emittance 99%</b>	$\pi\text{mm mrad}$	<b>240</b>
<b>Ring transverse acceptance</b>	$\pi\text{mm mrad}$	<b>480</b>
<b>Space charge Tune shift</b>	$\Delta Q_{x,y}$	<b>0.15</b>
Peak Current	A	52
HEBT / RTBT Length	m	170 / 150
Ring Circumference	m	248
RTBT transverse acceptance	$\pi\text{mm mrad}$	480
Beam size on target (HxV)	mm x mm	200x70




Several commissioning beam dumps


- Totals:**
- 235 Low Power Bipolar Supplies (< 5 kW)
  - 24 Medium Power Bipolar Supplies (5-50 kW)
  - 101 Medium Power Supplies (5-50 kW)
  - 42 High Power Supplies (>50 kW)
  - 22 Kicker Power Supplies

# 1% of the Reference Beam Misses the Injection Foil

Control Beam




Reference Beam



- Some fraction of uncollimated beam will miss the foil
- 200 kW “injection beam dump” ( $H^0, H^+$ )

- Transverse Jitter at the Foil is a Function of Quad Vibrations & Increases the Effective Emittance
- This drives tolerance for mechanical design




## Tune Diagram during Accumulation




$N=0.5 \cdot 10^{14}$  – 263 turns

$N=1.0 \cdot 10^{14}$  – 526 turns

$N=2.0 \cdot 10^{14}$  – 1052 turns



# Electron Cloud Coating, Clearing Electrodes, Studies




- Electron-cloud: a potential threat to full-intensity performance
- Floating-ground BPMs serve dual purpose as clearing electrodes
  - 42 BPM, each holding ~ +/- 1 kV
  - No change of design
- Clearing electrodes near injection foil assembly
- TiN coating fully in progress

**Electrons behind bunch**

# Ring Progress – Vacuum, Coating, Handling


(Half-cell chamber welding)



(Titanium Nitride Coating)




(Half-cell lifting fixture)






# Ring Progress –Magnet, Assembly, Measurements




Half-cell trial assembly



Ring dipole measurement




Dipole assembly area



Ring dipoles

# Ring Progress – RF, Injection, Extraction, Collimation



(RF system & dynamic tuning test)




(Injection foil changer)



(RTBT collimator)



(Extraction kicker section)






(Extraction kicker PFN oil fill)

# Controls Team: Scattered Effort over 5 Labs



- MPS, PPS, Timing... Everything under EPICS
- Support has been provided for Front End runs at Berkeley
- Global components are arriving. Timing and MPS components distributed among partner labs for testing and integration
- Linac Controls ready for DTL Installation
- Have been operating FES @ Berkeley from ORNL +data analysis→GAN



# The Installation and Production of Components


- Design, construction, transport and installation
  - Transfer line installation
  - Chase insert installation on site
  - Buss bar production



Building transferline

ASD

ORNL



chase installation



busbar production



Installing transferline





# Diagnostics: Scattered Effort over 5 Labs



IDump
1 Position
1 Harp 1 Current

RING		
44 Position	2 Ionization Profile	
87 Loss	1 Current	5 Electron Det.
	2 Wire	1 Beam in Gap
	2 Video	2 Wall Current




**LASER Profile Monitor:**  
*The future device for high power beams*




# Survey and Alignment Group (6/7)

- Establish independent network on the site
- Verification of construction
- Establish Laser Tracker as prime tool to speed up installation and alignment
- Enable long-term survey



## Legend

- Standing Concrete Monument
- Tunnel Penetration Points
- ▲ Rod Monument
- between exterior points
- to penetration points
- through future target
- before buildings



## SNS Precision Network Diagram

Drawing updated on Sept. 6, 2001 by ks




# The SNS target: A 2 MW design


**Cavitation is most recent issue !**

**Several routes out ...: Materials, Geometry, Mitigation**

## SNS Target Configuration



Pits on inner surface  
using cylindrical  
geometry



# Summary

---



- With delivery of the Front End Systems to ORNL installation on the site has begun.
- The first of the 5 partnerlabs is transitioning out of the collaboration after delivery (LBNL).
- The Project is on track for commissioning of the target in December '05.
- Major issues ( at least the ones we know about) are addressed and solutions are identified

- My Assessment:

*It is a very fruitful, intellectually and technically challenging and certainly very productive collaboration. Thanks to the contributors !!!!*