

Status of Japanese XFEL Project and SCSS Test Accelerator

Tsumoru Shintake & SCSS-XFEL Team


RIKEN/SPring-8, Japan

- 2001-2003 : R&D on electron gun, alignment devices, C-band,...
- 2004~2005: Construction of 250 MeV Prototype Accelerator
- 2006, June 20: ***Lasing at 49 nm***, in SCSS Prototype Accelerator
- XFEL Project, 8 GeV, 1 Å has been approved, January 2006.
 - Construction 2006~2010.
 - First beam: ~2010

XFEL Project at SPring-8/RIKEN




SCSS : SPring-8 Compact SASE Source



- **Low Emittance Injector** → **Short Saturation Length**
- **High Gradient Accelerator** → **Short Accelerator Length**
C-band 35 MV/m x 180 m (active length) = 6 GeV
- **Short Period Undulator** → **Lower Beam Energy and Short Saturation Length**

In-Vacuum Undulator : $E = 6\text{ GeV}$, $\lambda_u = 15\text{ mm}$, $\lambda_x = 0.1\text{ nm}$

Milestone of SPring-8 X-FEL



SCSS & X-ray FEL Beam Parameter


at undulator section

		Prototype	X-ray FEL	
Beam Energy	E	0.25	8.0	GeV
X-ray Wavelength	λ	60	0.1	nm
Beam Emittance	ϵ_n	2	1.0	$\pi\text{mm.mrad}$
Bunch Length	Δz FWMH	150 0.5	75 0.25	μm psec
Transverse Beam Size	$\sigma_{x,y}$	100	25	μm
Peak Current	I_p	1	4	kA
Charge per bunch	q	0.5	1	nC
Undulator Parameter	λ_u K Length L	15 1.3 9	18 1.3 80	mm m
FEL Saturation Length	L_{sat}	10	80	m

CeB₆ Cathode & Heater Assembly




- CeB₆ Cathode 3 mm Diameter
- Emittance 0.4 π .mm.mrad (thermal emittance, theoretical)
- Beam Current 3 Amp. at 1450 deg.C (using graphite heater)
- Current Density > 40 A/cm²




Emittance Measurement for the SCSS Electron Gun

Beam Profile



Phase Space




Beam Energy : 500 keV
Beam Current : 1.0 A (peak)
Pulse Width : 3 μs (FWHM)

Normalized Emittance (ϵ_n, RMS)

Experiment: **1.1 $\pi \cdot \text{mm} \cdot \text{mrad}$** at Gun

In-Vacuum Undulator for SCSS X-FEL


- Segment length 4.5 m
- $N = 300/\text{segment}$, $\lambda_u = 15\text{mm}$
- $K \sim 1.3$, at Nominal gap 3.5 mm
- Mechanical minimum gap = 2mm
- 45-deg. tilted Halbach type
- More compact than ordinary ones



First prototype model


Gap can full-open 25 mm, which provides optical alignment laser pass, and enough beam acceptance at the beam commissioning time.

BPM Alignment System for SASE FEL



Cavity-BPM (Beam Position Monitor)


Newly developed Cavity-BPM
For SPring-8 XFEL. 4.7 GHz.



- TM110 mode excitation amplitude provides very linear beam position information.
- Slot-coupling design isolates TM110 BPM signal from TM010 common-mode mixing, which cause position offset.
- Electrical center meets very accurately with mechanical center in a few micron-meter (insensitive to variation of cable length, or detection circuit details).




Stable Support using Cordierite Ceramic



- Beam line level is designed low: **800 mm**.
- Low thermal expansion cordierite is used.
- For stable positioning and lower vibration, No screw is used for position adjustment, but machining the spacer.
- Filled with sand for damper.

Compact HV Pulse Modulator Supply

March 2003



- Driving 50 MW klystron,
and 500 kV electron gun.
- Compact, Oil Filled Design
W 1.7 m x D 1.2 m x H 1m.
- Good EMI shield.
- Better cooling for HV component.
- Eliminating cooling air fan.
- No dust accumulation
due to high voltage in air.
- No environmental effects:
moisture and temperature variation.



SCSS Test Accelerator




- C-band Accelerator
- 50 MW Klystron x 2
- Acc Structure 1.8 m x 4
- 250 MeV

- Undulator 4.5 m x 2 unit
- 15 mm period
- 4 mm gap



First Lasing at SCSS Prototype Accelerator.



- The first lasing: 49 nm
 - E-beam energy : 250 MeV
 - Bunch charge: 0.25 nC
 - Bunch length: (< 1 pse)
 - Peak Current (> 300 A)
-
- At moment spectrum width 0.5 nm is dominated by e-beam energy fluctuation ~ 0.2%.

Schedule & Conclusion

- SCSS Prototype Test Accelerator:
 - HHG seeding test 60 nm. Autumn 2006, *G. Lambart, this EPAC06.*
 - UVU user run will start 2007.
- XFEL Construction 2006 – 2010
 - **Big construction, 80 klystrons**
 - **400 m C-band Accelerator**
- Remain R&D Items
 - Power supply stability improvement 0.1 % $\rightarrow$ 0.01 %
 - L-band buncher accelerator (L-band APS 1m x 2, 20 MW klystron)
 - C-band or X-band flat-topping accelerator $\rightarrow$ increase charge.
 - LORA bunch length monitor.
 - In-situ field measurement tool for undulator.

Thank you very much!

