

Yu.Ts. Oganessian, S.N. Dmitriev, G.G. Gulbekian , I.V. Kalagin,

SHE-Factory:
new cyclotron facility for super
heavy element research


Igor Kalagin

FLEROV LABORATORY of NUCLEAR REACTIONS
JOINT INSTITUTE FOR NUCLEAR RESEARCH

HIAT 2018



DUBNA Gas Filled Recoil Separator




U-400 cyclotron (1978):

Ion beam energy: 5.00 – 5.75 MeV/A


Beam intensity: 6 - 8 · 10¹² pps

Consumption of ⁴⁸Ca = 0.5-0.8 mg/h

Beam time: 2000 – 4000 hours per year




H₂ 1.3 mBar



In operation since 1989

DUBNA Gas Filled Recoil Separator






U-400 cyclotron (1978):

Ion beam energy: 5.00 – 5.75 MeV/A

Beam intensity: 6 - 8 · 10¹² pps

Consumption of ⁴⁸Ca = 0.5-0.8 mg/h


Beam time: 2000 – 4000 hours per year



In operation since 1989

H₂ 1.3 mBar

BEAM





ЛАБОРАТОРИЯ ЯДЕРНЫХ РЕАКЦИЙ



1	Периодическая таблица элементов Д.И. Менделеева D.I. Mendeleev's Periodic Table of Elements																18
Водород 1 H 1.008 Hydrogen	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	Гелий 2 He 4.0026 Helium
Литий 3 Li 6.94 Lithium	Бериллий 4 Be 9.0122 Beryllium	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	Неон 10 Ne 20.18 Neon
Натрий 11 Na 22.99 Sodium	Магний 12 Mg 24.305 Magnesium	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28
Калий 19 K 39.098 Potassium	Кальций 20 Ca 40.078(4) Calcium	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36
Рубидий 37 Rb 85.468 Rubidium	Стронций 38 Sr 87.62 Strontium	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54
Цезий 55 Cs 132.91 Cesium	Барий 56 Ba 137.33 Barium	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72
Франций 87 Fr [223] Francium	Радий 88 Ra [226] Radium	89	90	91	92	93	94	95	96	97	98	99	100	101	102	103	104

Лантаноиды Lanthanoides


Церий 58 Ce 140.12 Cerium	Прометий 59 Pr 140.91 Promethium	Неодим 60 Nd 144.24 Neodymium	Прометий 61 Pm [145] Promethium	Самарий 62 Sm 150.36(2) Samarium	Европий 63 Eu 151.96 Europium	Гадолиний 64 Gd 157.25(3) Gadolinium	Тербий 65 Tb 158.93 Terbium	Диспрозий 66 Dy 162.50 Dysprosium	Гольмий 67 Ho 164.93 Holmium	Эрбий 68 Er 167.26 Erbium	Тулий 69 Tm 168.93 Thulium	Иттербий 70 Yb 173.05 Ytterbium	Лютеций 71 Lu 174.97 Lutetium
------------------------------------	---	--	--	---	--	---	--------------------------------------	--	---------------------------------------	------------------------------------	-------------------------------------	--	--

Актиноиды Actinoides



Торий 90 Th 232.04 Thorium	Протактиний 91 Pa 231.04 Protactinium	Уран 92 U 238.03 Uranium	Нептуний 93 Np 237.04 Neptunium	Плутоний 94 Pu 244.06 Plutonium	Америций 95 Am 243.06 Americium	Кюриум 96 Cm 247.07 Curium	Берклий 97 Bk 247.07 Berkelium	Калифорний 98 Cf 251.08 Californium	Эйнштейний 99 Es 252.08 Einsteinium	Фермий 100 Fm 257.10 Fermium	Менделевий 101 Md 258.10 Mendelevium	Нобелий 102 No 259.10 Nobelium	Лоренций 103 Lr 262.10 Lawrencium
-------------------------------------	--	-----------------------------------	--	--	--	-------------------------------------	---	--	--	---------------------------------------	---	---	--

H - символ / symbol
1.00794 - атомная масса / atomic mass
1s² - электронная конфигурация / electron configuration
13.59844 - 1-я потенциал ионизации, эВ / 1st ionization potential, eV
0.8859 - плотность, кг/м³ / density, kg/m³
-259.34 - температура плавления, °C / melting temperature, °C
-252.87 - температура кипения, °C / boiling temperature, °C



Region of superheavy nuclei




Even-Z nuclei



Elements 115 and 117



Production cross-sections of heavy and super-heavy



What is beyond 118 element?

Heaviest target: $^{251}\text{Cf} + Z_{\text{max}} = 118 \dots$



➤ Heavier projectiles (^{50}Ti , ^{54}Cr , ^{58}Fe , ^{64}Ni)

**Sufficient increasing of overall
experiment efficiency is needed!**

Superheavy Elements (SHE) Factory




SHE Factory Building

High-current cyclotron DC-280



New facilities:

- New gas-filled separator
- Preseparator
- SHELS
- Etc.



SHE Factory – the Goals

- **Experiments at the extremely low ($\sigma < 100$ fb) cross sections:**
 - **Synthesis of new SHE in reactions with ^{50}Ti , ^{54}Cr ...;**
 - **Synthesis of new isotopes of SHE;**
 - **Study of decay properties of SHE;**

- **Experiments requiring high statistics:**
 - **Nuclear spectroscopy of SHE;**
 - **Study of chemical properties of SHE.**

DC-280 CYCLOTRON- THE NEW FLNR ACCELERATOR

To satisfy the **Goals**, the DC-280 has to provide the following parameters of ion beams:

Ion energy	4÷8 MeV/n
Ion masses	10÷238
Intensities (A~50)	>10 pμA
Beam emittance	less than 30 π mm·mrad
Efficiency of beam transfer	>50%

Ion energies correspond to total accelerating potential up to 40 MV

Stand-alone SHE factory with DC-280 cyclotron



SHE factory building 2012



SHE factory building 2018



DC280 (expected)
E=4÷8 MeV/A


Ion	Ion energy [MeV/A]	Output intensity
${}^7\text{Li}$	4	1×10^{14}
${}^{18}\text{O}$	8	1×10^{14}
${}^{40}\text{Ar}$	5	6×10^{13}
${}^{48}\text{Ca}$	5	$6,2 \times 10^{13}$
${}^{54}\text{Cr}$	5	2×10^{13}
${}^{58}\text{Fe}$	5	1×10^{13}
${}^{124}\text{Sn}$	5	2×10^{12}
${}^{136}\text{Xe}$	5	1×10^{14}
${}^{238}\text{U}$	7	5×10^{10}

DC-280


Main Parameters

Ion sources	DECRIS-PM - 14 GHz Superconducting ECR (developing stage)
Injection energy	Up to 80 keV/Z
A/Z range	4÷7.5
Energy	4÷8 MeV/n
Magnetic field level	0.6÷1.3 T
K factor	280
Magnet weight	1000 t
Magnet power	300 kW
Dee voltage	2x130 kV
RF power consumption	2x30 kW
Flat-top dee voltage	2x14 kV
Deflector voltage	90 kV

Configuration of the DC-280




DC-280 cyclotron




Launching and Tuning Works on the DC-280 systems without ion beam


Working diagram of the DC-280



Working diagram of the DC-280




DECRIS-PM ion source



Results of bench test of DECRIS-PM

Frequency	Power consumption	Ion currents, pμA													
		Q+	5+	7+	8+	9+	10+	11+	12+	15+	17+	19+	20+	23+	26+
14 GHz	5 kW	Ar			116	56		19	13						
		Kr							13	12	7,3	2,6			
		Xe											3,9	3	2
		²⁴ Mg	90	20	5	1,7									
		⁴⁰ Ca		16	22	24		14	4,8						
		⁵⁰ Ti				10	7,2	5,5	1,9						
		⁵⁶ Fe					9,4	8	5						

Beam injection system




Beam injection system



The HV platform



Area of the electrostatic deflector (Bender)




The DECRIS-PM ion source area




Area of the accelerating tube

Magnetic system of ДЦ-280


Size of magnet yoke LxWxH	8.76x4.08x4.84 m ³
Pole diameter	4 m
Gap between central plugs	400 mm
Valley/hill gap	500/208 mm/mm
Magnet weight	1000 t
Magnet power	300 kW
Maximal current	1000 A
Magnetic field level	0.6÷1.3 T




DC-280- isochronous cyclotron



Magnet assembling: September-November 2016
Magnetic field measurements: June-September 2017



Magnet assembling (November 2016)





Comparative radial distributions of
calculated and measured average magnetic
field at the main coil current of 750A


$F_{rf}=7.32\div 10.38\text{ MHz}$
$F_{ff}=21.96\div 31.14\text{ MHz}$

$$\mathbf{F}_{ft} = 21.96 \div 31.14 \text{ MHz}$$

RF system



RF resonator with dee




Flat-top resonator



RF generators

Beam extraction system

Extraction radius of
 $R_{\text{ext}}=1.79 \text{ m}$



Focusing
magnetic
channel

Electrostatic
deflector




Magnetic channel

$L=0.9 \text{ m}$, $G=4.6 \div 8.4 \text{ T/m}$





Assembling of the deflector

$L=1.8 \text{ m}$, $E=90 \text{ kB/cm}$



Electrostatic deflector in vacuum chamber

Beam transport channels



Bending magnet $\pm 50^\circ$


Steering magnet

Quadrupole doublet

Control and power supply systems



Power supplies of cyclotron



Power supplies of injection

Water cooling system



DC-280 control room




Launching and Tuning Works on the DC-280 systems without beam: June – Oct. 2018

Obtaining licenses and permits : Nov. 2018

Commissioning: Nov. – Dec. 2018

Plan of the 1-st floor of the SHE Factory



Experimental area ~1000 m² (3 halls)

First-day experiments at SHE Factory

Aims of the experiments:

1. Test of functionalities of all the systems of new accelerator and new gas-filled recoil separator
2. Accumulate additional statistics for the chosen reactions



Chosen reactions:

$^{48}\text{Ca}+^{243}\text{Am}$ (50 days experiment)

and


$^{48}\text{Ca}+^{242}\text{Pu}$ (50 days experiment)

1. Enough material to prepare “big” targets (60 mg)
2. Relatively large cross sections (~ 8 pb)
3. Well-studied in previous experiments. Good for testing of the accelerator complex




First experiments at SHE Factory

Synthesis of new elements 119 and 120



First experiments at SHE Factory


Synthesis of new elements 119 and 120




Target materials	Producer	Isotope enrichment (%)
^{237}Np	IAR	99.3
^{239}Pu	RFNC	---
^{240}Pu	IAR/ORNL	99.98
^{242}Pu	RFNC/ORNL	99.98
^{244}Pu	ORNL	98.6
^{243}Am	IAR / ORNL	99.9
^{245}Cm	IAR	98.7
^{248}Cm	IAR /ORNL	97.4
^{249}Bk	ORNL	≥ 95
^{249}Cf	IAR/ORNL	97.3
$^{249,250,251}\text{Cf}$	ORNL	(50+14+36)%
0,35-0,40 mg /cm ² - $\approx$ 12 mg		

Isotope reactors irradiation of targets at HFIR

HFIR, ORNL, Oak Ridge, USA




CM-3, IAR, Dimitrovgrad, RF




22 mg of ^{249}Bk
have been produced in 250 days
irradiation
at HFIR (ORNL)

Target block design

old




Target



310 $\mu\text{g}/\text{cm}^2$ BkO₂
on 1.5 μm -Ti foil


- Ø = 120 mm, 1500 r.p.m. synchronous
- Beam wobbler or scanner,
- Segmented beam diafrgm
- Is in use at GFS, SHELS, MASHA

new





- Ø = 240mm, 1500 r.p.m. synchronous,
- e-beam & optical diagnostic,
- water cooling

New FLNR gas-filled separator (contracted)




Technical Design
Report No 412923




Reaction	Transmission
$^{244}\text{Pu}(^{48}\text{Ca}, 3n)^{289}\text{114}$	60 %
$^{244}\text{Pu}(^{58}\text{Fe}, 4n)^{298}\text{120}$	75 %

Arrangement of GFS-2 at the beam line No3



Arrangement



William Beeckman: WEOAA01

Installation of magnets: **June 2018**

Expected obtaining licenses and permits : **Nov. 2018**

Planned commissioning: **Dec. 2018**

Conclusion

- Launching and Tuning Works of the DC-280 cyclotron systems are being carried out.
- The GFS-2 separator is being assembled.
- Obtaining licenses and permits: Nov. 2018
- Planned commissioning of the DC-280 and GFS-2 : Nov. – Dec. 2018
- First experiments on SHE Factory: 2019

THANKS FOR YOUR ATTENTION!

