




The first year of operation of
PSI's new SC cyclotron and beam lines
for proton therapy.

*Marco Schippers, Jürgen Duppich, Gudrun Goitein, Eugen Hug,
Martin Jermann, Anton Mezger, Eros Pedroni,
for the PROSCAN team (>50 persons)*

PROSCAN: Stand-alone facility at PSI

January-June 2007



Contents

Acceptance tests of cyclotron

Commissioning of beam lines

Operation experience

Acceptance tests and commissioning of cyclotron



basic design: NSCL
(Henry Blosser)

Delivered by ACCEL/Varian

an intensive collaboration



<u>Sign contract:</u>	April 2001
Extracted beam:	April 2005
Beam on Gantry-1:	June 2006
First patient:	Febr 2007





Levels of Quality Assurance of cyclotron

- Measurements for information & reference, not specified
e.g.: field maps
- Acceptance of subsystems (factory acceptance by ACCEL)
e.g.: coil-winding
vacuum
- Acceptance tests (**37**) defined by PSI
acceptance measurements
e.g.: beam quality
nr. of beam interruptions
access to components / exchange time
acceptance checks
e.g.: documentation

Dec 05 - Febr 06
33 done & OK


Energy measurement

Ion chamber in water tank to measure proton range



Range in water $\Rightarrow E=250.4(1)$ MeV

Reliability: beam interruptions




Beam on/off and stability

Necessary for fast dynamic scanning (Gantry-2)


Vertical deflector in cycl. Center

-beam on/off




Acceptance tests:

- repetition rate 1 kHz ✓
 - beam off < 50 μsec ✓
 - intensity stability $\sigma < 5\%$ —
- (for Gantry-1 and München: ✓)




Scan modes of new Gantry-2


Spot scanning: step & shoot



Cont. scanning "TV" mode




kHz-Intensity modulation



7 s for a 1 liter volume.

Target repainting: 17 scans / 2 min.

Intensity + beam scanning:




15 cm / 30 ms

David Meer, Christian Hilbes, (Dec. 2006)

Intensity control



- **Max intensity** set by:
Ion source + phase slits






Roles of deflector plate:

- **decrease drift** of intensity
- **set requested intensity** within 5%

Febr. 2007: start program
to reach spec=> best: $\sigma = 3\%$
(see poster)



Extraction efficiency



R=30 cm: 100%


**Routinely:
80-83%**

**Electrostatic
extraction
elements**

>80% extraction efficiency:
Low dose to service staff



inside cyclotron



Mid plane open cap

24 h after beam off, June 2007
(extracted beam integral $72 \mu\text{A}\cdot\text{h}$) :

on pole, closed cap:

400 $\mu\text{Sv/h}$ (40 mrem/h)


mid plane, open pole cap:

250 $\mu\text{Sv/h}$ (25 mrem/h)

Commissioning of beam lines




Beam-energy adjustment




Carbon wedge degrader
238-70 MeV

5 mm Δ Range in 50 ms




Energy scanning, Estep ~5 mm range in water.




Energy: Degradation error sensitivity

Slit aperture:
 $dp/p \pm 0.5\%$



E degrader





If degrader-error ± 5 MeV:

E-shift
(MeV)

200 MeV: ± 1.5
90 MeV: ± 0.2

- highest sensitivity at high energy
- if degrader error < 1 MeV:
mainly transmission loss.



Range Variations:

$\sigma = 0.4$ mm


$\sigma = 0.4$ mm

$\sigma = 0.3$ mm

$\Rightarrow \sigma E < 0.05\%$



Cycl+beamline

Transmission





Dual scattering system for OPTIS-2

Transmission = 0.5% at 70 MeV, $dp/p = \pm 1\%$ => Optimize scattering system



Test foil made by laser ablation
(Fachhochschule Windisch)



Dual Ring: eff. = 36% **Multiple Ring: eff. = 57%**

Design model tested and confirmed at HMI

The Multiple Ring solution follows the ideas presented by Yoshihisa Takada (poster PTCOG43)

Operation experience






Febr-May 2007: 18 patients treated at Gantry-1

PROSCAN Status 10-05-2007 09:26:13


MMAC3	121 nA	Vdef.	0.54 kV	Regelung: <input type="checkbox"/>
SOL	120 nA	Degr.	162.0 MeV	Ref Extern

MMAP5X/6Y

<p>Kicker</p> <p>60.0 A</p> <p>HF</p> <p>120.4 kW</p> <p>8.40 V</p> <p>Extractor</p> <p>50.0 kV</p> <p>50.0 kV</p> <p>Hauptmagnet</p> <p>158.49 A</p> <p>Phase</p> <p>95 Grad</p> <p>Ionenquelle</p> <p>2.22 kV</p> <p>518.7 mA</p> <p>0.49 cc/min</p>	<p>QMA1/2/3</p> <p>-92.47 A</p> <p>101.85 A</p> <p>-97.96 A</p> <p>SMJ1x/2y</p> <p>-0.86 A</p> <p>-0.57 A</p> <p>SMA1x/1y</p> <p>-15.88 A</p> <p>1.29 A</p> <p>Ph. Spalt</p> <p>1543 nA</p> <p>427 nA</p>	 <p>BMA1 Device offen RPS_Bew. OK PaSS_Bew. OK</p> <p>BMB1 Gantry2 Device faehrt RPS_Bew. OK PaSS_Bew. NOK</p> <p>BME1 Gantry1 Device offen RPS_Bew. OK PaSS_Bew. OK</p> <p>Banker-Temperatur: 34.7 Grad C Helium-Level: 504 mm</p>	 <p>0.05 mm</p>  <p>12.55 mm</p> <p>Kollimatoren</p> <p>1.5 mm</p> <p>8.8 mm</p> <p>RPS/Safety switch box</p> <p><input checked="" type="checkbox"/> Ionenquelle</p> <p><input checked="" type="checkbox"/> HF reduziert</p> <p><input checked="" type="checkbox"/> HF</p> <p><input checked="" type="checkbox"/> Ablenkplatte</p>
--	---	--	--

Mastership: Gantry 1



Operation statistics first 15 weeks of patient treatment



Machine "Up" when:
 HF "on"
 AND
 Ion source "high"

961 hours Up Time
18 patients Gantry-1

$$Avail = 1 - \frac{Unsched\ Down\ Time}{Up\ Time}$$



UDT per week: occurs as single events
 ⇒ MTBF (UDT>0.5 h) \approx 1.5-2 weeks
 (typically at start up)

- We are happy with performances of cyclotron and beam lines
- Last problems are being solved
- Patient treatment has started at Gantry-1 and runs successfully

Currently in progress: (see poster)

⇒ acquire experience and optimize operation

⇒ commissioning OPTIS-2

⇒ installation Gantry-2

