


INSTALLATION AND FIRST COMMISSIONING OF THE LLRF SYSTEM FOR THE EUROPEAN XFEL

Julien Branlard, for the LLRF team





■ Introduction



- Brief reminder about the XFEL LLRF system
- Commissioning goals

■ Commissioning

- Planning
- Steps description + automation
- Results: some statistics


■ Assessment

- What went well, what didn't
- What's done, what's left




The European X-ray Free Electron Laser

- 17.5 GeV light source user facility
- TESLA superconducting 1.3 GHz RF cavities
- 1.4 msec RF pulses at 10 Hz
- e- beam 1.35 mA nom. - 4.5 mA max
- Dec. 18th 2015: first beam in injector
- 2015-2016: main tunnel installation
- Q1 of 2017: main linac commissioning
- May 4th 2017 : first lasing ! 😊
- End of 2017: first user operation



source: <http://www.xfel.eu>






source: <http://www.fis-landschaft.de>




YouTube watch online:

<https://www.youtube.com/watch?v=p3G90p4gIQA>

INTRODUCTION: the XFEL LLRF system




INTRODUCTION: the XFEL LLRF system




Technical commissioning represents >50% of the commissioning time

Intersystem commissioning is a key factor of the commissioning time

INTRODUCTION: goals



6



■ INJ (GUN, A1, AH1)

- Already commissioned and in operation (cold) throughout 2016
- Recommissioning necessary due to warm up/cool down + installation of new components

■ L1 (A2)


- First time commissioning of a complete RF station (4 cryomodules)
- “Commissioning” of the commissioning plan
- First time 32 cavity vector sum feedback control

■ L2 (A3, A4, A5)

- 3 times L1
- “Validation” of the commissioning plan

■ L3 (A6 – A20)

- 15 times L1
- Hardware slightly different
- Change strategy : horizontal commissioning (step 1 for all stations, then step 2, etc..)



■ Introduction

- Brief reminder about the XFEL LLRF system
- Commissioning goals

■ Commissioning

- Planning and milestones
- Steps description + automation
- Results: some statistics

■ Assessment

- What went well, what didn't
- What's done, what's left

Commissioning team

- 8 LLRF experts
- 6 trained colleagues from DESY
- 6 colleagues from external facilities




Christian



Mariusz



Mathieu



Matthias




Sven



Uros



Valeri



Wojtek

Commissioning team of 20 people

Commissioning shifts

- Two 8-hours shifts / day
- Following DESY's operator shift program

Procedure

- Parallel work (station-wise)
- Follow detailed commissioning checklist
- Gather issues.
- Investigate/fix on maintenance day (once a week)

B. TUNING AND CALIBRATION

LLRF commissioning checklist

Last update: 20-Dec-16

RF station: _____ Date: _____

Operator(s): _____ Shift: _____

A. START UP		
1 Check servers	Done	Comments
a. lrfCtrl server master		
b. lrfCtrl server slave		
c. diagnostic server master		
d. diagnostic server slave		
e. other servers		
i. DCM		
ii. PSM		
iii. quench detect		
iv. LOGM / uLOG		
v. ADC scope		
f. Far detuning server		
g. QL set		
2 Check ADC readings		
a. Forward master / slave		
b. Reflected master / slave		
c. Probe master / slave		
3 Check drive		
a. Drive ability, drive level		
b. VM readout		
c. CPIM read out		
d. DAC offset adjustment (MATLAB script)		
4 Server initialization		
a. Down converter attenuation		
b. Timing settings		
c. Scaling factors		
5 Save and restore file		
a. Create save and restore file		

Cryo String	F stati	Model	LLRF system ready for	Attenuat on optimizat	Frequen cy tuning	Coopl er tuning	Power-based calibra	Attenuat on optimizat	Cavity Phasing
INJ	A1	M1							
		M2							
		M3							
		M4							
CS1	A2	M1							
		M2							
		M3							
		M4							
A3	A3	M1							
		M2							
		M3							
		M4							
CS2	A4	M1							
		M2							
		M3							
		M4							
A5	A5	M1							
		M2							
		M3							
		M4							
A6	A6	M1							
		M2							
		M3							
		M4							
CS3	A7	M1							
		M2							
		M3							
		M4							
A8	A8	M1							
		M2							
		M3							
		M4							
A9	A9	M1							
		M2							
		M3							
		M4							
CS4	A10	M1							
		M2							
		M3							
		M4							
A11	A11	M1							
		M2							
		M3							

COMMISSIONING: LLRF milestones (1/2)

■ Initial checks

- LLRF system ready for commissioning ?

RF ONLY

■ ~~Cold coupler conditioning~~

■ RF signal checks: Forward and Reflected

- Cabling issues? Signal saturation?

■ Frequency tuning

- From parking position to resonance

■ RF signal checks: Probe

- Cabling issues? Signal saturation?

■ Coupler tuning

- Target $Q_L = 4.6e6$

■ Power-based gradient calibration


- Coarse

■ Closed-loop operation


- Feedback, learning feedforward, ...

**READY FOR
BEAM**


COMMISSIONING: LLRF milestones (2/2)



- **Establish beam transport**
 - 30 bunches, 0.5nC
- **Cavity phasing**
 - Using waveguide phase shifters
- **Beam-based gradient calibration**
 - Fine relative calibration
 - Absolute validation using energy server



**BEAM
REQUIRED**




■ Estimated schedule

- **Injector** (gun, A1, AH1)
- **L1** (1 RF station)
- **L2** (3 RF stations)
- **L3** (15 RF stations)




- 2 weeks ✓
- 2 weeks ✓
- 2 weeks ✓
- 2 months ✓



■ Cavity tuning


1. Perform initial check (1 motor turn ~ 15 kHz)
“Check that the detuning changes in the correct direction, in the proper amount and for the correct cavity”
2. if successful, tune to resonance (coarse)
“Based on step-to-resonance measured at AMTF”
3. If successful, tune to resonance (fine)




Far Tuning RF station STATION.A16.L3


C1.M1.A16.L3	C2.M1.A16.L3	C3.M1.A16.L3	C4.M1.A16.L3	C5.M1.A16.L3	C6.M1.A16.L3	C7.M1.A16.L3	C8.M1.A16.L3
Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]	Detuning 0.55 [kHz]
Operator messages --	Operator messages --	Operator messages --	Operator messages --	Operator messages --	Operator messages --	Operator messages --	Operator messages --
FFT Initial check Perform step Detuning delta (+) -1.480E [Hz] Motor resolution 0.423 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.546E [Hz] Motor resolution 0.438 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.600E [Hz] Motor resolution 0.454 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.654E [Hz] Motor resolution 0.454 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.546E [Hz] Motor resolution 0.438 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.546E [Hz] Motor resolution 0.438 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.600E [Hz] Motor resolution 0.454 [Hz/step] Revert step	FFT Initial check Perform step Detuning delta (+) -1.654E [Hz] Motor resolution 0.454 [Hz/step] Revert step
Resonance - motor pos. 0.880019	Resonance - motor pos. 0.622340	Resonance - motor pos. 0.489113	Resonance - motor pos. 0.897301	Resonance - motor pos. 0.676009	Resonance - motor pos. 0.676763	Resonance - motor pos. 0.708117	Resonance - motor pos. 0.641286
Expert Motor position Start Stop Set -419384 Current -419384	Expert Motor position Start Stop Set -419384 Current -419384	Expert Motor position Start Stop Set -489816 Current -489816	Expert Motor position Start Stop Set -483728 Current -483728	Expert Motor position Start Stop Set -417194 Current -417194	Expert Motor position Start Stop Set -481786 Current -481786	Expert Motor position Start Stop Set -391167 Current -391167	Expert Motor position Start Stop Set -435914 Current -435914

Example: A3.L3 1 RF station (32 cavities) tuned from parking position to resonance in 1h.





■ Cavity tuning











■ Cavity tuning





■ **RF signal checks (1/2)**

“what’s wrong with this picture?”





RF signal checks (2/2)

- 3-4 mins per RF station
- Verify phase shifter functionality (32x)
- Identify cabling errors:
 - FORW ↔ REFL
 - C1 ↔ C2

Reminder:

- LLRF has 2500+ RF signals (Probe, forward, reflected)
- x2 counting int/ext cabling



■ Cabling issues



- **15 cabling issues** (outer rack) identified before cool down
- **11 cabling issues** (outer rack) identified after cool down
- **0 cabling issues** (inner rack) identified so far

} < 1%

■ Multipacting

- Observed on nearly all stations
- Start appearing around 550-600 MV (i.e. ~17-18 MV/m)
- Up to 50% of cavities / cryomodule required conditioning (worse case)
- Conditionable on all stations
- Required couple of hours per station (@10 Hz)
- 3 GeV additional energy after conditioning


COMMISSIONING: multipacting commissioning



- **4 out of 616** couplers shorted after test in XTL
 - A4.M4.C4 coupler problem: T70K [shorted]
 - A12.M4.C1 coupler problem: T70K [shorted]
 - A16.M2.C1 coupler problem: T70K [shorted]
 - A20.M4.C1 coupler problem: T70K [shorted]



- **5 out of 616** cavities not used due to AMTF results
 - A5.M1.C5 temporary, shorted pick up
 - A6.M3.C1 high FE/X-ray (10 MV/m limit)
 - A7.M2.C7 high FE/X-ray (11 MV/m limit)
 - A10.M1.C3 low Eacc BD (no FE) (13 MV/m limit)
 - A18.M4.C4 high FE/X-ray (23 MV/m limit + wrong P_{FORW})

- **10 out of 19** RF stations actually have all cavities tuned
 - i.e only 50% of the RF stations have a 32-cavity vector sum




COMMISSIONING: some statistics

RF regulation (in-loop)



Intra-pulse $\sigma(dA/A) = 0.0057 \%$
 Pulse-to-pulse $\sigma(dA/A) = 0.0056 \%$



Intra-pulse $\sigma(dP) = 0.0051 \text{ deg.}$
 Pulse-to-pulse $\sigma(dP) = 0.0024 \text{ deg.}$



Specifications: $\sigma(dA/A) = 0.01 \%$ ✓
 $\sigma(dP) = 0.01 \text{ deg.}$ ✓

Courtesy S. Pfeiffer

■ Introduction

- Brief reminder about the XFEL LLRF system
- Commissioning goals

■ Commissioning

- Planning
- Steps description + automation
- Results: some statistics

■ Assessment

- What went well, what didn't
- What's done, what's left

ASSESSMENT: what went well


Install / test as much as possible, as early as possible

- Individual component tests
- Crate installation
- Rack installation




Automation


- Simple scripts
- Broken down into single, modular tasks



Availability of cryomodule test data

- Results from individual cryomodule tests
- Cavity gradient limits, phase shifter limits, ...
- What to pay attention to (tune / don't tune)





Checklists + documentation

- Prepare the checklist
- Test the checklist
- Iterate the checklist
- Stick to it

Machine operation

- Handed over RF station to operators after couple of days
- Regular operator trainings
- On-call LLRF experts
- Finite State Machine: ramp up / down stations + recovery

Strong Team

- Large machine → large commissioning team
- Beware of the installation burn out (2 years...)
- External support (fresh eyes + enthusiasm)

LLRF commissioning checklist

RF station: _____ Last update: 15-Feb-17
Operator(s): _____ Date started: _____

A. START UP			
	Done	Date	Comments
1 Check servers			
a. lrfCtrl server master			
b. lrfCtrl server slave			
c. diagnostic server master			
d. diagnostic server slave			
e. other servers			
i. DCM			
ii. PSM			
iii. quench detect			
iv. LDCM / sLDC			
f. Check DAQ archiving (DAQdatagUI)			
g. Far detuning server			
h. CL set			
2 Check ADC readings			
a. Forward master / slave			
b. Reflected master / slave			
c. Probe master / slave			
3 Server Initialization (MATLAB)			
a. Attenuation			
PROBE to 0 dB			
FORW & REF to 33.5 dB			
VM (out 6dB, loopback 0 dB)			
b. Feed forward settings			
initial delay = 20 usec			
fill time = 750 usec			
flat time = 550 usec			
FF_limit to 140000			
c. Scaling factors			
set BIT_SCALING to 1000			
POWER_SCALING to 23.92			
SP_limit to 1000			
4 Timing setups			
a. Trigger alignment			
Master timing (TRIG + GATE)			
slave timing (TRIG)			
modulator + 0.3 ms = RF gate			
5 Check drive			
a. Drive ability, level (SP=100 → VM=6)			
b. VM readout			
c. CPIM read out (set it to cold path)			
d. DAC offset adjustment (MATLAB script)			
optimize on CPIM			
6 Save and restore			
a. Create "initial" Save and Restore file			

European XFEL - LLRF commissioning checklist

2



■ Initial checks of tuners drivers

- More than 40% initial checks failed
- Several iterations required → time consuming

■ Triggered one cryo incident

- Multipacting: “working here but quenching there”

■ Too long recovery time (“phase jumps”)

- Intricate combination of timing + reset + clocks resulting in 240 deg. phase jumps (single boards) after a crate reboot

■ Piezo driver


- Piezo driver production was delayed > 2 years
- To be installed and commissioned during maintenance this year

■ The baseline commissioning phase went relatively well

- Strong commissioning team
- Automation

■ Still a few milestones on our “to do” list

- Max energy ?
- Piezo
- Performance assessment, stability, drifts (i.e. “advanced” commissioning)
- Improved diagnostics (aging, radiation, system health)



Courtesy N. Walker

■ Further higher-level development

- Inter-RF station communication + automation
- Multi-beamline operation

THANK YOU FOR YOUR ATTENTION !




Photo Dirk Noelle