

The Installation of the 28GHz Superconducting ECR Ion Source At KBSI

A detailed 3D cutaway diagram of the 28GHz Superconducting ECR Ion Source. The diagram shows a long, complex assembly of components, including a large rectangular cryogenic chamber on the left, a central superconducting cavity, and various support structures and diagnostic equipment extending to the right. The components are rendered in a light gray wireframe style, showing the intricate internal and external structures of the ion source.

Mi-Sook Won

**on behalf of the ECR IS development team,
Busan Center, Korea Basic Science Institute**

I Overview of KBSI Accelerator

II A goal of KBSI Accelerator

III Current status of ECR ion source

3.1 Plasma chamber and extraction system

3.2 28 GHz Microwave system


3.3 Superconducting magnet system

3.4 Remote control program

IV First plasma ignition


V Future plan

I. Overview of KBSI Accelerator




I. Overview of KBSI Accelerator

(Li^{2-3+} production $>1pA$)




II. A goal of KBSI accelerator: Neutron facility

Concept of fast neutron production



Inverse kinematics: the produced neutron will go forward. Production angle is limited about 30 degree compared to forward direction. High intensity neutron beam.

Concept of the heavy ion linear accelerator based neutron production.



Normal kinematics: the produced neutron will be go to all direction.


II. A goal of KBSI accelerator: Neutron facility

Requirement of KBSI Neutron Facility

- Beam intensity: $\text{Li}^{2\sim 3+}$ higher than 2pMA
- Beam energy : $\sim 2 \text{ MeV/u}$
- Gas target : $> 350 \text{ Torr}$
- Neutron detection : High efficiency for fast neutron

Fast Neutron Yield

$$Y_n = F_{\text{Li}} \times \rho \frac{N_A}{A} \times L \times \sigma$$



Y : Neutron yield

F_{Li} : Beam flux

ρ : Density

N_A : Avogadro constant

A : Atomic number


L : Target length

σ : Cross section


	Li energy (MeV/u)	Neutron yield	Limit angle (deg)	Maximum neutron energy (MeV)
	1.88	8.5×10^8	\sim few deg.	1.88
	1.9	1.7×10^{10}	4	2.1
	1.92	3.6×10^{10}	7	2.3
	2.5	1.0×10^{12}	28	4.0

III. The current status of KBSI ECRIS



Layout of KBSI ECR ion source




3.1 Plasma Chamber & Extraction System




3.1 Plasma Chamber & Extraction System



3.2 28 GHz microwave system



3.2 28 GHz microwave system: MW transmission test at end of each component




Location	Components	Transmitted power (kW)
Test condition: Gyrotron output = 28 GHz, 2 kW		
Default	Directional coupler	1.9
1	Default+mode converter	1.891
2	1+mode filter	1.886
3	2+ 90° bend	1.886
4	3+dc break	1.877



3.3 Superconducting magnet system: Design results

Two candidates considering domestic vendor technology



- Saddle type is the best but it difficult to make a winding by domestic supplier
- We've invented the **step-type hexapole** modified from racetrack and saddle coils




Racetrack type



Step type




3.3 Superconducting magnet system: Design results



3 Solenoid + 1 hexapole magnet (6 step-type coils)


- The axial field: ~ 3.6 T at injection, ~ 2.2 T at extraction.
- The minimum axial field (variable): $0.4 \sim 0.8$ T.
- The radial design field on the plasma chamber wall: 2.1 T

3.3 Superconducting magnet system: Design results



	SL1	SL2	SL3	Hexapole
Axial position of center (mm)	-250	+250	0	0
Inner diameter (mm)	442	442	442	207
Outer diameter (mm)	540.8	540.8	540.8	394.96
Depth (mm)	49.4	49.4	49.4	75.6
Width (mm)	252	128.8	145.6	53.2
Hexapole length (mm)	-	-	-	1066.4
Hexapole inner radius (mm)	-	-	-	30
Conductor size (mm)	0.95 x 1.4	0.95 x 1.4	0.95 x 1.4	0.95 x 1.4
Cu/NbTi ratio	4.9	4.9	4.9	2.32
Turns/coil	9360	4784	5408	2304
Wire lengths/coil (km)	14.5	7.4	8.4	4.9
Current (A)	197	198	197	263
B_{max} (T)	5.98	5.35	4.72	7.65
Inductance (H)	39	13.5	16.5	23

3.3 Superconducting magnet system: 4 step reinforcement for superconducting magnet



- **6 GFRP supports** to guide the edge of step-type coils

- **6 Titanium wedges insertion** between step-type coils in hexapole magnet





- **Final assembly**









- **2 Metal (stainless-steel) clampings** to squeeze the return-end section in hexapole magnet
- **3 Stainless-steel tension wiring** on the outer-most layers of solenoid magnet

3.3 Superconducting magnet system: Structural improvement after reinforcement/support

Before reinforcement/support



After reinforcement/support



Return-end section

Straight section


Return-end section

Straight section

3.3 Superconducting magnet system: Initial performance test of superconducting magnet



Magnet test at open-type cryostat

- Separate coil performance was checked before final assembly
- Vertical cryostat(open type) was prepared for convenient test
- Magnet status, temperature, magnetic field were observed



3.3 Superconducting magnet system: Separate performance of superconducting magnet

The separate coil performance




- Solenoid coils satisfied the requirements of operating current.
- Hexapole have not reached the final values yet (83% of I_{op}).
- Further training has not carried out due to the shortage of LHe supply

3.3 Superconducting magnet system: SC magnet assembly at LHe recondensed cryostat

Cryostat

- 4 GM cryocoolers
- 4 LHe recondenser
- HTS current lead:
300 A (6 ea), 500 A (2ea)
- temperature monitor: 7
cernox sensors
- level monitor: 2 LHe level
sensors
- Several normal
conducting joints (18ea @SC
magnet) ●



3.3 Superconducting magnet system: Cooling margin of LHe recondensed cryostat

Specification		Unit	Value
Weight of Cryostat (magnetic shield)		kg	<1500
Vacuum Rate of Cryostat		torr	<~9x10 ⁻⁵
He Leak Rate of Cryostat		cc.atm/sec	<~9x10 ⁻⁹
Volume of LHe Vessel		Litter	<950
Cooler Capacity (4ea)	First Stage (50K)	Watt	200
	Second Stage (4.2K)	Watt	6
Number of 4.2K Cooler Port		ea	4
Number of HTS 500A Current Lead		pairs	4


Heat estimation @ first stage	
Shield Radiation	35
Current Lead (4pair) Conduction	80
Access Port Conduction	5
Access Port Radiation	3
Support (8ea) Conduction	3
Total Heat Loss of Thermal Shield	< 126 W
Cooling capacity	200 W
Margin	>74 W

Heat estimation @ second stage	
LHe Vessel Radiation	0.3
HTS Current Lead (4pair) Conduction	0.5
Access Port Conduction	0.4
Access Port Radiation	0.2
Support (8ea) Conduction	0.2
X-ray Heating	3 (assuming)
Total Heat at Loss of LHe Vessel	< 4.6 W
Cooling capacity	6 W
Margin	> 1.4 W

- Cooling margin at the first stage > 74 Watt
- Cooling margin at the second stage > 1.4 Watt (assuming 3 Watt x-ray heating)

3.3 Superconducting magnet system:

The comparison of magnet field between design and experimental values



3.4 Remote control program

Gas Main : (CO₂) 0.000m FOR OUT ERR OPEN CLOSE SETUP	Gas Sub : (Xe) 0.000m FOR OUT ERR OPEN CLOSE SETUP	Extraction Position(C) 0.000m FOR OUT ERR OUT IN SETUP	Bias Disk(M) 0.000m FOR OUT ERR OUT IN SETUP	Oven 0.000m FOR OUT ERR OUT IN SETUP
--	---	---	---	---

28GHz Gyrotron ON RF ON LOWER STATE EBMON(KV) 0.00KV IBMON(A) 0.00A EFMON(V) 0.00V MAGIMON(A) 0.00A Set RF Power 0.000kW Power FWD 0.00kW Power REV 0.000kW 	Extraction PS ON Measured Voltage 0.39kV Measured Current -0.18mA Set Voltage 0kV ON OFF SETUP	Bias PS ON Measured Voltage 0kV Measured Current 0mA Set Voltage 0kV ON OFF SETUP	Accel/Decel PS ON Measured Voltage -0.52kV Measured Current -0.18mA Set Voltage 0kV ON OFF SETUP	Oven PS ON Measured Voltage 0kV Measured Current 0mA Set Voltage 0kV ON OFF SETUP
---	---	--	---	--

SC Magnet No Current Change RUN ALARM SET(A) CURRENT(A) VOLTAGE(V) CC CV SL1 0.0A 0.0A 0.0V SL2 0.0A 0.0A 0.0V SL3 0.0A 0.0A 0.0V SL4 0.0A 0.0A 0.0V Ramp Stage 0Point Current Stage 0Point EXCITATION HOLD ZERO RESET ALARM	LEBT Magnet Qu1 Qu2 St1 St2 St3 St4 PS-A PS-B PS-C BM CV CC SWP EN SWP ON ERROR Voltage PV 0.000V Current PV 0.000A Voltage SV 0.000V Current SV 0.000A Set Current 0.000A ON OFF SETUP	Faraday Cup SETUP Gain 21 Sign Positive Negative Measured Data 22 BM Current 0 IN OUT GRAPH	Slit & Wire Scanner Slit Upper Position 20.871mm Slit Lower Position 20.871mm Slit Left Position 20.871mm Slit Right Position 20.871mm Wire Scanner Position 20.871mm Emittance 20.871
--	--	--	---

Vacuum CG1 IG1 CG2 IG2 ECR 8.66E02Torr 1.10E03Torr 6.59E02Torr 1.10E03Torr LEBT 3.59E00Torr 1.10E03Torr 7.73E00Torr 1.10E03Torr Pump/Valve Control AUTO Alarm Reset 24H Graph MANUAL Buzzer Stop 72H Graph Auto Manual Alarm	ALARM Capture Screen
--	----------------------

VI. The first plasma ignition

Setup for plasma ignition




VI. The first plasma ignition

Current status of ECRIS for first plasma ignition as of August 2014


Gas type	Ready	Ar
SC magnet	Ready (limited)	Solenoid was qualified
		HP was limited yet (83% of design)
Plasma chamber	Ready	$\sim 10^{-8}$ Torr (Before gas injection)
		$\sim 10^{-7}$ Torr (After gas injection)
Microwave	Ready	28 GHz, below 1 kW

※ More training of superconducting magnet (HP magnet) will be required


VI. The first plasma ignition



- ◆ The first plasma ignition was performed on 14 August, 2014
- ◆ 28 GHz ECR ion source developed at KBSI has been started to operate.



The magnet value of plasma ignition (preliminary)




Location	Design values	Plasma ignition condition
B_{inj} (T)	3.65	2.3
B_{min} (T)	variable	0.48
B_{ext} (T)	2.24	2.02
B_r (T)	2.2	1.3

Black lines: Design values, Blue lines: Plasma ignition condition

- ⊗ Training of superconducting magnet has been much delayed due to LHe shock.
- ⊗ Solenoids performance is now limited by yet-trained Hexapole-magnet.
- ⊗ More training of superconducting magnet (HP-magnet) is planned.

V. Future plan

- **More training of superconducting magnet (HP)**
 - **Operational condition establishment of ECR ion source**
 - **Beam extraction from ECR ion source (Sep., 2014)**
 - **Beam diagnosis under LEBT operation (Sep., 2014)**
 - **Fabrication of RFQ LINAC (Dec., 2014)**
 - **Engineering design of Drift Tube LINAC**
 - **Design of neutron facility**
- 

Thank you for your attention.

