### **Cornell SRF Overview**



### - focusing on ERL fraction of SRF group -

### Georg Hoffstaetter Cornell Physics Dept. / CLASSE

- 1) ERL Injector R&D, prototyping, and operation
- 2) ERL main linac R&D, prototyping, and technology transfer
- 3) Low Loss Research (For CW linacs, mostly ERL and Project-X)
- 4) High Voltage Research (Mostly for ILC)
- 5) New SRF materials with potential for high voltage and low loss.
- 6) Fundamental SRF properties theory and experiment
- 7) Storage ring SRF cavities operation and technology transfer
- 8) SRF related Beam Research:
  - a) Dark current in SRF linacs
  - b) X-ray background outside SRF linacs
  - c) Cavity focusing and ERL linac optics

Cornell University









### Cornell's SRF R&D facilities -2-

• Strong research team:

3Prof, 4PhD, 7Eng/Tech, 4Grads

- RF measurement lab
- Clean room
- Chemical handling



## CLASSE

### Cornell's SRF R&D facilities -3-

- Precision coordinate measurement
- Scanning electron microscope, Auger analysis, SIMS
- Advanced m-Kelvin thermometry
- OST quench locator
- Questar optical inspection
- Helium recovery system
- Large 1450C high-vacuum furnaces











NSF Review of ERL and CHESS, Cornell 10-28-2011



### **Cavity Production at Newman Lab**





## CLASSE

### **Pushing the Envelope in Many Ways**



**SRF cavity:** design for high beam current



**RF input coupler:** design for high power



HOM damper: design for strong HOM suppression

Frequency tuner: stabilize cavity length on nm scale

Module design: support high cryo loads and provide excellent alignment





Georg.Hoffstaetter@Cornell.edu



NSF Review of Eks. and CHESS, Cornell 10-28-2011

### **ERL Injector Module Assembly** in Cornell's SRF group





### ERL Injector Module Assembly in Cornell's SRF group





All done at CLASSE - No company could do this today !



### ERL Injector Module Assembly in Cornell's SRF group





All done at CLASSE - No company could do this today !



### ERL Injector Module Assembly in Cornell's SRF group





All done at CLASSE - No company could do this today !



### **Rebuilding and Improving the ERL Injector**





### **Module Assembly at Newman Lab**







### Localization and elimination of magnetic error







### SRF ERL Injector Cryomodule Re-Work (fall 2009 – spring 2010)



The first run period (July 2008 – August 2009) revealed lower than expected cavity  $Q_0$  and HOM load absorber tiles charging -> beam steering.



### **Does the injector work?**



- All components work well (after some initial hitches)
- Successfully accelerated beam currents of 25 mA
  - ✓ Transferred > 125 kW of RF power to the beam
  - ✓ Performance projected indicates that operation at >100 mA is possible



### **Milestones at Cornell's injector**



Peak DC-power supply voltage: 750kV Peak DC-gun voltage: 440kV (of 500kV required with beam)

Peak DC-beam current: 25mA (up to brilliance mode spec) Peak bunched-beam current: 25mA with GaAs / 20mA with CsK<sub>2</sub>Sb for 8h

Peak charge per bunch: 200pC (more than needed)

Typical bunch length: 2ps (up to spec)

Smallest normalized thermal emittance: 0.25 mm mrad/mm radius Smallest normalized emittance after injector at 80pC: 0.8 mm mrad For this gun, 0.5 mm mrad is theoretical limit ! This bunch in a 5GeV ERL would produce X-rays brighter than any ring today.

Largest SRF-injector cavity Q0: 1.e10 (of 2.e10 required) Largest injector-coupler power: 60kW (of 100kW required) Largest SRF-cavity voltage: 13MV/m (up to spec)

Cornell University

### **HOM Damping Workshop at Cornell**



Cornell University International Workshop on Higher-Order-Mode Damping in Superconducting RF Cavities

#### October 11–13, 2010 701 Clark Hall, Cornell University

The workshop will be held on the beautiful upstate New York Cornell University campus. It will address different methods of damping Higher-Order-Modes in superconducting RF cavities.



Specific subjects of interest are: • RF absorbing materials • Antenna HOM absorbers • Beampipe HOM absorbers • Waveguide HOM absorbers • HOM simulation tools • HOM measurement methods



For information or to register, visit: www.lepp.cornell.edu/Events/HOM10

- ~40 participants
- From 15 different labs/ universities from Asia, Europe and U.S.







### **Cornell's HOM Beamline Absorber**

Extensive research program to find absorber materials which

- are effective at 80 K
- and\_absorb over the required wide frequency range (1 GHz to >100 GHz)
- Be vacuum compatible and radiation hard
  - Ferrites
  - Graphite loaded SiC
  - Carbon-nanotube loaded ceramics





#### Spherical carbon inclusions vs. CNTs

### **HOM Results from the Injector SRF Module**



Yes, very well...

- HOM spectra measurements confirm excellent damping with typical Qs of a few 1000
- ✓ Operated injector SRF module with beam currents of 25 mA
  - Measured ΔT very small. → operation at
    >100 mA feasible (>10\* previous record!)



<sup>m</sup> 19:00:00 20:00:00 21:00:00 22:00:00 time







### **ERL Phase1B progress for SRF**

- Engineering design of 7-cell cavity, dumbbells ready, v-test of 1<sup>st</sup> cavity in Sept.
- Engineering design of 8 HOM absorber, parts ready for brazing
- Concept design and quote for SC quadrupole/corrector/BPM package
- Horizontal test to evaluate midfield Q in early 2012
- Horizontal test with beam for HOM measurements in 2013
  - Incorporate a full-circumference heat sink to allow >500W dissipation @ 80K
  - New beamline flanges, variations of the "Zero Impedance Flange"



### Phase 1B ERL protoyping: 2010-2014 Technology development for ERLs (anywhere)



- a) Continued Gun R&D
- b) High-brightness beam physics
- d) ERL Undulators
- e) Other X-ray beamline R&D



### ERL cavity fabrication and measurement





Georg.Hoffstaetter@Cornell.edu

### Second Sound Quench Location





Georg.Hoffstaetter@Cornell.edu

NSF Review of ERL and CHESS, Cornell 10-28-2011

## **From Specs to Finished Cavity** ERL operation with >100 mA, minimize cryogenic wall losses, minimize cavity microphonics (modulation of cavity frequency by mechanical vibrations) **RF** design Mechanical design **Cavity fabrication**



Cornell University

### upler Kick Studies in Cornell **RF** Optimization Cell shape optimization • ~20 free parameters • 1000's of eigenmodes • Impact of cell shape errors -> Supports beam current >400 mA (previous record: 10 mA) 3BU Parameter [<u>0</u>/cm<sup>2</sup>/GHz] $10^{0}$ Dipole mode damping calculated up to 10 GHz with realistic RF absorbers Worst mode limits beam current! 2 8 9 10 Frequency [GHz] LENCEPHOTOLIBRARY Georg.Hoffstaetter@Cornell.edu NSF Review of ERL and CHESS, Cornell 10-28-2011

### **Mechanical Design**





### Next Steps: 2011 – 2014





- Test of prototype cavity without and with beam (up to 100 mA)
- Build and test full main linac SRF cryomodule





### Intern. CW Cryomodule Collaboration ( Host lab: Daresbury





- Collaboration formulated in early 2005 to design and fabricate new CW cryomodule and validate with beam
- Dimensioned to fit on the ALICE ERL facility at Daresbury:
  - Same cryomodule footprint
  - Same cryo/RF interconnects
  - 'Plug Compatible' with existing cryomodule











Georg.Hoffstaetter@Cornell.edu

NSF Review of ERL and CHESS, Cornell 10-28-2011

Parameter	Target
Frequency (GHz)	1.3
Cryomodule Length	3.6m
R/Q (Ω)	762
E <sub>acc</sub> (MV/m)	>20
E <sub>pk</sub> /E <sub>acc</sub>	2.23
H <sub>pk</sub> /E <sub>acc</sub>	46.9
CM Energy Gain	>32MeV
Q <sub>o</sub>	>1010
Q <sub>ext</sub>	4x10 <sup>6</sup> - 10 <sup>8</sup>

### See poster: TUPO013



### Assembly preparations at Daresbury for the intern. CW cryomodule



DESY superstructures modified, changed to optimised end groups by Cornell



Eacc (MV/m)

Modified Saclay-II tuner with wider aperture and low voltage piezo cartridges.





Modified Cornell ERL injector coupler with a shortened cold section.





Cold couplers installed  $\Rightarrow$  awaiting HOM absorbers. Cryomodule to be ready later this year.





Cryomodule Cornell University

### **Collaborations**



1) MOU with KEK (Tsukuba) who have adopted many of our parameters and designs for their hard x-ray ERL plans – includes SRF collaboration

2) MOU with HMZ (Berlin) on the development of LLRF control for ERLs and exchange of ERL SRF-injector designs.

3) Daresbury (UK): International SRF ERL cryomodule collaboration.

- 4) LBNL: Upcoming collaboration meeting on SRF for the NGLS soft x-ray FEL
- 5) JLAB: Joint measurements and exchange of students (SRF control and BBU)
- 6) TRIUMF (Vancouver): Exchange of ERL SRF hardware and injector designs.







# END



38