

Superconducting RF Activities in IHEP

Jiyuan Zhai

IHEP, China



ERL2011, KEK, Oct. 17, 2011

Outline

- BEPCII 500 MHz SCRF Progress
- ILC 1.3 GHz SCRF Progress
- SCRF Infrastructures
- ADS and ERL SCRF Design Study

Outline


- BEPCII 500 MHz SCRF Progress
- ILC/XFEL 1.3 GHz SCRF Progress
- SCRF Infrastructures
- ADS and ERL SCRF Design Study




help from T. Furuya etc. of KEK

IHEP BEPCII 500 MHz SCRF

- Spare module for BEPCII (2008-2011)
- R&D for future SR light source
- Cavity vertical test: Jan.-Jul., 2011
- **Horizontal test: Oct. 13-15, 2011**
 - $V_c = 2.05 \text{ MV}, Q_0 = 7.7 \times 10^8$
 - $V_c = 2.16 \text{ MV}, Q_0 = 4.1 \times 10^8$




500 MHz Cavity



Spinning




BCP & HPR




DESIGN VALUE
($V_c = 1.5 \text{ MV}$, $\sigma_0 = 5 \times 10^8 \text{ nm}$)

500 MHz Input Coupler






High Power Conditioning:

**180 kW CW in IHEP test stand
(limited by klystron power)**
420 kW CW in KEK test stand



HOM Absorber



Ni-Zn Ferrite Powder XRD




High Power Test > 4.4 kW at 500 MHz

Cryostat and Assembly



Outline

- BEPCII 500 MHz SCRF Progress
- **ILC 1.3 GHz SCRF Progress**
- SCRF Infrastructures
- ADS and ERL SCRF Design Study




IHEP ILC SCRF R&D Program

- IHEP Innovation Project (2009-2012)
- Primary goals of the program:
 1. key components prototyping (1.3 GHz cavity, input coupler, tuner, LLRF)
 2. SRF infrastructure construction and commissioning
 3. cryomodule integration with one 9-cell cavity (assembly and alignment)
 4. cryomodule test (20-31.5 MV/m, $Q_0 > 8E9$, pulsed 5 Hz, 1 ms flat-top, 1% amplitude and 1 deg phase variation)
 5. horizontal test stand or booster (capture cryomodule) for future SRF test facility

Key Components Prototypes



9-cell cavity (IHEP-01)
Large grain low loss shape



Tuner
KEK slide jack type



Input coupler
KEK STF type




LLRF



Cryomodule for Euro-XFEL
PXFEL1, 58 more ordered

IHEP-01 9-cell Cavity

- Low loss shape, without end groups
- fabricated in Beijing with Ningxia OTIC large grain Nb
- processed and RF tuned with SCRF infrastructures in IHEP
- final processing and vertical test in KEK (VT1) and JLAB (VT2)







1st Pass Processing

VT1 at KEK
T-mapping




VT2 at JLAB
OST, T-sensor


IHEP-01 Vertical Test Results




IHEP-02 9-cell Cavity with Helium Vessel



IHEP-03 for STF2 Linac




- TESLA-like shape 9-cell fine grain cavity in collaboration with KEK
- small Lorentz detuning
- might install to KEK STF2 for beam test





1.3 GHz Input Coupler


- Two double-choke-window input couplers
 - In-house made (IHEP workshop)
 - TiN coating on ceramics
 - finished fabrication of two couplers
 - high power test at KEK STF: November 2011



Refer to E. Kako (KEK)



Welded Coupler Parts



Warm and Cold Window



Door knob



Warm outer part







Warm inner part



Cold outer and inner parts



Tuner and LLRF

- Home-made slide jack tuner
- Performance test with MHI-04 from KEK
 - Tuner stroke
 - Piezo
 - Stability
- Cold test planned
- Motor inside cryomodule




Refer to S. Noguchi (KEK)

LLRF Performance @ RT



Frequency stability	$\pm 1 \text{ kHz}$ (room temperature)
Amplitude stability	$\pm 0.05 \%$ (peak to peak)
Phase stability	$\pm 0.035^\circ$ (peak to peak)
Response time	70 μs
Dynamic range	20 dB

Cryomodule for the 9-cell Cavity



- Based on PXFEL1 success and XFEL cryomodule mass production
 - Design finished, fabricate and assemble in 2011-2012
 - Horizontal test with IHEP's new cryogenic system

Outline

- BEPCII 500 MHz SCRF Progress
- ILC 1.3 GHz SCRF Progress
- **SCRF Infrastructures**
- ADS and ERL SCRF Design Study

SRF Infrastructures



CBP



BCP




UPW & HPR




Ultrasonic



RF Pretuning



Clean Room



Vertical Test Stand



SRF Infrastructures (cont.)



Cavity RF Lab




RF Measurement



Inspection Camera



LLRF Lab



Vertical test Dewar and heat
exchanger (in fabrication)


Planned Infrastructures

- EBW machine and cavity fabrication plant
- EP facility, T-mapping
- Dedicated 2K cryogenic system (for ADS, ERL & ILC)
 - cavity vertical test
 - cavity package & module horizontal test
 - test facility operation
- New large SCRF labs outside IHEP campus
 - Huai Rou (future site for *Beijing Advanced Photon Complex*)
 - Erdos (future site for *China ADS*)

Outline


- BEPCII 500 MHz SCRF Progress
- ILC/XFEL 1.3 GHz SCRF Progress
- SCRF Infrastructures
- **ADS and ERL SCRF Design Study**

Layout of the China ADS Linac




- 3 types of spoke cavities and 2 types of elliptical cavities are needed for China ADS Linac, and the spoke cavity for 3~10 MeV injector is most challenging.
- The collaborations with PKU&HIT were fixed, and collaborations with FNAL/ANL/MSU etc. are expected.

Spoke 0.12 RF Design



Leav	f	G	R/Q@ β_{opt}	Ep/Eacc	Bp/Eacc	Ttran
170mm	325.0MHz	53Ω	150Ω	3.19	4.66mT/MV/m	0.77

Spoke012 Mechanical Properties




	Without ribs	With ribs
Beam pipe free	4.47 mm/bar -13.7 MHz/bar Von stress=212 MPa $\Delta f/\Delta p = -18 \text{ kHz/torr}$	0.423 mm/bar -1.04 MHz/bar Von stress=56 MPa $\Delta f/\Delta p = -1.4 \text{ kHz/torr}$
Beam pipe fixed	0.359 mm/bar -402.29 kHz/bar Von stress=440 MPa $\Delta f/\Delta p = -530 \text{ Hz/torr}$	0.08 mm/bar +6.5 kHz/bar Von stress=65 MPa $\Delta f/\Delta p = -8.5 \text{ Hz/torr}$
Tuning sensitivity	0.577 mm/100 kgf 761.3 kHz/100 kgf 1.32 MHz/mm	0.052 mm/100kgf 68.6 kHz/100kgf 1.32 MHz/mm
Lorentz detuning	-25.83 Hz/(MV/m) ²	-3.2 Hz/(MV/m) ²

Elliptical Cavities for ADS



$\beta=0.45$, 1.3 GHz scaled cavity




$\beta=0.45$, 650 MHz cavity half cells

New beta = 0.82 & 0.63
650 MHz 5-cell cavity prototyping
in 2012-2015


Beijing Advanced Photon Complex

1st Phase: Small emittance synchrotron light source (2015-2020 ?)

2nd Phase : BX-ERL-FEL



Layout of the ERL Test Facility at IHEP



Compact TF-- 35 MeV-10 mA

- DC- and 5 MeV injector ([2 x 2-cell CW SC cavity](#))
- L-band CW SC Linac: $E = 15\text{--}20 \text{ MV/m}$ 、 35 MeV $\sim 10 \text{ mA}$ ([2 x 7-cell CW SC cavity](#))
- ERL ring: 2 TBA arcs , 2 strait section
- ERL-THz beam lines (from CSR or oscillator)

J.Q. Wang's talk
Tue. p.m. WG2

Injector Cryomodule Parameters

Energy gain	5 MeV
RF frequency	1.3 GHz
Number of 2-cell cavities	2
Effective length of 2-cell cavity	23 cm
2-cell cavity R / Q	214Ω
#1 cavity voltage	1.5 MV (1~3 MV)
#1 cavity gradient	6.5 MV / m
#1 cavity total Q_L	7×10^5
#1 cavity Q_L of each input coupler	1.4×10^6
#1 cavity beam phase	-15° ~ -30°
#1 cavity beam power	15 kW
#1 cavity power of each input coupler	7.5 kW (CW)
#2 cavity voltage	3.5 MV (1~3 MV)
#2 cavity gradient	15.2 MV / m
#2 cavity total Q_L	1.6×10^6

Injector Cryomodule Parameters (Cont.)

#2 cavity Q_L of each input coupler	3.2×10^6
#2 cavity beam phase	-10°
#2 cavity beam power	35 kW
#2 cavity power of each input coupler	17.5 kW (CW)
Number of input couplers per cavity	2
Number of input couplers	4
RF power of the input coupler	20 kW (CW)
Input coupler Q_e	2.3×10^6
Variable coupler Q_e range	$10^6 \sim 10^7$
Number of HOM absorbers	3
RF power of a HOM absorber	20 W
Amplitude stability	0.1 %
Phase stability	0.1 °
Max beam current	10 mA
2 K / 5 K / 80 K heat load	12 W / 14 W / 154 W
Total Length	2.4 m

Main Linac Cryomodule Parameters


Mode	A	B
Accelerating beam current		10 mA
Accelerating beam phase	-10°	0°
Decelerating beam current	9.7 mA	9.98 mA
Decelerating beam phase	165°	179.5°
Detune	-26.8 Hz	~ 0 Hz
Beam loss	3 %	0.02 %
Bunch charge		77 pC
Bunch repetition frequency		130 MHz
Bunch spacing		7.7 ns
Number of 7-cell cavities		2
7-cell cavity voltage		15 MV
7-cell cavity Q_0		1×10^{10}
7-cell cavity R / Q		800 Ω
Q_e		2×10^7
Band width		65 Hz

Main Linac Cryomodule Parameters (cont.)


Microphonics (p-p)	50 Hz	10 Hz
RF power	16.3 kW	4 kW
RF Power (30 % abundance)	21.19 kW	5 kW
Number of input couplers per cavity		1
Number of input couplers		2
RF Power of input couplers		20 kW (CW)
Variable coupler Q_e range		$2 \times 10^6 \sim 2 \times 10^7$
Number of HOM absorbers		3
RF Power of a HOM absorber		20 W
Amplitude / phase stability		0.01 % / 0.01 °
2 K/ 5 K / 80 K heat load		60 W / 20 W / 180 W
Total length		4.8 m

-10 deg was assumed for chicane compressor, now the bunch compression will be performed by TBA1, so the bunch phase should be about 10 deg.

Injector Booster Cavity



Type of accelerating structure	Standing wave
Accelerating mode	TM010, π mode
Fundamental frequency	1301.000 MHz
Design gradient	15 MV / m
Quality factor	1×10^{10}
Active length	0.2292 m
Number of cells	2
Geometry factor (G)	274.5 Ω
R / Q	214.2 Ω
$G \times R / Q$	58776 Ω^2
$E_{\text{peak}} / E_{\text{acc}}$	2.02
$B_{\text{peak}} / E_{\text{acc}}$	4.2 mT / (MV / m)




Main Linac Cavity

7-cell , iris 70 mm, based on TESLA cavity

refer to Cornell “HOM-robust” shape

end cell: similar to the 2-cell cavity

CBP (with EP? *C. Cooper SRF2011*) and Large Grain (BCP only or EP, *R. Geng, S. Aderhold SRF2011*) seem to **increase the Q value at medium gradient (~ 20 MV/m) 1~2 times higher**



	$R/Q \cdot G$	E_{pk}/E_{acc}	Wall Angle	Iris Radius	Eq. Horiz.	Eq. Vert.	Iris Horiz.	Iris Vert.
Baseline	15576 Ω	2.00	85°	3,500	4.399	3.506	1.253	2.095
New Design	14837 Ω	2.06	77°	3,598	4.135	3.557	1.235	2.114

$$\left(\frac{R}{Q}\right) Q < 5000 \quad [\Omega]$$

$$\left(\frac{R_t}{Q}\right) \frac{Q}{f} < 2.8 \times 10^5 \quad \left[\frac{\Omega}{\text{cm}^2\text{GHz}}\right]$$

$$\left(\frac{R_q}{Q}\right) \frac{Q}{f} < 8 \times 10^6 \quad \left[\frac{\Omega}{\text{cm}^4\text{GHz}}\right]$$

f_0 1.3 GHz

V_c 15 MV

L_{eff} 0.8 m

E_{acc} 18.8 MV / m



Q_0 10^{10}

R / Q 800 Ω

Courtesy of Cornell

ERL Input Coupler

- 20 kW CW input coupler for main linac
- same with main linac or 200 kW CW input coupler for injector, if consider 100 mA (if initial power source for the injector is 30 kW, the 200 kW input coupler should be variable)
- Refer to STF-II and KEK ERL Variable Coupler, ERL injector coupler
- IHEP made some of the RF simulation



Courtesy of KEK

RF Power for Cryomodules

	2-cell #1	2-cell #2	7-cell #1	7-cell #2
Cavity Voltage	1.5 / 2.5 MV	2.5 / 3.5 MV	15 MV	15 MV
Q_L (total)	7×10^5 / 1.2×10^6	1.2×10^6 / 1.6×10^6	2×10^7	2×10^7
Bunch phase	$-15^\circ \sim -30^\circ$ / 0°	0° / -10°	0° , 180° / -10° , 165°	0° , 180° / -10° , 165°
Power needed	15 kW / 25 kW	25 kW / 35 kW	20 kW	20 kW
Output power	20 kW / 30 kW	30 kW / 45 kW	30 kW	30 kW
Power Source	30 kW	45 kW or 30 kW	30 kW	30 kW


RF Power Source

项目	单位	Buncher	Inj-1	Inj-2	ML-1	ML-2
结构		NC	SC	SC	SC	SC
加速梯度	MV/m	0.14	15	15	15	15
Q_e			8×10^5	2×10^6	2×10^7	2×10^7
束流相位	degree	-90	-15 to -30	-10	0	0
所需功率	kW	4.5	25	25	16.3	16.3
输出功率	kW	6.2	35	35	35	35
功率源类型		IOT	IOT	IOT	IOT	IOT

LLRF

Name	2-cell #1	2-cell #2	7-cell #1	7-cell #2
f_0 (GHz)	1.3	1.3	1.3	1.3
Bandwidth(Hz)	--	--	65	65
V_c (MV)	3	4	15	15
Q_L	$\sim 1 \times 10^6$	$\sim 1 \times 10^6$	$\sim 1 \times 10^7$	$\sim 1 \times 10^7$
r/Q_0 (Ω)	214	214	800	800
I_b (mA)	10	10	10	10
$\sigma A/A$ (%)	0.1	0.1	0.01	0.01
$\sigma\theta/\theta$ ($^\circ$)	0.1	0.1	0.01	0.01

LLRF



Injector CM Heat Load

	Static	2-cell cavity	Input coupler	HOM damper	Total
		$R/Q = 214 \Omega$ $\mathcal{Q}_0 = 1 \times 10^{10}$ $V_c = 2.5 \text{ MV}$ CW	CW 12.5 kW SW	Ferrite (bunch length 2 ps)	
Reference	KEK cERL injector	IHEP ERL	KEK ERL injector coupler	Cornell	
2K	2 W	3 W	1 W	0	12 W
5K	10 W	0	1 W	0	14 W
80K	80 W	0	8 W	14 W	154 W
No.		2	4	3	

Main Linac CM Heat Load

	Static	7-cell cavity	Input coupler	HOM damper	Total
		$R/Q = 800 \Omega$ $Q_0 = 1 \times 10^{10}$ $V_c = 15 \text{ MV}$ CW	CW 20 kW SW	Ferrite (bunch length 2 ps)	
Reference	KEK cERL	Cornell	KEK ERL Linac Coupler	Cornell	
2K	1 W	28 W	1 W	0	60 W
5K	14 W	0	3 W	0	20 W
80K	60 W	0	30 W	20 W	180 W
No.		2	2	3	

Total Heat Load

	2 K	4.5 K	80 K	4.5 K
Two 2-cell (W)	12	14	154	82
Two 7-cell (W)	60	20	180	329
4.5 K valve box (W)		30		30
4.5 K transfer line 100 m, 0.5W / m (W)		50		50
Two 2 K cold box (W)		60		60
2 K transfer line 30 m, 0.5 W / m		15		75
Sum	85	174	334	626 W

IHEP ERL TF SCRF Plan

- 2012-2013:** 2-cell and 7-cell cavity, input coupler and HOM absorber prototyping
- 2013-2014:** **injector cryomodule** construction and commissioning with beam (at IHEP campus)
- 2014-2015:** **main linac cryomodule** construction and commissioning with beam (may move to Huai Rou)

Summary

- *IHEP SCRF R&D progressing for many projects*
 - **BEPCII**: spare cavity module meet specs last weekend
 - **ILC**: 1.3 GHz short cryomodule integrated next year
 - **light source** (storage ring, **ERL**), **China ADS, CSNS**
- *Infrastructures established and will expand*
- *ERL SCRF R&D based on the above activities*
 - CDR finished
 - key components prototyping in 2012-2015



Acknowledgement

We would like to thank the experts from
KEK, JLAB, FNAL, ANL & DESY as well as the ILC GDE
for their kindest cooperation and help.


Thank you!

Single Cell Cavities

- 3 Ningxia large grain cavities, made by KEK, in 2007: **48 MV/m (CBP + EP)**
- 2 Ningxia large grain cavities, fabricated and processed in IHEP, tested at KEK in 2008 **40 MV/m (CBP + BCP)**
- 1 fine grain cavity for reference study




Does Centrifugal Barrel Polishing Affect Q-Slope ?



Recent high Q results on Tesla-Type cavities. Do grain boundaries have a negative effect on Q(Low, Mid, and High)?

Comparison of Q0: LG \leftrightarrow FG



Details: R. L. Geng's
poster TUPP004g

Comparison of Q0: LG \leftrightarrow FG

