




Successful Result of the Commissioning on cERL in KEK

Shogo Sakanaka (KEK), on behalf of the cERL team



cERL Team



High Energy Accelerator Research Organization (KEK)

M. Adachi, S. Adachi, T. Akagi, M. Akemoto, D. Arakawa, S. Araki, S. Asaoka, K. Enami, K. Endo, S. Fukuda, T. Furuya, K. Haga, K. Hara, K. Harada, T. Honda, Y. Honda, H. Honma, T. Honma, K. Hosoyama, K. Hozumi, A. Ishii, X. Jin, E. Kako, Y. Kamiya, H. Katagiri, R. Kato, H. Kawata, Y. Kobayashi, Y. Kojima, Y. Kondou, T. Konomi, A. Kosuge, T. Kubo, T. Kume, T. Matsumoto, H. Matsumura, H. Matsushita, S. Michizono, T. Miura, T. Miyajima, H. Miyauchi, S. Nagahashi, H. Nakai, H. Nakajima, N. Nakamura, K. Nakanishi, K. Nakao, K. Nigorikawa, T. Nogami, S. Noguchi [on leave], S. Nozawa, T. Obina, T. Ozaki, F. Qiu, H. Sagehashi, H. Sakai, S. Sakanaka, S. Sasaki, K. Satoh, M. Satoh, Y. Seimiya, T. Shidara, M. Shimada, K. Shinoe, T. Shioya, T. Shishido, M. Tadano, T. Tahara, T. Takahashi, R. Takai, H. Takaki, O. Tanaka, T. Takenaka, Y. Tanimoto, N. Terunuma, M. Tobiyama, K. Tsuchiya, T. Uchiyama, A. Ueda, K. Umemori, J. Urakawa, K. Watanabe, M. Yamamoto, N. Yamamoto, Y. Yamamoto, Y. Yano, M. Yoshida



Japan Atomic Energy Agency (JAEA)

R. Hajima, S. Matsuba [on leave], M. Mori, R. Nagai, N. Nishimori, M. Sawamura, T. Shizuma



Hiroshima University

M. Kuriki




The Graduate University for Advanced Studies (Sokendai)

E. Cenni [on leave]

1. Introduction

Future Plan: ERL Light Source Project at KEK



Normalized emittance	0.1 - 1 mm-mrad
Beam current	10 - 100 mA
Bunch charge	7.7 - 77 pC
RF frequency	1.3 GHz

3 GeV ERL

- Diffraction-limited X-ray source
- Ultra-short-pulse light source
- Driver for XFEL-O (2nd stage)

demonstrate




The Compact ERL

- Injector (low ε , high I_0)
- Main linac (CW, ~ 15 MV/m)
- Beam dynamics
- Beam losses

The Compact ERL (cERL)

The cERL contains all important technologies.



Parameters of the cERL

	Design	In operation
Beam energy E	35 MeV	20 MeV
Injector energy E_{inj}	5 MeV	2.9 - 6 MeV
Gun high voltage	500 kV	390 kV
E_{acc} in main linac	15 MV/m	8.2 MV/m
Beam current	10 mA	80 μ A
Normalized emittance [mm·mrad]	0.1 @7.7 pC 1 @77 pC	See, page 21
Repetition frequency of bunches	1.3 GHz	1.3 GHz (usual) 162.5 MHz (for LCS)
RMS bunch length	1-3 ps (usual) ~ 100 fs (compress.)	1-3 ps (usual)
Max. heat load at 2K	80 W	80 - 100 W


©Rey.Hori/KEK

Circumference: ~ 90 m

Critical Components

Photocathode DC gun

- GaAs photocathode,
- Drive laser: 532 nm
- Conditioned up to 550 kV (at JAEA)
- In stable operation at 390 kV (at cERL)



Nishimori's talk
(Tuesday)


Injector Cryomodule

- Three 2-cell cavities
- Conditioned up to $E_{acc}=8$ MV/m (CW); limited by heating-up of HOM couplers
- In stable operation at $E_{acc}=3.2 - 7$ MV/m at cERL





Main-Linac Cryomodule

- Two 9-cell cavities
- Demonstrated $E_{acc}=13.5$ MV/m (CW)
- In stable operation at $E_{acc}=8.2$ MV/m at cERL; limited by field-emission




Sakai's talk
(Wednesday)

Beam Optics of cERL




Injector (gun → exit of main linac).



Recirculation loop (exit of main linac → beam dump).

Construction and Commissioning of cERL



 Construction
 Commissioning/Operation



ERL2015

2. Construction of Recirculation Loop

Construction of Recirculation Loop (Jul. - Nov. 2013)

Determine beam energy ($E = 20 \text{ MeV}$,
 $p_{\text{loop}}/p_{\text{inj}} = 6-7$) → determine the coordinates
of all magnets

Survey and marking beamline

Installation of girders and magnets

Alignment of magnets

Installation of vacuum chambers. Wiring

Survey of magnets

Cool-down and conditioning of SC cavities


Commissioning



Survey and marking (Jul. 2013)



Installation of girder (Jul. 2013)



Alignment (Sep. 2013)



Installation of vacuum chamber
(Sep.-Oct. 2013)



Conditioning
of main linac cavities (Nov. 2013)




Finished (Nov. 2013)

Precise Prediction of Path Length of the Loop


- Precise prediction and installation of path length is essential for energy recovery:

$$\omega C / (\beta c) = (2n+1)\pi \quad (C: \text{circumference})$$


- Optimum path length depends on:
 - speed (βc) of particles
 - heights in injection and dump chicanes (depends on $\rho_{\text{loop}}/\rho_{\text{inj}}$)
- Before the construction, we chose the nominal energy of $E=20$ MeV and $\rho_{\text{loop}}/\rho_{\text{inj}} = 6-7$
- Trajectory length in each bending magnet was precisely predicted based on 3D field analysis




Dependence of the optimum circumference on the beam energy



Precise prediction of trajectory-length in the bending magnet, which is based on OPERA-3D calculation.



Picture of the cERL



Photocathode DC gun

Injector diagnostic beamline

Main-linac cryomodule

Recirculation loop



Injector cryomodule

3. Commissioning of cERL

Time Structure of Beams


CW beam
(for high currents)

Burst beam
(for beam tuning)



Bunch charge: 7.7 pC \rightarrow average current: 10 mA

Initial conditions are determined by the gun-drive laser.



The First Transportation of Beams to the Dump (Feb. 6, 2014)

Beam energy (E)


- Injector: 2.9 MeV
- Recirculation loop: 19.9 MeV

Parameters

- Gun voltage: 390 kV Buncher: OFF
- Injector cavities: $E_{acc} = (3.3, 3.3, 3.1)$ MV/m
- Main-Linac cavities: $V_c = (8.57, 8.57)$ MV

Beam pulses (macropulse)

- peak current: $\sim 24 \mu\text{A}$
- macropulse width: $1.2 \mu\text{s}$
- repetition of bunches: 1.3 GHz
- repetition frequency: 5 Hz
- average beam current: $\sim 140 \text{ pA}$



MS14

MS17

MS19

Movable FC

MS26

MS27

MS29

MS1

MS11


MS3

Gun FC (faraday cup)

Dump FC

MS31 (dump line)

Beam profiles on screen monitors.



	BPM		CT
	Screen		DCCT

Procedure of Start-Up Tuning

(3) Main linac


- Adjust rf phases (on-crest)
- Steering beam to the centers of ML cavities (option)
- Adjust beam energy

(2) Merger and beam transport

- Steering to the centers of QMs
- Adjust beam energy at injector

(1) Injector

- Steering beam to the **centers of solenoids and QMs** (optionally, to the centers of cavities)
- Adjust **rf phases** (on crest)



(4) Arcs and south-straight sections


- Steering beam to the **centers of QMs**
- Optics matching (option) - describe later

(5) Beam tuning for ML section (second passage) and dump line

- Adjust **steering coils** of these QMs so that the **beam passes the ML cavities** and appears at the dump line
- Adjust **K-values** of these QMs finely to adjust the **beam profiles at the dump line**



(6) Path-length correction

- Correct the **path length** so that the beam momentum take a minimum at the dump line



Correction of Path Length for Optimum Energy Recovery

- Two measures for path-length correction were prepared
- Path length was corrected so that the beam momentum took a minimum at the dump line



Path-length control chicane

- Tuning range: ± 5 mm
- Large hysteresis
- Currently fixed



Orbit bump in the arc

- Tuning range: ± 10 mm/arc
- Routinely used

Determination of an optimum path length

Single-Kick Response Measurement

- Measured responses agreed with those calculated within a range of 20-30 m after the kick.
- Large differences in downstream locations suggested accumulation of gradient errors.



Measured (cross) and calculated (line) responses to single-kicks.


Sources of Magnetic-Field Errors

Ambient fields

Cold cathode gauges (shielded)




Leakage fields from neighboring magnets



Merger section


Magnetic fields from Super-KEKB (due to cable of main dipoles)



$B \sim 20\text{-}30 \text{ mG}$ (at cERL)

Remanent fields and hysteresis of quadrupoles

- Remanent fields in quadrupoles cause large gradient errors:
 $\Delta K/K \geq 10\text{-}20\%$
- Gradient errors also accumulate through daily operations




Measured hysteresis curve of a quadrupole (QMIM03).

Countermeasures
(under study)

- Standardized excitation
- Subtract/add offsets due to remanent fields (when we set K-values for operation)


Method of Optics Matching

T. Miyajima
IPAC'15





- Single quadrupole (Q5) is used to measure the **quadrupole-scan response** (information of ε , α , β)
- Adjust the upstream 4 QMs so that the response curve agrees with the design one.

Before the matching



After the matching



Locations of matching points (MP1 - MP7).

(Right) Results of quadrupole-scan measurements before and after the optics matching at a location “MP2”.


Emittance Measurements

Injector ($E = 6.1$ MeV)


Bunch charge	At injector
0.02 pC	0.17 mm·mrad
0.77 pC	≈ 0.3 mm·mrad
7.7 pC	0.5 - 0.8 mm·mrad

(normalized emittance: ϵ_n [mm·mrad] = $\beta\gamma\epsilon$)

Slit-scan method



Q-scan method



Recirculation loop
(at injector energy of $E = 2.9$ MeV)

$$\rho_{\text{loop}}/\rho_{\text{inj}} = 7$$

Bunch charge	At injector ($E=2.9$ MeV)	At recirculation loop ($E=19.9$ MeV)
0.02 pC	-	0.14 / 0.14
0.5 pC	-	0.32 / 0.28
7.7 pC	(2.5 / 2.9)	(5.8 / 4.6)

$$(\epsilon_{n,x} / \epsilon_{n,y})$$



For LCS experiment




Very preliminary (under study)


Tuning for low-emittance at high charges is under study

4. High-Current Operation and Other Important Topics



Beam Currents: Achievement and Prospect



Beam Current of 80 μA (CW) was Recirculated




Collimators were used to cut beam halo/tails



Beam collimator


COL4:

- at arc section
- $\eta = -1.28 \text{ m}$
- cut low-energy tails (not very effective)




COL3:

- at straight section
- $\eta = 0$
- cut halos (large β_y)



COL2:

- at merger
- $\eta = 0.23 \text{ m}$
- cut low-energy tails



Radiation and Beam Losses (at beam current of $\sim 80 \mu\text{A}$)


Unit: mSv/h

Radiation levels inside the accelerator room under two conditions:

Beam optics: LCS

Red: using collimators No. 2, 3, 4 (shown in the previous page), on April 2, 2015

Blue: using collimator No. 2 (right 2.0 mm, top 3.4 mm), on April 3, 2015



● Radiation monitors (Organge1-6), for interlock (PPS)

● Loss (radiation) monitors, ALOKA MAR-782, for interlock (MPS)




● Fast loss monitors, for fast interlock (MPS)



Demonstration of Energy Recovery ($I_0 = 30 \mu\text{A}$)


ERL operation

Cavities 1 and 2: acceleration (1st pass) and deceleration (2nd pass)




Non-ERL operation

Cavity 2: deceleration ($V_c=8.57 \text{ MV/cavity}$) Cavity 1: acceleration ($V_c=8.57 \text{ MV/cavity}$)




No beam loading

Energy recovery: 100-98.6%
(within accuracy of the measurement)




Beam loading (+ and -)





(Power lost in cavity) = $(P_{in} : \text{input power to cavity}) - (P_{ref} : \text{reflected power from cavity})$

Other Important Topics

Successful Production of X-ray From Laser Compton Scattering (LCS)





Development of the Second Photocathode DC Gun






Yamamoto's talk (Tuesday)

Achievement of High RF Stability Using Sophisticated Digital LLRF System




Non-destructive Beam Position Monitoring in Two-Beam Section



Obina's talk (Wednesday)

Statistics of Operation Time (per month)



Japanese Fiscal Year:
April - March

Japanese Fiscal Year

Summary and Outlook

- The Compact ERL was commissioned and is in stable operation.
- Learned many lessons from the commissioning.
- The photocathode DC gun and both (injector and ML) SC cavities are operating very stably.
- Achieved beam current of 80 μA .
- Achieved low beam emittance ($< 1 \text{ mm}\cdot\text{mrad}$) at low bunch charges ($< 0.5 \text{ pC/bunch}$).
- X-ray production from Laser Compton Scattering was successfully demonstrated.

Subjects in the near future

- Lower emittance at high bunch-charges ($q_b \geq 7.7 \text{ pC}$)
- Beam current: 1 mA ($\rightarrow 10 \text{ mA}$)
- Bunch compression ($\sigma_t \sim 100 \text{ fs}$) and THz production

We have established many important technologies for the ERL light source. We continue to conduct R&D effort on remaining issues such as:

- Improved cavity-assembly technique for higher accelerating gradient
- Mass-production technique for main-linac cavities

Acknowledgment

We have learned much from designs and experiences of JLab IR-FEL and Cornell Injector.

We appreciate useful information and advices from

JLab: George Neil, Steve Benson, Geoffrey Krafft, David Douglas, Kevin Jordan,
Carlos Hernandez-Garcia, Pavel Evtushenko, Vashek Vylet, Andrew Hutton,

Cornell: Georg Hoffstaetter, Bruce Dunham, Ivan Bazarov, Christopher Mayes,
and many other people.

We would also thank the people of ERL community for useful discussions and encouragement.

