


SACLA (XFEL/SPring-8) Project - Status of Beam Commissioning -



Hitoshi Tanaka, on behalf of all the staffs contributing to the
SACLA beam commissioning


XFEL Research & Development Division,
RIKEN SPring-8 Center, RIKEN Harima Institute



1. SACLA System



The world's first compact XFEL based on in-vacuum UNDs designed to realize;

- (a) small scale
- (b) laser stability
- (c) operation reliability
- (d) extensibility




2. Construction & Commissioning Status of SACLA

- 2005 *Prototype system constructed*
- 2006 *Construction of SACLA started*
- 2007 *EUV SASE power saturation at the proto-type*
- 2009 *Accelerator & undulator buildings completed*
- 2010 *RF aging started*
- 2011
 - 21 Feb. *Beam commissioning started*
 - 23 Mar. *Full energy accel. achieved & und rad observed*
 - 7 Jun. *First SASE lasing at 0.12 nm*
 - 17 Jun. *Facility inspection completed*
 - 28 Jul. *Beam tuning before summer shutdown terminated*



2. Commissioning Schedule until Summer



3. Present Laser Performance (1)

Present Result Summary w/o Laser Heater

Quick beam commissioning (~3 months to the lasing) with a newly constructed machine

Maximum laser power

~4 GW


Lasing wavelength range

0.8 ~ 1.6 Å


Laser being reproducible

- w/o beam FB keeping the peak current
- at 60~70% of peak intensity


Shortening of Laser Wavelengths




3. Present Laser Performance (2)




3. Present Laser Performance (3)



3. Present Laser Performance (4)




3. Present Laser Performance (5) Variation of Laser Profile $\lambda=1.2 \text{ \AA}$




3. Present Laser Performance (6)

Laser Spatial Profile after Monochromatization




Photon energy: 10 keV
110 m from the exit of ID18



Si(111) DCM covering photon energy range from 4 to 30 keV

3. Present Laser Performance (7)

Focused down to $1.1 \mu\text{m} \times 0.9 \mu\text{m}$ (FWHM)



Ablation pattern
by focused XFEL on
gold-deposited film

Collaboration with
Osaka Univ. (Prof.
Yamauchi) and Univ.
Tokyo (Prof. Mimura)



4. Accelerator Performance (1)

RF Stability High enough for Achieving Stable Bunch Compression

Stability of cavity pickup signals (rms of 10 shots ave. for 12hr)

unit		amplitude		phase (deg.)	
		mes.	target	mes.	target
238MHz	SHB	1.0×10^{-4}	1×10^{-4}	0.0067	0.01
				78 fs	120 fs
5712MHz	CB01-1	5.6×10^{-4}	1×10^{-3} *	0.032	0.1*
				16 fs	49 fs


* tolerance for C-band correction accelerator



4. Accelerator Performance (2)

RF System Satisfying a Target Gradient of 35 MV/m


Operation status of C-band accelerator (May 2011 - June 2011)




Off-crest accel.

4. Accelerator Performance (3)


Longitudinal Beam Profile over Multi-stage Bunch Compressor



Simulation




Measurement



4. Accelerator Performance (4)

Transverse Beam Profile over Linear Accelerator





4. Accelerator Performance (5)

Beam Normalized Projection Emittance

Extracted e-beam from e-gun
 Energy = 500 keV
 Measured by slit-scan

$$\begin{aligned} \sigma_b^2 &= \mathbf{A}x^2 + \mathbf{B}x + \mathbf{C} \\ &= \mathbf{A}\left(x + \frac{\mathbf{B}}{2\mathbf{A}}\right)^2 + \mathbf{D}\left(\equiv \mathbf{C} - \frac{\mathbf{B}^2}{4\mathbf{A}^2}\right) \\ \varepsilon_b &\approx \gamma\beta \frac{\sqrt{AD}}{L^2} = \sqrt{D} \sqrt{\frac{A}{L^4}} \end{aligned}$$



5. Undulator Performance (1)

XFEL Undulator Main Parameters

Magnet Structure	Hybrid Type
Material	NdFeB
Length (m)	5
Period Length (mm)	18
Number of Periods	277
Number of Undulators	18
Minimum Gap (mm)	3.5
Maximum K	2.2
$K@\lambda=0.12$ nm, $E=7$ GeV	~ 1.8



5. Undulator Performance (2)

XFEL Undulator Tuning Step

Def.
UND=Undulator,
PS=Phase Shifter

1. Undulator Spectrum Measurement & Check
2. Correction Table for UND & PS Gap Changes < a few μm
3. K-value Fine Tuning $\Delta K/K \sim 5 \times 10^{-4}$ (3 μm)
4. Electron Beam Orbit Setting & Vertical Alignment of UND
5. PS Gap Preset $\sim 1 \mu\text{rad}$ $\Delta K/K \sim 1.5 \times 10^{-4}$ (50 μm)
6. UND K-value Tapering (Peak Current Dependence only Considered)




First lasing trial

After lasing, by using laser intensity as a probe



7. PS Gap Optimization
8. UND K-value Tapering Optimization

5. Undulator Performance (3)




5. Undulator Performance (4)

After full-beam tuning at the end of July, each spatial distribution at the low energy tail became more clear




5. Undulator Performance (5)

Precise K-value Tuning



X-ray Beam Size Observed at Optical Hutch



6. Remaining Issues & Future Perspectives

Present schedule is



- Tuning restart Sep. 12
- Test use of SASE Middle of Oct.
- User Operation March 2012

Remaining issues are

- Beam profile measurement downstream of BC3
- Lower pulse energy compared with the expectation
- Unverified alignment precision of beam orbit over UND
- Vertical beam center of mass fluctuation
- Introduction of Long pulse mode (high charge acceleration)
- Feedback control of bunch length drift

COTR Observed in SACLA

Coherent OTR (COTR) was actually a serious problem at the early stage of the beam commissioning. Now, we can tune the bunch compressor owing to a spatial mask in front of the lens.



Temporal profile measurement (screen monitor images at RF deflector)

Interpretation of the Measured Gain Curve

