Accelerator Beamline Performance for the IR FEL at the Fritz-Haber-Institut, Berlin

FEL 2012 Nara, Japan, August 2012



Abstract

H. P. Bluem, J. Ditta, D. Dowell*, H. Loos*, J. Park,A. M. M. Todd and L. M. Young*Advanced Energy Systems, Medford, NY, USA.

S. Gewinner and W. Schöllkopf, Fritz-Haber-Institut der Max-Planck-Gesellschaft, Berlin, Germany

An electron accelerator and beamline for an IR and THz FEL with a design wavelength range from 4 to 500 μ m has been commissioned by Advanced Energy Systems at the Fritz-Haber-Institut (FHI) [1] in Berlin, Germany, for applications in molecular and cluster spectroscopy as well as surface science. The linac comprises two S-band standing-wave copper structures and was designed to meet challenging specifications, including a final energy adjustable in the range of 15 to 50 MeV, low longitudinal emittance (< 50 keV-psec) and transverse emittance (< 20 π mm-mrad), at more than 200 pC bunch charge with a micro pulse repetition rate of 1 GHz. First lasing was achieved February 2012.



* Consultants to AES

FEL 2012 - 2



FEL Layout



Oscillator and Electron Beam Properties

| Undulator | MIR | FIR |
|------------------|---------------|----------------------|
| Туре | Planar hybrid | Planar hybrid or PPM |
| Material | NdFeB | NdFeB or SmCo |
| Period (mm) | 40 | 110 |
| No. of periods | 50 | 40 |
| Length (m) | 2.0 | 4.4 |
| K _{rms} | 0.5 – 1.6 | 1.0 - 3.0 |
| IR-cavity | MIR | FIR |
| Length (m) | 5.4 | 7.2 |
| Waveguide | none | 1-D 10 mm high |
| Wavelength | $4-50 \ \mu$ | >40 μ |

| Parameter | Unit | Specification | Achieved |
|----------------------------|---------------|---------------|----------|
| Electron Energy | MeV | (15) 20 - 50 | 20 - 50 |
| Energy Spread | keV | (<) 50 | 50 |
| Energy Drift per Hour | % | (<) 0.1 | TBD |
| Bunch Charge | pC | (>) 200 | 215 |
| Micropulse Length | psec | 1 - 5 (10) | 2 - 5 |
| Micropulse Repetition Rate | GHz | 1 | 1 |
| Micropulse Jitter | psec | 0.5 (0.1) | TBD |
| Macropulse Length | μsec | 1 - 8 (15) | 1 - 8 |
| Macropulse Repetition Rate | Hz | 10 (20) | 1 |
| Transverse RMS Emittance | π mm-mrad | 20 | 13.1 |





FEL 2012 - 4

Photo of Installed System







FEL 2012 - 5

Front End & Linacs





FEL 2012 - 6

Putting Accelerator Technology to Work



Gun, Chicane, Mirrors & Undulator







Putting Accelerator Technology to Work

STI Optronics



FEL 2012 - 7

50 MeV Design Point Beam Dynamics Simulations



35 MeV, K = 1.0 Beam Envelope Undulator Simulation



FEL 2012 - 9

Putting Accelerator Technology to Work

Systems, Inc.

Emittance Measurement @ 125 pC & 45 MeV



Energy Spread Measurement @ 45 MeV

FEL 2012 - 11

Bunch Length Measurement

- Bunch length is set by the end of the chicane (20 MeV) and does not change significantly in the downstream beamline
- Set Linac 2 to compensate for beam loading and to deliver zero energy gain
- Use the zero-crossing technique to correlate the bunch length with energy spread (Graves at SDL)
- Phase scan of Linac 2 with measurement of the energy spread gives an estimate the longitudinal phase space (SLAC et al.)
- Bunch length with chicane on/off estimated to be 2/5 psec

Vstems, Inc

Optical and Electron Beams Through Undulator

Spontaneous Emission @ 28 MeV & K_{rms} = 1.22

- Current transformers at undulator entrance and exit (Red and Green respectively)
 - Initial 3 μ sec has significant spread in energy => isochronous bend loss
 - Final 2 μsec shows near 100% transmission through undulator
- Baseline MCT signal without beam (White)
- Spontaneous emission (Blue)
- Electron beam current signal > 200 mA or 210 pC (Yellow) FEL 2012 - 14 Putting Accelerator Technology to Work

First Light @ 16 microns

- 28 MeV with $K_{rms} = 1.22$ (20 mm gap)
- Saturated MCT signal (Blue)
- Electron beam current signal > 200 mA or 210 pC (Red)
- Subharmonic buncher I & Q signal (Yellow and Green respectively)
 - Green curve indicates large phase slew and shot-to-shot variation (now fixed)

FEL 2012 - 15

Gain Contours

- Contours assume 200 pC bunch charge, 50 keV energy spread, 20 μ transverse emittance => estimated gain ~ 60%
- First light: 210 pC and estimated ~ 50 keV energy spread (50 keV @ 25 and 45 MeV), ~ 20 μ transverse emittance (13.1 μ measured @ 45 MeV and 125 pC) with microbunch length assumed ~ 5 psec (measured with chicane off)

* Gain curves courtesy Rudi Wünsch, HZDR, Dresden

Blue trace: IR detector signal, Green trace: SHB phase,

Cavity

Brown trace: electron bunch current Yellow trace: SHB amplitude

 $E_{\rm El} =$ 28 MeV $\lambda_{\rm IR} =$ 16 µm

Improved SHB Signal (Beam Loaded)

Flattened Linac 1 Signal with Beam Pulse

SHB Q Linac 1 I Linac 1 Q CT

Effect of LLRF Feedforward

Putting Accelerator Technology to Work

Energy Systems, Inc.

Advance

Issues & Plans

- 20 50 MeV achieved but decelerating mode for energies < 20 MeV must be demonstrated with second accelerator
- Confirm 50 keV energy spread requirement across the full energy range
- Verify transverse emittance $< 20 \pi$ mm-mrad at full current
- Verify bunch length measurements and demonstrate ~ 1 psec with chicane
- Increase the macropulse length to $> 8 \ \mu sec$
- Approval to increase the PRF to 20 Hz is anticipated shortly
- Complete residual punch list
- Provide method for reduced micropulse repetition rate operation
- Complete and test final gun HVPS (temporary system has stability issues)
- One klystron requires refurbishment to reach the desired power level (FHI is also purchasing a spare)
- Acceptance testing will be completed shortly

FEL 2012 - 32

Summary

- FHI FEL MIR beamline is being commissioning:
 - Beam first delivered to MIR beam dump in mid October 2011
 - First light at ~ 16 microns was achieved on February 14, 2012
- Demonstrated performance includes:
 - -20-50 MeV (15-50 MeV)
 - 215 pC current @ 1 GHz (> 200 pC)
 - 50 keV energy spread at 25 MeV and 45 MeV (0.1% @ 50 MeV => 50 keV)
 - = 13.1 (H) / 10.1 (V) π mm-mrad @ 125 pC and 45 MeV (20 π mm-mrad)
 - \pm 3% emittance error bar implies good energy stability
 - 2/5 psec bunch length estimated with chicane on / off (1 10 psec)
- Acceptance testing planned for Fall when new gun HVPS is commissioned

Putting Accelerator Technology to Work

Acknowledgement

- Organizers for the opportunity to present this work at FEL 2012
- Max-Planck-Gesellschaft for the opportunity to design and build their challenging FEL
- The FEL crew at FHI (Wieland Schöllkopf, Sandy Gewinner, Gert von Helden, Heinz Junkes, Weiqing Zhang, Gerard Meijer, Wolfgang Erlebach, Andreas Liedke) and HZDR (Ulf Lehnert, Wolfgang Seidel, Rudi Wünsch and Peter Michel) for their support
- Lex van der Meer for his interest and invaluable suggestions
- Steve Gottschalk for his undulator
- Dave Dowell, Lloyd Young, Ralph Lange, Henrik Loos, Kevin Jordan, Bob Dalesio, Michael Davidsaver and Dave Douglas for their varied and irreplaceable contributions
- AES physics, engineering, manufacturing and technical staff who supported the project

Putting Accelerator Technology to Work

Systems, Inc