



Beam operation at the PAL-XFEL Injector Test Facility


J.-H. Han, J. Hong, J. H. Lee, M. S. Chae, S.Y. Baek,
H. J. Choi, T. Ha, J. Hu, W. H. Hwang, S. H. Jung, C. B. Kim,
C. H. Kim, I.Y. Kim, J. M. Kim, S. H. Kim, H. S. Lee, S.-J. Lee,
Y.Y. Lee, C.-K. Min, G.Y. Mun, D. H. Na, S.-J. Park, S.-S. Park,
Y. J. Park, Y. K. Son, H. R. Yang, H.-S. Kang, I. S. Ko,
Pohang Accelerator Laboratory




FEL2014, Basel, 25-29 August 2014

- PAL-XFEL Project
- Injector Test Facility
- Electron Beam Property Measurement
- Beam Test of Accelerator Components

PAL-XFEL Overview




PAL-XFEL Parameters



Undulator Line	HX1	SX1
Wavelength	0.06 ~ 0.6 nm	1 ~ 4.5 nm
Electron Beam Energy	4 ~ 10 GeV	3.15 GeV
Wavelength Tuning	0.1 ~ 0.06 nm (Undulator Gap) 0.6 ~ 0.1 nm (Beam Energy)	3 ~ 1 nm (Undulator gap) 4.5 ~ 3 nm (Beam Energy)
Undulator Type	Planar	Planar + APPLE II
Undulator Period	26 mm	37 mm
Undulator Gap	8.3 mm	10 mm
Repetition Rate	60 Hz	

PAL-XFEL Layout



RF Gun	Dipole Magnet	Stripline BPM H116, S39	BCM	H7, S3	fs streak camera	Kicker Magnet
Laser	Quadrupole	Cavity BPM H31, S18	Screen	H40, S10	Dechirper	H0, S2
X band Cavity	Plannar Undulator	Energy BPM H3, S1	Wire Scanner H8, S2	Deflector	Tune-up Dump	Safety Permanent Magnet
Accelerating Column	EPU	CSR monitor H3, S1	Beam Arrival Monitor H4, S2	Collimator	H10, S7	Gate valve H63, S14
						Fast shutter H4, S3


- The building is under construction, to be ready by December 2014
- Component installation from late autumn 2014 for a year
 - All accelerator components to be installed
- Beam commissioning from winter 2015
 - 10 Hz repetition rate
- First FEL expected in late spring 2016
 - 0.3 nm at hard X-ray beamline with 6 GeV

Test Facilities/Lab for PAL-XFEL (2012~)




- ITF (Injector Test Facility): Injector components and diagnostics commissioning
- ATF (Accelerator Test Facility): High power RF components R&D and test
- IDL (Insertion Device test Lab): Field measurement, control test
- PTF (Photon Test Facility): Photon Beamline components test, pump-probe test

- Goal: Development and test of injector components
Diagnostics test using electron beams
- S-band photocathode gun for beam generation
- Ti:sapphire laser system
- Two S-band 3 m traveling-wave structures. Max beam energy ~ 140 MeV
- Test of high power RF system (klystron, modulator, RF window, SiC load) and low level RF, solid state amplifier
- Test of various accelerator components
- Operation normally at 10 Hz, tested up to 60 Hz
- Building construction started in 2011
- First electron beam in December 2012
- Operational until summer 2015




S. J. Park et al, IPAC2013, p. 2220

ITF Layout



Installation


Tunnel



Gallery




Laser room





Baseline gun







RF Amplitude & Phase Control of Gun





ITF Beam Diagnostic Components



RF Gun	Accelerating Column	Deflector	Dipole Magnet	Dechirper
Screen	Stripline BPM	Laser	Quadrupole	




- Developed at PAL (with POSTECH) since 2005
- Design based on BNL S-band gun
- 1.61 cell & side coupling with 2 RF coupling and 2 pumping holes
- Drive laser normal incident to cathode
- Solenoid immediate downstream of the gun
- Designed for 120 Hz operation at 120 MV/m
- Beam commissioning ongoing at ITF
- RF operation is stable up to 30 Hz & 120 MV/m. 60 Hz test was done shortly in summer 2014



J . H. Hong et al, FEL2013, p. 279



Cold Test and Installation of Gun1



Cold test result


Gun installed in ITF

Gun after brazing



FEL20

60 Hz Gun Operation



41.5 kV, 40 Hz (rf 1.5 us)

41.5 kV, 60 Hz (rf 1.5 us)

41.5 kV, 40 Hz (rf 1.75 us)

41.5 kV, 60 Hz (rf 1.75 us)



Ti:sapphire Laser Parameters


Parameter	Value
Oscillator rep. rate	79.333 MHz
Amplifier rep. rate	120 Hz
Center wavelength	770 nm
Pulse duration	~150 ps
Pulse energy	20 mJ
Energy jitter (RMS)	~0.24 %

C. H. Kim, C. K. Min

Photocathode Drive Laser Generation




- Repetition rate of seed laser (Coherent Mira) set to 79.333 MHz, synchronized to the master oscillator.
- Regenerative amplifier (Coherent Legend Elite) used to generate pre-amplified output with about 150 ps and 120 Hz repetition rate.
- Post-power amplifier boosts output power up to 2.5 W (rms noise; 0.24 %)




UV & IR Laser Transportation



ITF Laser room



ITF Tunnel



UV Laser Parameters

Parameter	Value
Center wavelength	257 nm
Pulse energy (variable)	Up to 1 mJ
Pulse duration (variable)	3~5 ps
Energy jitter (RMS)	~1 %
Beam size at cathode (variable)	<1 mm

IR Laser for Laser Cleaning

Parameter	Value
Center wavelength	770 nm
Pulse energy (variable)	< 400 μJ
Pulse duration	~ 150 ps
Energy jitter (RMS)	<1 %
Beam size at gun (variable)	< 1 mm

Drive Laser Pulse Length Measurement


Different frequency generation (DFG)



Pulse duration by DFG
cross-correlation measurement

A drive laser pulse to the
cathode is not affected by this
measurement


C. H. Kim, C. K. Min



Drive Laser Shape Monitoring


Optics table

Hard aperture
Image transport to cathode



Courtesy of C.Min

Beam profile in virtual cathode camera, $\phi 1$ mm iris




C. H. Kim, C. K. Min

Accelerating Structures




Delivered from Mitsubishi Heavy Industries

Installed in ITF tunnel




RF coupler




Bunch Generation at Cathode



Beam Charge VS Phase




Quantum Efficiency




J. Hong et al, FEL2014, THP011

Best Results from ITF – July 2013


Parameter	Value
Beam energy	135 MeV
Charge	200 pC
Gun phase	35 degs
Acc's phase	on-crest (both)




Laser beam profile



Measured in summer 2013



Measured in summer 2014




Minimum emittance with 3 ps laser pulse length


Both measurements show discrepancy to simulation

Emittance with longer laser pulse is lower according to simulation


Emittance (95%) at 200 pC



Slice Emittance Measurement



RF deflector for vertical streaking
Horizontal emittance of bunch slices
measured



Measurement condition not optimized
Projected & slice emittance measurement
planned in September 2014


J. H. Lee et al, FEL2014, THP013

Possible Sources of Large Emittance Value – I




Higher order mode and field alignment of gun solenoid


Gun solenoid



Higher order mode of solenoid field






→ Corrector coils to be repaired in September 2014,
for higher order mode compensation





Misalignment of Solenoid Field \rightarrow BBA

Gun solenoid micro-mover is manufactured for beam-based alignment, to be installed at ITF in winter 2014



Non-ideal longitudinal & transverse profile of drive laser pulse





Possible Sources of Large Emittance Value – III



- Alignment of beam to RF and solenoid fields
 - > New alignment done recently
- Non-symmetric RF coupler field of accelerating structures (?)
 - > Study underway

MHI J-type coupler with circular coupler cell



e-beam


RF power in

- Laser cleaning of cathode
- Beam test of accelerator components
 - Stripline BPM
 - Beam arrival time monitor (cavity type)
 - Dechirper
 - ...

Laser Cleaning

150 ps long IR (760 nm) laser used for cleaning

QE maps



Photocathode is the central area of the copper gun cavity back plane

QE recovered from 4.0×10^{-5} to 1.3×10^{-4} and stayed for a few months


C. K. Min, 6th Hard X-ray Collaboration Meeting, DESY, 2014

Beam Test of Stripline BPM


Calibrated Libera Single Pass E

- $KX = KY = 6.666$ mm
- Attenuator setting = 18 dB
- Measured resolution = **1.4552 μm**

BPM6X Resolution Calculation Results by Three BPM Method
(BPMResolutionTestSinglePassE2014Feb27_121437Data.mat)



— Measured Resolution: 1.4552micro-meter
• ICT 31.2(~200pC) mV, BPM6Y Gain: 18dB




Libera Brilliance Single Pass and BPM controller produced by SLAC were tested at ITF $\sim 3 \mu\text{m}$ with 200 pC (PAL-XFEL linac requirement $< 5 \mu\text{m}$)


Beam Arrival Time Monitor

2.856 GHz signal analyzed with the LLRF module


Time resolution ~ 10 fs




46 fs rms jitter for 20 min



76 fs rms jitter for 8 hours



Corrugated-Wall Dechirper



Corrugated structure

P. Emma et al., PRL 112, 034801 (2014)






FIG. 7 (color online). Screen 6 images (*top-row*: measured, *bottom-row*: simulated, $Q = 150$ pC), with $g = 6$ mm, rf deflector switched off and L0a phase adjusted 10 degrees off crest, showing no dipole kick when gap is centered on the beam (*left*), but a strong tail kick with gap off axis by 1 mm (*right*). The bunch head is at left in each image.


- Vacuum line upgrade with low mu materials in winter 2014
- Laser shaping improvement for spatial & temporal
- Gun solenoid higher order mode cancelation in September 2014
- Finer beam-based alignment including gun solenoid micro-mover in winter 2014
- Test of new gun with coaxial coupler in winter 2014
- Laser heater test in winter 2014




- Components are ready for installation
- Full beam test to be done at ITF for efficient injector commissioning at PAL-XFEL



Undulator field
measured at IDL



- 1.5 cell S-band gun with coaxial coupler
- Lower emittance and better thermal behavior expected



To be installed in the ITF tunnel in winter 2014

- PAL-FEL ITF is running for injector commissioning prior to main linac commissioning in a year
- Beam property measurement ongoing, the present beam quality satisfies the required parameter for initial beam commissioning of PAL-XFEL
- R&D and test of diagnostics, high power RF, laser ongoing
- New gun and laser heater to be tested
- ITF to be operational till summer 2015

Thanks

