

Advances of the SPIRAL 2 project

Jean-Michel Lagniel (GANIL) for the SPIRAL 2 Team






Menu

- 1- SPIRAL 2 facility (Phase 1) status
- 2- Challenges induced by the safety rules
- 3- Plan for the commissioning
- 4- SPIRAL 2 future prospects
- 5- Summary

SPIRAL 2 integration of the accelerator processes,
building construction and process connections
Pascal ANGER (next talk)




-1- SPIRAL 2 Facility 7,200 m² 4 levels



More than 100 rooms

-1- SPIRAL 2 Facility - 9.50 m (beam level)





-1- SPIRAL 2 Status

SPIRAL 2 building site preparation December 2010 - January 2011





-1- SPIRAL 2 Status

+3.5 years : September, 2014

(Pascal Anger talk)




-1- SPIRAL 2 Facility injector




**18 GHz 60 kV
LPSC Grenoble**

**Free space for the future Q/A = 1/7 injector
connection**



2.45 GHz 40 kV IRFU Saclay




0.75 MeV/u RFQ







-1- SPIRAL 2 p/d Source Status

First beam December 19, 2014






-1- SPIRAL 2 p/d Source Status



Long period stability (6 mA CW)

0.2 π mm mrd
rms norm.





Emittance measurements f(I) July + August

Ability to extract 11 mA CW from the source => 6 mA proton beam
Beam intensity and emittance control using 6 H and 6 V slit systems




-1- SPIRAL 2 Heavy-Ion $q/A = 1/3$ Source Status

First beam (230 μA Argon 9+) July 10, 2015




Ask
Thierry Lamy
for details !

-1- SPIRAL 2 RFQ Status



Installation Nov. 2014 to Feb. 2015





Voltage law (bead-pull) measurements + adjustments (40 plungers) OK March 2015

Max error = 2.3 % on the quadrupolar mode (+3 % longitudinal emittance increase)

Expected transmission = 99.7 %

RF amplifiers installed, still in test
Cooling/tuning system commissioning ok
First RFQ beam expected October 2015








1- SPIRAL 2 Facility

Superconducting LINAC

88 MHz QWR

12 x 1 = 12 $\beta = 0.07$ cavities

7 x 2 = 14 $\beta = 0.12$ cavities



	Q/A	I max (mA)	Energy (MeV/n)	CW max beam power (kW)
P	1/1	5	2 - 33	165
D	1/2	5	2 - 20	200
Ions	1/3	1	2 - 14.5	45
	1/7	1	2 - 8	48

Wide range of particles, intensities, energies, duty-cycles (CW up to single bunch)



-1- SPIRAL 2 LINAC Status

Cryogenic system (1,300 W equivalent 4.5 K) installed, first liquid helium in July



4 /12 CM-A + 3 /7 CM-B aligned and connected to their valve boxes
First connection to the hot sections this week




One solid state
amplifier / cavity
Up to 20 kW

Amplifiers,
feeders, circulators,
LLRF and interlock
PLC have been tested
independently,
installed in the building
and interconnected



-1- SPIRAL 2 LINAC / LHE Status



First LINAC beam September 2016

MCNPX calculations



d+ Be and p+⁷Li N source

N beam stop

Actinide targets

28 m x 6 m ToF hall


$T_{rf\ LINAC} = 11\ ns$
Fast choper $\Rightarrow 1\ ns\ bunches$



NfS ready for the first SPIRAL 2 experiment (September 2016)

High-power rotating targets
including actinides

Super Separator-Spectrometer



S3 ready beginning 2017



Which challenges for such facilities ?

Challenges usually faced in any (accelerator based) project

Construction of an (efficient) multi-competency project team

National / international collaboration management Real cost evaluation Cost vs performance optimizations

Risk evaluation and risk management Schedule constraints ...

Plus new challenges for the new generation of high-power accelerators

High radio-active ion production and high neutron flux + **Actinide target management**

Guaranty ALARA radioactive releases and worker / public exposition

☞ Challenges induced by the safety rules

Beam loss control + **Multi-ions / multi-energies / multi-duty-cycle / multi-intensities machine**

+ **Safety constraints**

☞ Challenges for the commissioning and operation



-2- Challenges induced by the safety rules

SPIRAL 2 Safety main objectives :

Nominal operation

Workers : ALARA, goal < 2 mSv/y, max < 10 mSv/y

Public : ALARA, impact on the environment < 10 μ Sv/y

Accidental situation

Workers : ALARA, goal < 10 mSv/accident, max < 20 mSv/accident

Public : ALARA, goal < 10 μ Sv/accident, max < 100 μ Sv/accident, Total release < 1 mSv/accident





**These values have severe impacts on
the schedule, cost, commissioning and operation of the facility**

-2- Challenges induced by the safety rules

Construction done to “ Prevent – Monitor – Limit “

All the safety systems must “work” in case of accident
e.g. electricity failure, fire, earthquake, plane crash...

“Earthquake of reference” = Caen, December 30, 1775 (5.7 mag.)



15 000 m³ of concrete


Ironing
total = 2 200 T up to 400 kg/m³

The equipments (cryomodules,
magnets, helium tanks, cranes...) **must not** damage the confinement
barriers and shieldings

-2- Challenges induced by the safety rules


Confine and monitor @ a Nuclear Ventilation System

Linac and HEBT activated air, Beam dump, AEL, Actinide targets



-2- Challenges induced by the safety rules

Beam dump & actinide targets



Nuclear Ventilation System

Minimum air leaks ➡ Airtight doors +
**Block up the cable and beam pipe
wall traversals ...**

Vacuum pumps and glove box
exhausts treated separately



Very-High-Efficiency filters



Air Treatment Facility (CTA)



-3- Commissioning and operation challenges

200 kW beam power vs 100 W enough to drill the vacuum chamber

200 kW beam power vs 1W/m beam losses for hands on maintenance

Although beam losses are unavoidable during commissioning and tunings !

Safety constraints ➡ **Limited amount of radio activated material**

➡ **Limited use of the beam dump : 400 W /24h → 3 min 200 kW /24h**

Superconducting LINAC ➡ Non (weak) interceptive diagnostics @ pollution


➡ Limited amount of diagnostics

Low frequency single gap cavities ➡ Long radial and longitudinal focusing periods


➡ High space charge (nonlinear) effects 5 mA > 50 mA (SNS / ESS)

Low energy accelerator ➡ **Weak efficiency of the Beam Loss Monitors**

-3- Commissioning and operation plan




-3- Commissioning and operation plan



Tuning constraints

- ☞ Current ok for the diagnostics
($>150 \mu\text{A}$ for the BPMs)
- ☞ Pulse duration ok for stable beam
and diagnostic acquisition
- ☞ Rep rate for fast tuning
2 Hz / 1 Hz min



Beam loss recording system

to understand and predict
the beam loss level
at full power

-3- Commissioning and operation plan


Choices of beam current, rep. rate and pulse duration
for the tunings at very low power (Phases 1 and 2)

Full beam loss during tunings

2 hypotheses : $\langle Pf \rangle = 1\text{W}$ and 10W BPM degraded performances at $50\text{ }\mu\text{A}$

Mean power	Pick intensity	Duty cycle	Pulse length / rep. rate
1 W	25 nA	CW	
	50 μA	$5.0 \cdot 10^{-4}$	500 μs / 1 s
	150 μA	$1.7 \cdot 10^{-4}$	170 μs / 1 s 660 μs / 4 s
	5 mA	$5.0 \cdot 10^{-6}$	5 μs / 1 s 500 μs / 100 s
10 W	250 nA	CW	
	50 μA	$5.0 \cdot 10^{-3}$	5 ms / 1 s
	150 μA	$1.7 \cdot 10^{-3}$	1.7 ms / 1 s
	5 mA	$5.0 \cdot 10^{-5}$	50 μs / 1 s 500 μs / 10 s

The success will depend on the diagnostic quality !






-4- SPIRAL 2 1+ Phase future prospect


100% financed

Possible schedule





4- SPIRAL 2 Q/A = 1/7 injector future prospect



Grenoble + Saclay + GANIL Working Group
First step = Source choice

60 GHz ECR ? Thierry Lamy, Thursday morning



-5- Summary

Good advances of the SPIRAL 2 project since HIAT'12 Chicago

- Accelerator and conventional facility installations in great progress (Pascal Anger talk)
 - The light and heavy ion sources are working very well
- RFQ RF voltage law tuning and cooling control ok, first beam expected next month
 - Cryogenic plant, RFQ and linac RF amplifiers installed
- Superconducting linac installation in // with the RFQ commissioning
- The installation progresses are limited by the availability of the GANIL team
(Operation of the GANIL “cyclotron facility” in //)
 - First linac beam in September 2016
- The safety constraints have been and still are a concern