



High Power Beam Commissioning Issues for the Prototype of C-ADS Injector



C-ADS Injector Demo Facility

Zhijun Wang


Institute of Modern Physics, CAS@Lanzhou




Outline



- Brief introduction of the beam commissioning progress
- Commissioning Issues for the C-ADS injector
- Summary and outlook
- Acknowledge




Commissioning Schedule of C-ADS injector




1

- At the beginning of June , RF CW achieved,2014
- June 6th, the first beam, **energy is 2.15 MeV ,2014**
- June 30th, **10 mA, CW beam**, beam power 21.6 kW,2014




2

- ECRIS + LEPT + RFQ + MEPT + TCM, **2.5 MeV,2015**
- RFQ commissioning, validate CM design.
- CW operation with 10 mA in Feb, 2015 successfully




3

- ECRIS+LEPT+RFQ+MEPT+CM6, **5 MeV**
- 10.2mA,5.3MeV, pulsed beam at 6th Jun:**2.7mA, 5.2 MeV ,CW** at 24th Jun ,2015



4


- **~25 MeV at IMP**, Sept. 2016 – 2017
- Cooperation with IHEP





Beam commissioning Issues for the Prototype of C-ADS injector




- CW operated RFQ with 10 mA beam
- Benchmark between simulation and experiments
- Hydrogen gas transfer problem
- Beam loss control and detection
- Pulse beam to CW beam issue
- 6D-emittance measurements with no-interceptive BPMs





10 mA CW beam tuning of RFQ




The RF power amplifier is tuned to compensate the beam loading effect.



10 mA CW beam tuning of MEBT&TCM1










The temperature of RFQ cavity cooling water is tuned manually to decrease the reflection RF power caused by beam loading!





Benchmark between simulation and experimental results

	Alpha_x	Beta_x (m/rad)	Alpha_y	Beta_y (m/rad)
Exp	0.3	0.22	-0.11	0.12
Parmteq	0.46	0.27	-0.10	0.12
Totoutis	0.20	0.22	-0.18	0.11
Track	0.22	0.23	-0.31	0.11





Transfer of hydrogen at C-ADS






Fig. 13. Log of the RGA installed at the first MEBT chamber. Effect on hydrogen partial pressure at opening of the EIS and PSM valves are shown for the original configuration (a) and after replacement of the ion pump by a turbo pump (b).

The hydrogen and residual gas will be frozen on the RF surface of the sc cavity. It is contaminated again and causes multipacting.

The reason of sc cavity failure?





Fig.14. Increase of hydrogen pressure in the MEBT chamber during beam operation




Beam loss detection



Type: PT100
Normal temperature





LAKE SHORE: DT-670B
2K-305K ($\pm 0.5K$)






Operation from Pulse to CW beam






Operation from Pulse to CW beam



16 KeV, 3.5mA H- Beam pulsed @ 50% duty factor



Operation mode transition from pulse mode to CW, beam maybe out of control.

Q. Ji et al

Beam dynamics studies of H- beam chopping in a LEBT for project X

12/19







Table 2: Space-Charge Transient Time for Proton Beam

Pressure	SCC rise time
3.5 10 ⁻⁷ mbar	300 μs
7.5 10 ⁻⁷ mbar	150 μs
5.5 10 ⁻⁶ mbar	30 μs
1.2 10 ⁻⁵ mbar	15 μs


D. Uriot, O. Tuske et al COMMISSIONING OF THE SPIRAL2 DEUTERON INJECTOR



Operation from Pulse to CW beam



Yuan Xu, Shixiang Peng et al, High current H_2^+ and H_3^+ beam generation by pulsed 2.45 GHz electron cyclotron resonance ion source




No-interceptive diagnostics-BPMs


128 hours beam including
2.1MeV, 4.5h, 10mA, and 6h
6mA CW beam.



2.1MeV, 10mA, 100us, 1Hz




2.1MeV, 1mA, CW, 6-7mins




Transverse:
$$\langle x^2 \rangle - \langle y^2 \rangle + \bar{x}^2 - \bar{y}^2 = a^2 \frac{\alpha}{\sin 2\alpha} \frac{A_R + A_L - A_T - A_B}{A_R + A_L + A_T + A_B}$$

Longitudinal:
$$Z_\varphi = \left(-\frac{360^{\circ 4}}{2\pi^2} \left(\frac{f_{RF}}{f_{BPM}} \right)^2 \text{Ln} \left(AMP_{bpm} \cdot I_{BPM}^{sum} \right) \right)^{-1/2}$$

The 6-D Twiss parameters can be calculated by scanning technology.




No-interceptive diagnostics-BPMs



- ❑ Multi-Q scanning
- ❑ Small beam size inside the BPM
- ❑ Benchmarked with slit + wire scanner method
- ❑ The longitudinal emittance is under study

$$\begin{pmatrix}
 \langle x_i^2 \rangle \\
 \langle x_i x_i' \rangle \\
 \langle x_i'^2 \rangle \\
 \langle y_i^2 \rangle \\
 \langle y_i y_i' \rangle \\
 \langle y_i'^2 \rangle
 \end{pmatrix} = (A^T A)^{-1} A^T \begin{pmatrix}
 (\langle x_f^2 \rangle - \langle y_f^2 \rangle)^{(1)} \\
 (\langle x_f^2 \rangle - \langle y_f^2 \rangle)^{(2)} \\
 \dots \\
 (\langle x_f^2 \rangle - \langle y_f^2 \rangle)^{(m)}
 \end{pmatrix}$$


	BPM	Wires	$\Delta(\%)$
α_x	0.146	0.302	52
$\beta_x(m)$	0.212	0.22	3.6
$E_x(mmmrad)$	0.294	0.286	2.8
α_y	-0.397	-0.102	289
$\beta_y(m)$	0.141	0.121	5.0
$E_y(mmmrad)$	0.306	0.297	3.0




Summary and outlooks



- RFQ with CW 10mA, stability still on the way.
 - Circulator has delivered and tested at IMP
 - The frequency stability control achieved
- Transverse emittance has been studied, longitudinal is the point next step.
- Hydrogen gas transfer has been investigated
 - New LEFT scheme has been proposed
- Beam loss control and detection, more detailed work needed
- 6D-emittance measurements with no-interceptive BPM
 - Multi-electrode has been proposed



Acknowledge





THANKS *for your attention!*