



# LIA-20 Control System Project


G.A. Fatkin<sup>1,2</sup>, A.O. Baluev<sup>1,2</sup>, A.M. Batrakov<sup>1</sup>, E.A. Bekhtenev<sup>1,2</sup>, E.S. Kotov<sup>1,2</sup>, Ya. M. Macheret<sup>1</sup>,  
V. R. Mamkin<sup>1</sup>, A.V. Ottmar<sup>1,2</sup>, A.N. Panov<sup>1,2</sup>, A.V. Pavlenko<sup>1</sup>, K.S. Shtro<sup>1</sup>, A.N. Selivanov<sup>1</sup>,  
P.A. Selivanov<sup>1</sup>, A.I. Senchenko<sup>1,2</sup>, S.S. Serednyakov<sup>1,2</sup>, S.R. Singatulin<sup>1</sup>, M.Yu. Vasilyev<sup>1</sup>  
<sup>1</sup>Budker Institute of Nuclear Physics, Novosibirsk; <sup>2</sup>Novosibirsk State University, Novosibirsk  
E-mail: G.A.Fatkin@inp.nsk.su



## Introduction

Linear Induction Accelerator LIA-20 is designed to provide three consecutive electron beams with an energy up to 20 MeV, current up to 2 kA and the beam lateral size after focusing on the target less than 1 mm. It is planned to have one of the pulses divided into 9 angles. The accelerator will be used for the flash X-Ray radiography. Successfully commissioned LIA-2 accelerator (2 MeV, 2 kA) could be considered a prototype for the injector of the 20 MeV installation. The installation consists of a large number of complex electrophysical devices that require extensive control. First stage of commissioning will be a 5 MeV installation.

## Structure of the Linear Accelerator Part



Problems of scale:

480 modulators

Length ~ 120 m

> 6000 control channels

Realibility requirements




Components

- Pulsed Power Supply Rack:
- 8 modulators
- Demagnetizing device
- Charging devices
- Beam position monitors
- Lense power supplies
- Cathode power supply
- AM positioning system
- Vacuum pumps

...




## Control System Structure



Linear part


- Timing subsystem
  - timers
  - delay lines
- Measurement subsystem
  - «fast» (<10 us)
  - «slow» (>10 us)
- Fast interlock subsystem
- Slow controls subsystem
  - Geodetic measurements
  - Vacuum, power supplies, etc.
- System infrastructure:
  - crates
  - controllers
  - interfaces



For more details visit [THMPL10!](#)

## Slow Controls Subsystem

1. Beamline elements positioning:
  - Angle poisioning (water)
  - X-Y positioning (wire)
2. Pulsed power control
  - Modulators
  - Degaussing
  - Lense power supplies
3. Cathode heater control
4. Vacuum control
5. Crate power control



All using CAN-BUS

## Measurement Subsystem

For more details visit [THMPL09!](#)

"Fast" signals

Duration ~10 us, 4 ns per point

- 16 inductor voltages
- 4 BPM signals

Kicker voltages 1 ns per point

"Slow" signals


Duration > 10 us, ~125kSPS

- 1 charging voltage
- 16 forming line voltage
- 2 degauss currents
- 1-3 lense currents

Total > 480 channels

Total > 1860 channels


## Synchronization Subsystem



The synchronization subsystem provides all the controlled and controlling devices with the start pulses. The overall accuracy must be better than 4 ns across 70 m of length. This means that the propagation delays between the control units must be taken into consideration and negated.


## Fast Interlock Subsystem

For more details look up [TUPHA103!](#)



Inhibit the experiment at ~ 200 m, with reaction time < 20 us

## System Infrastructure



The system infrastructure is built upon COTS hardware: Intel x86-64 servers and multi-monitor x86-64 client machines.

Ubuntu LTS is used both on server and client machines. Debian is used on controllers.

Software is TANGO-Based

ICALEPCS 2017 - THPHA052