

# The Control System For The Linear Accelerator At The European XFEL

Status And First Experiences


Tim Wilksen, DESY  
ICALEPCS 2017, Barcelona, 09.10.2017

# The European XFEL Accelerator

Aerial View and Beam Line Layout

# The European XFEL

## Aerial View of Hamburg and Surroundings



**Experimental Hall  
Schenefeld Campus**

**Undulator sections and  
photon beam tunnels**


**Linear Accelerator  
1.9 km long / 17.5 GeV**

**Injector on  
DESY campus**

# The European XFEL

## Accelerator And Photon Beamlines

**Parameters:**  
 Repetition Rate 1 - 10 Hz  
 RF Pulse (flat top) 600  $\mu$ s  
 Bunches 27000/s  
 Bunch Charge 0.02 – 1 nC



# The Accelerator Control System

Concepts and Implementation

# Concepts

## Specifications and Key Components


### Specifications

- Standard hardware platform for all front-end device controls
  - Remotely manageable and hot-swap capabilities
- Well-established Software framework based on open source standards
  - For hardware support and applications
- Shot-synchronized acquisition system for online monitoring and offline analysis

### Key Components

- MicroTCA.4 as standard hardware platform for front-end devices
  - Beam diagnostics, RF/LLRF controls, vacuum and magnet controls
- MicroTCA.4-based timing system suitable for pulsed accelerators
- DOOCS as control system software framework with integrated TINE and EPICS interface
- Integrated, shot-synchronized bunch-resolved data acquisition system
- Java-based, thin-client GUI for experts and operators plus MATLAB- and Python-based applications


## MicroTCA.4 Base System




## Java DOOCS Data Display (JDDD)

# Accelerator Control System Model


Classic three-layer design of an accelerator control system enhanced by integration of data acquisition system



# DOOCS Accelerator Data Acquisition



# MicroTCA Server Read-Out Example








© K. Rehlich

# Status – Installation and Commissioning

First User

# Installation And Commissioning Stages

## Stages Of Control System Installation and Commissioning



# Statistics



## Some Numbers Of The Accelerator Control System

### System Statistics

- About 300 MicroTCA systems and server installed
- More than 9 million control system parameters visible in accelerator namespace
- About 600000 of local DOOCS archives plus TINE central archive
- More than 800 different device types and 38000 locations

### Data Acquisition System Statistics

- Running since first day of RF-gun operations
- Four instances for diagnostics, RF/LLRF
- About 1.5 GB/s sustained input rate
- More than 13000 complex DOOCS channels
- Compressed data rate to disk up to 30 TB/day
- Virtual XFEL instance for test and simulation



# Experiences

Commissioning and First Operations

# Experiences

## Commissioning and First Operations

### Installation and Commissioning

- Staged installation posed challenge to parallel commissioning of completed sections but doable ✓
- Staged commissioning process required to have accelerator control system infrastructure and common software in place from day one ✓
- With ongoing installation phases workflow, tools and experience improved; paid off already for maintenance ✓

### Design

- Well-known software frameworks and expertise on site saved time for implementing required controls applications
- FLASH as “prototype” and test-bed facilitated launching the MicroTCA hardware for the European XFEL accelerator
- Virtual XFEL turned out to be a useful tool for testing new concepts and software – learned “on the way”

## XFEL Control System WP 28

### Conceptual Design Report

Version 03/12/10

#### Table of Contents

|   |    |
|---|----|
| 1 Introduction.....   | 3  |
| 1.1 Requirements.....   | 4  |
| 1.1.1 XFEL accelerator parameters that are relevant for the control system..... | 4  |
| 1.1.2 XFEL functional requirements.....   | 4  |
| 1.2 Guideline.....  | 4  |
| 2 The Architecture.....   | 5  |
| 3 Front-End Tier.....   | 6  |
| 3.1 Hardware.....   | 6  |
| 3.1.1 General Front-End Concept.....  | 7  |
| 3.1.2 Crates.....   | 8  |
| 3.1.3 $\mu$ TCA Carrier Hub.....  | 8  |
| 3.1.4 CPU.....  | 8  |
| 3.1.5 AMC for Slow I/O.....   | 9  |
| 3.1.6 Fast single wide AMC board.....   | 9  |
| 3.1.7 Fast general double wide AMC board.....                                   | 9  |
| 3.1.8 Fast high performance 10 channel, 16 bit ADC.....                         | 9  |
| 3.1.9 Fast 8 channel 14 bit ADC, single size AMC.....                           | 9  |
| 3.2 FPGA Firmware.....  | 9  |
| 3.3 Server Operating Systems.....   | 11 |
| 3.3.1 Drivers.....  | 11 |
| 3.3.2 Hot-swap.....   | 11 |
| 3.4 Server Software.....  | 11 |
| 3.4.1 Concept.....  | 11 |
| 3.4.2 The Distributed Object-Oriented Control System (DOOCS).....               | 11 |
| Device Servers.....   | 12 |
| Application Programming Interface to Access Servers.....                        | 12 |
| Archiving.....  | 13 |
| DAQ Interface.....  | 13 |
| Alarm Interface.....  | 13 |
| 3.4.3 The Three-fold Networking Environment (TINE).....                         | 14 |
| 3.4.4 Integration of TINE and DOOCS.....  | 16 |
| 4 System Interfaces.....  | 18 |
| 4.1 Timing System.....  | 18 |
| 4.2 Low-Level RF System.....  | 18 |
| 4.2.1 Examples for these front-end servers.....                                 | 19 |
| 4.2.2 Examples of service tier applications.....                                | 20 |
| 4.2.3 Next steps.....   | 20 |
| 4.3 RF-Systems.....   | 21 |
| 4.3.1 Modulators.....   | 21 |
| 4.3.2 Klystron controls.....  | 21 |
| 4.3.3 Coupler Interlocks.....   | 21 |
| 4.3.4 Cavity and Wave Guide Tuners.....   | 21 |

# Conclusions

Outlook

# Conclusions

- The control system for the European XFEL linear accelerator has been operable from day one!
- MicroTCA.4 hardware platform well established within the accelerator control system
- Standardization of hardware and software simplified implementation, deployment and maintenance -> reliability and availability
- Fast and very successful commissioning of the accelerator control system

## Outlook

- Accelerator control system components installation completed this month for second electron beam line
- Upcoming commissioning of two photon beam lines
- Operations with multiple electron and photon beam lines and – will profit from FLASH experience
- Regular scheduled user runs
- Upcoming challenges prompted by photon science experiments

# Thanks for your attention!

DESY Accelerator Control Room  
- XFEL Area -

