

PAUL SCHERRER INSTITUT




WIR SCHAFFEN WISSEN – HEUTE FÜR MORGEN

Elke Zimoch :: Controls :: Paul Scherrer Institute

# SwissFEL Control System Overview, Status, and Lessons Learned

ICALEPCS 2017, Barcelona, Spain



- 24. August 2016 First electrons from the gun with 7.9 MeV
- 11. November 2016 First beam transport up to main beam dump
- 2. December 2016 First lasing at 380 MeV, 24 nm
- 30. August 2017 lasing at 1620 MeV, 1.3 nm
- 31. August 2017 First FEL photons in optics hutch

**Design Parameter:**

- Length: 720 m
- Energy: 5.8 GeV
- Rate: 100 Hz
- Photons: 0.65 – 5 nm

VME based systems

Power Brick LV-180

Motion Controller

EPICS  
Version R3.14.12


caQtDM | Qt  
GUIs on consoles

GitLab  
Consoles, development, and repository



Pshell – experiment scripting

- 2009: (plan) copy everything from SLS
- 2011: (experience with SITF) new hardware and new software needed
- 2016: first electrons displayed with working control system


The control system is the last system finished/working (cabling) and the first needed for commissioning



# Lesson 1 – NOT Another Storage Ring




Hardware: MRF 300 (VME and PCIe)  
See TUCPL04





Beam Synchronous Data Acquisition System  
See TUCPA06

- FEL = Pulsed Beam = **Timing and Event System is crucial**
  - Nearly all devices need trigger
  - Additional flags needed: beam-ok signal
- FEL = Pulsed Beam = **Beam Synchronous DAQ needed**
  - Tag all data with pulse id
  - Collect data with same pulse id for measurements




Archiver Appliance and BS-DAQ Web Interface



- 5 to 10 times more network ports needed than estimated ...
- Current assumptions about control system architecture need revision



# Lesson 3 – Test Systems



... and all those sites needed a working control system with consoles, network, timing, and support

- SwissFEL Control System is working and supporting accelerator and beamline commissioning
- Watch out
  - for Timing and Synchronization (Beam Synchronous Data)
  - for a huge increased number of network devices
  - for test setups with need for support and maintenance



## My thanks go to

- all PSI Controls people working for SwissFEL
- Cosylab people working for SwissFEL
- Dach Consulting
- PSI IT department
- all our users who help with debugging and tests

