




Science & Technology  
Facilities Council

# **Commissioning of the EMMA non-scaling FFAG**

**Rob Edgecock**  
**STFC Rutherford Appleton Laboratory**  
**For the EMMA Collaboration\***



\*BNL, CERN, CI, FNAL, JAI, LPSC Grenoble, STFC, TRIUMF



# Outline

## **One small problem.....**

- **Introduction**
- **Motivation for EMMA**
- **EMMA design**
- **Status of construction**
- **Status of commissioning**
- **Next steps**
- **Conclusions**




# Introduction

- **Linear non-scaling FFAGs:**
  - **invented 1997/9**
  - **for muon acceleration in a Neutrino Factory**

$$B = B_0 \left( 1 + \frac{k}{r_0} r \right)$$

Neutrino Factory






# Introduction


- **Linear non-scaling FFAGs:**
  - **invented 1997/9**
  - **for muon acceleration in a Neutrino Factory**
  - **large dynamic aperture**
  - **small orbit excursion – higher frequency RF**
  - **CW acceleration**

$$B = B_0 \left( 1 + \frac{k}{r_0} r \right)$$






# Introduction



**Fast resonance  
crossings**

**Serpentine, bucketless,  
asynchronous, etc  
acceleration**





# Motivation for EMMA

- **Realised early on:**

- **Other potential applications:**

- **hadron therapy**
    - **ADSR**
    - **other high power proton beam applications**

MOPEA021  
MOPEC047

- **One or two issues:**

- **tiny momentum compaction**
    - **unique longitudinal dynamics**
    - **possible transverse dynamics problems**
    - **resonance crossings**
    - **constraints on construction**
    - **standard tracking codes not applicable**
    - **purpose built codes need benchmarking**

- **Must build one!**

- **Hence, EMMA**




# EMMA Design

- **Simplest to build linear non-scaling machine**
- **Main parameters taken from muon accelerator:**
  - **electrons, 10-20MeV**
  - **linear magnets, cw RF**
  - **42 cells, doublet lattice**
- **In addition**
  - **very flexible**
  - **injection into full muon acceptance**
  - **lots of diagnostics**
  - **need flexible (10-20 MeV) injector with hall space**
  - **small**
  - **not too expensive!**





# EMMA Location










# EMMA Location

TUPE096



# EMMA Specifications

- **Driven by experimental nature**
- **8 lattices to explore long. & trans. dynamics**



## Requires:

- indep. dipole & quadrupole fields
- sufficient magnet aperture
- RF frequency: -4.0 to 1.5MHz
- RF gain: ~20kV to 180kV/cavity




# EMMA Design

**42 “identical” cells, ~40cm long**

**Ring ~16.5m circumference**

**Very compact!**

**7 girders**







# EMMA Design

**42 “identical” cells, ~40cm long**

**Ring ~16.5m circumference**


**Very compact**

**7 girders**





# Status of Construction





# Injection line

Transport beam to  
EMMA.

Matching.


Measure beam  
parameters on entry  
to EMMA.

Completed ~2 months.

Beam transported to  
end.


First measurements  
made.

MOPEC046





# Injection line



Transport beam to  
EMMA.

Matching.

Measure beam  
parameters on entry  
to EMMA.

Completed ~2 months.

Beam transported to  
end.

First measurements  
made.


MOPEC046








# EMMA Ring



# Injection & Extraction

## Requirements




- **Injection of:**
  - all 8 lattices
  - all energies between 10 and 20 MeV
  - into  $3\pi$  m mrad
- **Minimal impact on next turn:**
  - leakage field from septum < 0.01%
  - kickers off before 55ns (<1% ripples)
- **Slot length: ~10cm**







# Injection & Extraction








# EMMA Ring

- 42 cells mounted on 7 girders:







# EMMA Ring








# EMMA Ring









# Diagnostics








# Diagnostics



**YAG screen**



# Diagnostics Beam Line



“Destructive” diagnostic devices.

Beam can be extracted at any energy for measurement

# Commissioning Status

## Stages in commissioning

- **ALICE:**

- settings required for EMMA
- beam parameter measurements

Started

- **Injection line:**

- transmission of beam
- diagnostics commissioning

Started

- **4 sector commissioning:**






- injection & setting beam on orbit
- check lattice(s)
- tune measurements

Very soon!

- **Full ring**

- **Extraction and external beam measurements**





First emittance measurement.  
See THPD028

# Conclusions

- **EMMA is the proof-of-principle non-scaling FFAG**
- **Construction has been a challenge**
  - **novel machine**
  - **very compact: “...everything takes 5 times longer in EMMA...”, Neil Bliss, project manager**
- **Construction of ring is almost complete**
- **Commissioning has started**
- **Commissioning of ring will start soon**