





First operational experience with the LHC Cryogenic System

S. Claudet (CERN, Geneva) on behalf of the "Cryogenics Group" Technology Department

IPAC 10

The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010







Outline



- Introduction
- Cool-down _
- Tuning 🚃
- Operation
- Nice features !
- Consolidations
- Summary



3/44





ARC12_MAGS_TTAVG ● ARC23_MAGS_TTAVG ■ ARC34_MAGS_TTAVG ● ARC45_MAGS_TTAVG
 ARC56_MAGS_TTAVG ● ARC67_MAGS_TTAVG ■ ARC78_MAGS_TTAVG ▲ ARC81_MAGS_TTAVG



Cryogenic architecture







CERN

LHC Cryo-OP









The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010















The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010



Magnet cooling scheme







90ie

Overall strategy



- The cryogenic team has always been responsible for the definition of the heat loads, RnD for innovative aspects, architecture for cooling and distribution, process selection
- Commissioning of sub-systems were done one after each other, with performance assessment for all refrigerators and at least a type test of other sub-systems



The cryogenic system is operated transversally, from cooling capacity production to distribution and cooling of components (magnets, RF cavities, current leads)





Outline



- Introduction
- Cool-down
- Tuning
- Operation
- Nice features !
- Consolidations
- Summary





Single sector cool-down sequence



 From room temperature to 80K: Precooling with liquid nitrogen(LN2) 4700 tons of material to be cooled, 1200 tons of LN2 (64 trucks of 20 tons) Three weeks for the first sectors, a bit more than two weeks now

13/44

- From 80K to 20K: Cooldown with Helium turbines Almost three weeks for the first sectors, one week now
- From 20K to 4.5K: Continued with He turbines
 Filling some 10 tons of helium in the machine at this stage
 One to three weeks for the first sector, three days now
- From 4.2K to 1.9K: Cold compressors (15 mbar) Two weeks (+) for the first sector, two days now



TERN



18 kW @ 4.5 K Refrigerators



33 kW @ 50 K to 75 K - 23 kW @ 4.6 K to 20 K - 41 g/s liquefaction





The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010





LHC 18 kW @ 4.5 K Refrigerator Process cycle for Air Liquide

















125 g/s GHe from 15 mbar with 4 stages



CERN

The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010





Complex operation of hydro-dynamic compressor:

- high rotational speed: up to 800 Hz,
- reduced operation range at constant pressure ratio.



The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010





Outline



- Introduction
- Cool-down
- Tuning
- Operation
- Nice features !
- Consolidations
- Summary





Tuning one of 8 LHC sectors





From LHC Magnet String test





Functional analysis, Methodic and systematic approach, a bit of time ...



Changes on « supply conditions » may have an effect some hours later ...





Warm bump propagation







The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010

^e 27/44



The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010



LHC Cryogenic commissioning



- 2 K magnets in ARC
 - LT/EH at return modules
 - LT of SSS in ARC
 - EH at lowest point
 - EH of cold masses & beam screens
 - ⇒ Possible pump-down and cool-down of magnets, including tests with cold compressors

Principle set-up in 2007, foreseen during the (target =two) weeks after ARC magnets @ 4.5K,

- 6 weeks required per sector in 2008
- 2 weeks OK June 2009 for 1st time
- < 1 week per sector now</p>



- 4.5K stand-alone magnets
 - Cool-down to < 10K
 - Adjust instrumentation LT/EH
 - Control LHe at 50%
 - ⇒ Fill-up and boil-off to determine appropriate set-point

Electrical Feed Boxes (DFB's)

- Cool-down shield (if any)
- Cool-down leads at 150K, then cool-down phase separator
- Adjust instrumentation LT/EH
- Control LHe at nominal
- ⇒ Fill-up and boil-off to determine appropriate set-point
- \Rightarrow Tuning of Temp. control loops



Cryo conditions for powering



Cryo Start: set of conditions to allow powering of concerned sub-sector (rather strict = good stability of process)

Cryo Maintain: Few important conditions checking integrity of HW, with slow power abort in case this signal is lost





Outline



- Introduction
- Cool-down
- Tuning
- Operation
- Nice features !
- Consolidations
- Summary





Operation structure & approach



Cool-down Tuning

Per site, one experienced engineer to guide a local team of operators, with help of support teams (instrumentation, experts, controls)

• For machine controls (temperature, level, pressure), basic interlocks and simple PID loops with generic tools for fast orders, now completed with automated sequences

Once experienced

Since 2009, one operator in shift 24h/7d, more transverse structure site/CCC, procedures





Stability of temperature, 8 sectors



Getting closer to stable and "longer" periods below 2K







Availability



Based on LHC_Global_CryoMaintain signal per unit of time 90% +/- 5% 110 100 90 80 70 Availability 60 50 40 30 20 Powering tests 10 0 25-01-08- 15- 22- 01- 08- 15- 22- 29- 05- 12- 19- 26- 03- 10- 17- 24-Jan- Feb- Feb- Feb- Feb- Mar- Mar- Mar- Mar- Mar- Apr- Apr- Apr- Apr- May- May- May- May-

→ Daily "Global LHC Cryo" ■ weekly AVG ◆ Monthly AVG □ Scheduled Beams



CERN







Outline



- Introduction
- Cool-down
- Tuning
- Operation
- Nice features !
- Consolidations
- Summary





Confirmation of valid design, fabrication, installation and quality control

38/44



The 1st International Particle Accelerator Conference Kyoto, Japan / May 23-28, 2010

Calorimetry, principle









1.89

0

tO

2

3

Time [h]

CERN

5

5

0

Current

Calorimetry, results







CERN











Not valid for large transients, but an interesting feature for low beam loads, or validated fall-back scenario if serious problems with a refrigerator



Around 30% yearly losses, with efforts to identify and treat dominant effects



Global performance monitoring







CERN



Outline



- Introduction
- Cool-down
- Tuning
- Operation
- Nice features !
- Consolidations
- Summary





Consolidations



- Done before beams:
 - Electrical feedboxes: condensation, valves (continued)
 - Cryogenic control valve plugs (10% most critical)
 - Cryogenic instrumentation capillary for some magnets (80%)
 - Software simplification and tuning
- Launched, for increased operational reactivity:
 - Liquid helium storage capacity, to reach 110% of inventory
 - Critical spares (screw compressor casings, some turbines)
- Being considered:
 - Possibility to fully decouple adjacent sectors
 - Terminate correct (phase separation) and LHe measurements
- + Additional safety relief valves on magnet cryostats



Conclusion: Learning curves



Once understood, easyer to set automatisms and procedures !



Recovering main 4.5K Refrigerator stop



Tuning before HWC

Recovering 1.8K Unit





CERN



Summary



- LHC cryogenics is the largest, the longest and the most complex cryogenic system worldwide. We could achieve a reasonable availability (around 90%) so far with beams. This demonstrates that there are no big issues in concept, technology or global approach.
- Despite a step by step methodical approach and great involvement of key design/project engineers with experience, we had very hard time and lengthy commissioning to learn how to tune all these sub-systems together while permanently consolidating what was not conform. Could it be done differently, more smoothly (tests, simulators, software)?
- Cryogenics operation is now integrated in central control room with LHC main systems, but operated/supported independently (about 70 people)
- Few specific consolidations are foreseen in 2012, mostly for faster reactivity. And we have to prepare for continued gain in availability!

