


Status of Main Linac Cryomodule Development for Compact ERL Project



2012/5/21

IPAC12(@ New Orleans)

K. Umemori, K. Enami, T. Furuya, H. Sakai, M. Sato, K. Shinoe (KEK),
M. Sawamura (JAEA-ERL), E. Cenni (Sokendai)

Contents

- Compact ERL (cERL) project
- Main linac cryomodule
- 9-cell cavity development
- Input coupler
- HOM absorber
- Frequency tuner
- Schedule
- Summary


Compact ERL(cERL) project

Demonstrate the technologies needed for future multi-GeV class ERL, and show its beam performances

Parameters of the Compact ERL


| | Parameters |
|----------------------------|--|
| Beam energy | 35 - 200 MeV |
| Injection energy | 5 MeV |
| Average current | 10 - 100 mA |
| Acc. gradient (main linac) | 15 MV/m |
| Normalized emittance | 0.1 - 1 mm·mrad |
| Bunch length (rms) | 1 - 3 ps (usual) ~ 100 fs (with B.C.) |
| RF frequency | 1.3 GHz |

✳ red numbers are parameters for initial stage



ERL main linac cryomodule

- Accelerate 30MV by two 9-cell SC cavities
- Follow High Pressure Gas Safety Act in Japan
- CW operation (1.3GHz)
- Dynamic loss
 - Cavity : 25 W (for 2K) / cavity (@15MV/m)
 - Input coupler : 1.5 W (for 5K) / coupler
 - HOM absorber : 150W (for 80K)/ cavity
- Alignment
 - Target : 1mm across beam axis after cooling down
- Support
 - Cavity(2K) – 5K Support frame – Backbone(RT) – Central tower(RT)






Frequency tuner

- Slide-Jack tuner
- Piezo tuner
- Located on 4 K




9-cell cavity

- HOM damped cavity shape
- $E_{acc} = 15\text{-}20\text{ MV/m}$
- 100mA CW
- Energy recovery



ERL main linac 9-cell cavity

- Requirement
 - $E_{acc} = 15 \sim 20$ MV/m
 - $Q_0 > 1 \times 10^{10}$ at 15 MV/m
 - CW operation
- KEK-ERL model-2 cavity
 - Optimized cell shape for strong HOM damping
 - Large iris diameter, 80mm
 - $E_{peak}/E_{acc} = 3.0$
- Important to **suppress field emission**
 - reduce cryogenic loss
 - Less dark current




Results of vertical tests

WEPPC011
K. Umemori

Two 9-cell cavities were fabricated for cERL and vertical tests were performed two times for each cavity. (followings are results for 2nd tests)


ERL 9-cell #3 cavity

- Field reached to 25 MV/m
- No limitation up to 25 MV/m
- $Q > 1e10@15MV/m$
- Satisfied cERL specification
- X-ray onset around 14 MV/m



ERL 9-cell #4 cavity

- Field reached to 25 MV/m
- No limitation up to 25 MV/m
- $Q > 1e10@15MV/m$
- Satisfied cERL specification
- X-ray onset around 22 MV/m




Our approach against field emission

① What we did before vertical test

- Low current density, $32\text{mA}/\text{cm}^2$, EP to suppress remaining Sulfur
- Careful flange assembly using ionized gun and particle counter


② Diagnostics at vertical test

Example of X-ray mapping(#3 cav., 2nd VT, Eacc=22MV/m)



③ Calculation

MOPPC070
E. Cenni



Trying to deeply understand phenomena of field emission by calculation, using Fishpact


Input coupler

Requirement


- Max **20 kW standing wave** (Total reflection)
 - Compensate field fluctuation due to micrphonic detuning
 - No beam loading because of energy recovery
- $Q_{ext} = 1 \sim 4 \times 10^7$ and **variable coupling**

Coupler design


- **Coaxial type double windows** to avoid dust contamination into cavity
- HA997 ceramic
- 5K and 80K anchor
- N₂ gas cooling for inner conductor



Results of coupler conditioning for cERL





- Two input couplers for cERL were fabricated.
- Conditioning by traveling wave using 300kW klystron
- RF power up to 100kW (pulse)
40kW(CW)
- Keep 40kW CW, 4hours
- Highest Temp: bellows of inner conductor ($\Delta T \sim 60$ degree, OK)



HOM absorber


- HOM absorber located on **80K** region
- Heat load of **150W/cavity** is estimated for 100 + 100mA electron beam with 3ps bunch length
- New IB004 ferrite is **HIP** bonded on Cu pipe
- Outside: bellows, Inside: **Comb-type RF bridge**



Test of HOM absorber using prototypes

Cooling test at 80K


(using prototype without ferrite)



- Cooling ability against 150W HOMs was tested under 80K condition.
- Generally, it went well.
- Contact at the tip or side of Comb-structure could give large thermal conductance.
- **Modification for Comb-shape**

Heat cycle test (RT – 80K)

(using prototype with ferrite)




- Heat cycles, between RT to 80K, were applied to prototype HOM absorber.
- Some cracks were observed
- **Modification of ferrite structure, especially taper part, which close to the boundary section.**


⇒ **Modified version of HOM dampers for cERL are almost fabricated.**

Frequency tuner


- Tuner system basically developed for STF-BL cavity
- Mechanical tuner for course tuning
 - Slide-Jack tuner
 - Stroke 3mm → 900kHz frequency change
- Piezo tuner for fine tuning
 - Stroke 80um at RT
 - ⇒ ~8um at 4K
 - ~4um for cavity
- Piezo tuner compensate microphonic detuning
- $QL = 2 \times 10^7$ ($\Delta f = 65$ Hz)
- Two frequency tuners were fabricated for cERL




Performance test of prototype mechanical tuner at RT




Stroke is OK (3mm)




Max. backlash ~0.4um




Performance test of prototype piezo tuner at RT



Stroke is OK (80um)




Reproducibility of hysteresis curve is fine



Status and future plan




Cavity: He jacket was mounted



HOM damper: fabricated
✂ picture: before bellows and flanges were attached.



Input coupler:
Conditioning finished



Frequency tuner: fabricated

- Almost all components are ready
- Cryomodule assembly this summer
- Cooling test and first high power test within this year
- ERL beam will come to main linac next year

ERL Development Building




2K refrigerator system



300 kW klystron

30 kW klystron and IOT



Concrete shield



Cleanroom for module assembly



Summary

- cERL is under construction in KEK.
- Development and fabrication of components for cERL main linac cryomodule has been finished.
 - Two 9-cell cavities were fabricated. They successfully reached to > 25 MV/m. He jackets were mounted on them.
 - Two sets of input couplers were prepared. They successfully passed > 100 kW pulse/40 kW CW traveling wave.
 - HOM absorbers are almost fabricated.
 - Two sets of frequency tuners were fabricated.
- Cryomodule will be assembled in this summer.
- Cooling test and high power test will be scheduled in this year.
- Beam operation will start next year.