

# Producing Medical Isotopes Using X-rays

M. de Jong


Canadian Light Source

2012 May 24

# The Goal: $^{99m}\text{Tc}$

$^{99m}\text{Tc}$ :


- 140 keV  $\gamma$ -ray, 6 hr half life
- Used for ~90 % of nuclear medicine diagnostic imaging
- Canada – about 5500 procedures per day




# Current Production Method

Mo-99 via U-235 fission:

- Mo-99 at peak of fission mass distribution
- ~ 6 % of fissions yield Mo-99
- Half life of 66 hrs



# Current Production Method



# NRCan 2010 Call for Proposals for Accelerator Production $^{99m}\text{Tc}$


- Non-reactor-based Isotope Supply contribution Program (NISP – announced 2010 June 2)
  - \$35M total funds available
  - Particle accelerator production of  $^{99}\text{Mo}$  or  $^{99m}\text{Tc}$
  - Demonstrate “commercial-scale” production
  - Two approaches funded:
    - Electron linear accelerator (linac) production of  $^{99}\text{Mo}$
    - Proton cyclotron production of  $^{99m}\text{Tc}$
  - Covers a maximum of 90% of total costs
  - NRCan funding ended 2012 March 31
- Four projects funded:
  - two linac-based (CLSI and PIPE)
  - two cyclotron-based (ACSI and TRIUMF)

# Linac Production of $^{99}\text{Mo}$


- Photo-nuclear reaction on  $^{100}\text{Mo}$ :
  - $^{100}\text{Mo} (\gamma, n) ^{99}\text{Mo}$
- Natural Mo about 10 %  $^{100}\text{Mo}$
- Available at enrichments of > 95 %
- Known for more than 40 years
- Photons produced via Bremsstrahlung using high-energy electrons from linear accelerator  $\Rightarrow$  high-energy X-rays



Exploit “giant dipole resonance” around 15 MeV in most heavy nuclei



# Mo-99 decay and Tc-99m production



# Production Capacity Needed

- |   |  |
|---|--|
| <ul style="list-style-type: none"><li>• For Canada, 5,500 Tc-99m procedures per day</li><li>• Each procedure requires 10 - 30 mCi; thus 110 Ci/day of Tc-99m</li><li>• Every 24 hrs, can elute ~100 % of remaining Mo-99 activity</li></ul> | <ul style="list-style-type: none"><li>• So need to replace 22 Ci/ day of Mo-99</li><li>• From EoB to delivery can be less than 1 <math>t_{1/2}</math> (~ 3 days)</li><li>• Conclude 44 Ci/day, EoB, should be adequate</li></ul> |
|---|--|

- ***Certainly optimistic because of other losses***
- ***Mo-99 and Tc-99m decay whether it's used or not!***



# Why Electron Linear Accelerators?

- Disadvantages:
  - Lower cross-sections (electromagnetic vs nuclear interactions)
  - Fewer reaction channels, especially for positron emitters
- Advantages:
  - Photons are more penetrating => thicker targets, windows
  - Photons are “cheap”
  - Electron linacs are generally simpler and more reliable
  - Fewer reaction channels
    - Fewer undesired isotopes
    - Less radioactive waste
- Relatively unexplored option!

# Other Reaction Channels

- Arrows show ( $\gamma$ , n) reactions on Mo isotopes
- ( $\gamma$ , p) produces Nb isotopes which decay to Mo
- Trace amounts of  $^{95}\text{Nb}$  and  $^{94}\text{Nb}$  may arise in time



	EC	EC	5.52	1.88	12.7	12.6	17.0	31.6	$\beta^-$	
<b>Tc92</b> 4.23 m (8)+	<b>Tc93</b> 2.75 h 9/2+	<b>Tc94</b> 293 m 7+	<b>Tc95</b> 20.0 h 9/2+	<b>Tc96</b> 4.28 d 7+	<b>Tc97</b> 2.6E6 y 9/2+	<b>Tc98</b> 4.2E+6 y (6)+	<b>Tc99</b> 2.11E+5 y 9/2+	<b>Tc100</b> 15.8 s 1+	<b>Tc101</b> 14.22 m (9/2)+	<b>Tc102</b> 5.28 s 1+
C	EC	EC	EC	EC	EC	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	
<b>Mo91</b> 15.49 m 9/2+	<b>Mo92</b> 0+	<b>Mo93</b> 4.0E+3 y 5/2+	<b>Mo94</b> 0+	<b>Mo95</b> 5/2+	<b>Mo96</b> 0+	<b>Mo97</b> 5/2+	<b>Mo98</b> 0+	<b>Mo99</b> 65.94 h 1/2+	<b>Mo100</b> 1.2E19 y 0+	<b>Mo101</b> 14.61 m 1/2+
C	14.84	EC	9.25	15.92	16.68	9.55	24.13	$\beta^-$	$\beta\beta$ 9.63	$\beta^-$
<b>Nb90</b> 14.60 h 8+	<b>Nb91</b> 680 y 9/2+	<b>Nb92</b> 3.47E+7 y (7)+	<b>Nb93</b> 9/2+	<b>Nb94</b> 2.03E+4 y (6)+	<b>Nb95</b> 34.975 d 9/2+	<b>Nb96</b> 23.35 h 6+	<b>Nb97</b> 72.1 m 9/2+	<b>Nb98</b> 2.86 s 1+	<b>Nb99</b> 15.0 s 9/2+	<b>Nb100</b> 1.5 s 1+
C	EC	EC, $\beta^-$	100	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$
<b>Zr89</b> 78.41 h 9/2+	<b>Zr90</b> 0+	<b>Zr91</b> 5/2+	<b>Zr92</b> 0+	<b>Zr93</b> 1.53E+6 y 5/2+	<b>Zr94</b> 0+	<b>Zr95</b> 64.02 d 5/2+	<b>Zr96</b> 3.9E19 y 0+	<b>Zr97</b> 16.91 h 1/2+	<b>Zr98</b> 30.7 s 0+	<b>Zr99</b> 2.1 s (1/2+)
C	51.45	11.22	17.15	$\beta^-$	17.38	$\beta^-$	$\beta^-$ 2.90	$\beta^-$	$\beta^-$	$\beta^-$
<b>Y88</b> 106.65 d 4-	<b>Y89</b> 1/2-	<b>Y90</b> 64.10 h 2-	<b>Y91</b> 58.51 d 1/2-	<b>Y92</b> 3.54 h 2-	<b>Y93</b> 10.18 h 1/2-	<b>Y94</b> 18.7 m 2-	<b>Y95</b> 10.3 m 1/2-	<b>Y96</b> 5.34 s 0-	<b>Y97</b> 3.75 s (1/2-)	<b>Y98</b> 0.548 s (0)-
C	100	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta^-$	$\beta\text{-n}$	$\beta\text{-n}$

# CLS Project Scope

- Fabrication methods for  $^{100}\text{Mo}$  targets
- Low-power testing ( $< 3\text{kW}$ ) of the bremsstrahlung converter and target design to validate production yield estimates
- Evaluation of the quality of the  $^{99}\text{Mo}$  produced and the  $^{99\text{m}}\text{Tc}$  separation process required for radio-pharmaceutical production
- Design and fabrication of high-power ( $>20\text{ kW}$ ) converter and target assembly
- Installation of a high-power 35 MeV industrial electron linac at CLS
- Development of a suitable recycling process to recover the  $^{100}\text{Mo}$  after irradiation and  $^{99\text{m}}\text{Tc}$  separation for future targets


# NRC (Ottawa) - INMS

- Proof-of-concept work using 35 MeV, 2 kW linac at INMS




# NRC (Ottawa) - INMS


Used automated separator to extract  $^{99m}\text{Tc}$  from  $\text{Na}_2\text{MoO}_4$  solution.



- $\text{Na}[^{99\text{m}}\text{TcO}_4]$  is clinically equivalent in:
  - Radio-purity
  - No Al contamination
  - pH 5 – 9
  - Sterility
  - Radio-chemical purity
  - Pyrogen free
- Meets all USP tests



- Performed pre-clinical trial comparing linac  $^{99m}\text{Tc}$  to standard Mo-generator
- Used heart scan comparison on three rats
  - Heart scans comparable
  - Detected more Tc in kidneys with linac-sourced  $^{99m}\text{Tc}$
  - Identified problem in pH adjustment process in separator



# NRC + Winnipeg HSC


- Three  $^{100}\text{Mo}$  irradiations each yielding  $\sim 6$  GBq ( $\sim 160$  mCi)  $^{99}\text{Mo}$ 
  - Performed at NRC linac
  - $\sim 12$  hours at 3 kW, 35 MeV
- Targets were shipped Winnipeg HSC Radiopharmaceutical Research Group for evaluation of  $^{99}\text{Mo}$  and  $^{99\text{m}}\text{Tc}$
- $^{99}\text{Mo}$  targets were dissolved, and  $^{99\text{m}}\text{Tc}$  extracted ( $\sim 90\%$  efficiency) using automated solvent-solvent extraction generator (developed at HSC/CCMB)
  - $^{99\text{m}}\text{Tc}$ -pertechnetate passed standard QC for Mo-breakthrough, alumina and pH up to 7 days after delivery
  - $^{99\text{m}}\text{Tc}$ -labelled MDP, DTPA, MIBI, and MAA were produced
  - MDP and DTPA consistently passed radiochemical purity, pH and stability tests
  - MIBI and MAA failed one or more tests, probably due to low level of activity at time of production




# CLS Work

- Install 35 MeV, 40 kW, industrial linac in an existing underground experimental hall
  - Three 1.2m S-band on-axis coupled standing-wave sections
  - Three modulators + klystrons 5MW peak, high-duty factor
  - 60 kV thermionic gun
- Design & build bremsstrahlung converter and target holder
  - must handle > 20 kW beam power
  - modest remote handling requirements
  - evaluate maximum power handling of converter and Mo-100 targets
- Install nuclear substance laboratory to support target manufacture and recycling
- Develop plan to support post-project activities
- Winnipeg HSC to evaluate production of  $^{99}\text{Mo}$  from CLS


# Location of Isotope Linac at CLS




# Layout of Isotope Production Facility




# Isotope Linac and Target Assembly




# Isotope Production Electron Linac



# Converter and Target Holder




# Photon Shower (EGS++)



Electrons and photons above 14 MeV shown

# Mo-99 Specific Activity after 24 hours

MCNP5: 40.0 kW 35.0 MeV for 24.00 hours - Bsph\_Femix\_s0.09r0.75E9.58





# Future for CLS Isotope Project

- Start commissioning linac this June, with first irradiations in August
- Work to end of current project (2013 March 31)
  - Demonstrate initial ~2.5 – 5 Ci (~100 – 200 GBq) per day production rate
  - Perform full suite of analysis tests on  $^{99}\text{Mo}$  and extracted  $^{99\text{m}}\text{Tc}$  at Winnipeg HSC
  - Continue with refining the processes and improving production rate for more than 20 Ci (800 GBq) per day at full power
- Explore commercialization options to manage the future development
  - Construct additional facilities elsewhere in Canada
  - Investigate possible production of other medical isotopes
- Obtain Health Canada approvals for this  $^{99}\text{Mo}/^{99\text{m}}\text{Tc}$  production method
- Relocate present linac as a production facility
  - Possibly locate with the new PET cyclotron facility at U of Saskatchewan
  - Design with infrastructure suitable for routine production

# Project Team

- Canadian Light Source Inc. (lead)
- National Research Council (INMS and IMI)
- Winnipeg Health Sciences Centre (U of Manitoba)
- Mevex Corp.
- Consultants:
  - retirees from AECL, Dupont, CNSC
  - DoyleTech Inc. – business case

## With support from:

- University of Ottawa Heart Institute
- NorthStar Medical Radioisotopes LLC
- University Health Network (U of Toronto)
- Acsion Ltd. (member of PIPE)

## Project Funding:

- Natural Resources Canada (\$10M)
- Province of Saskatchewan (\$2M)