


# Beam Commissioning and Operation of New Linac Injector for RIKEN RI Beam Factory



RIKEN Nishina Center

Kazunari Yamada, K. Suda, S. Arai, M. Fujimaki, T. Fujinawa, H. Fujisawa, N. Fukunishi, Y. Higurashi, E. Ikezawa, H. Imao, O. Kamigaito, M. Kase, M. Komiyama, K. Kumagai, T. Maie, T. Nakagawa, J. Ohnishi, H. Okuno, N. Sakamoto, H. Watanabe, T. Watanabe, Y. Watanabe, H. Yamasawa, Y. Sato (J-PARC center, KEK), A. Goto (NIRS)


# Subject of RIKEN Nishina Center

- RI beam factory (RIBF)

Producing the world's most intense RI beams over the entire range of atomic masses by powerful heavy ion beams accelerated up to  $v/c \approx 0.7$  (U beam has a first priority)

- Synthesis of super-heavy elements (SHEs)


RILAC plays a role of  $\left\{ \begin{array}{l} \text{injector for RIBF experiment} \\ \text{accelerator for SHE research}^* \end{array} \right. \Rightarrow$  Function conflicting



# Role of new linac injector RILAC2

- Independent operation of RIBF experiments and SHE research
- Intensity upgrade of U, Xe beams

## Maximum beam intensity at RIBF(pnA)



d,  $\alpha$ ,  $^{18}\text{O}$  beam (RILAC-RRC-IRC-SRC)

1 p $\mu$ A

( $6 \times 10^{12}$  particles/s, max. 6.2 kW)

⇒ Attained a goal of RIBF

$^{48}\text{Ca}$  beam (RILAC-RRC-IRC-SRC)

230 pnA (3.8 kW)

⇒ Best in the world

$^{238}\text{U}$  beam (RILAC-RRC-fRC-IRC-SRC)

0.8 pnA (2009/12)

⇒ **Insufficient**

- Deficiency of beam current from an ion source
- Deterioration of RILAC (over 30 years old)  
→ vacuum leak, rf instability

# Key features of RILAC2

New SC-ECRIS

⇒ Increase beam intensity

Required RF stability

$$\Delta V < \pm 0.1\%$$

$$\Delta \phi < \pm 0.1^\circ$$


Higher vacuum level  $\sim 10^{-6}$  Pa

⇒ Improve transmission


Compact equipments

$m/q$  ratio  $\sim 7$   
( $^{238}\text{U}^{35+}$ ,  $^{124}\text{Xe}^{19+,20+}$ )  
 $\sim 670$  keV/u to RRC

In CW mode



# Key features of RILAC2



# CW 4-rod RFQ linac

Recycled a 4-rod RFQ linac kindly provided by Kyoto University.

33.8 MHz

Original

36.5 MHz


Vane

Modified





Beam

2220 mm



Frequency	36.5 MHz
Duty	100 %
$m/q$ ratio	7
Input energy	3.28 keV/u
Output energy	100.3 keV/u
Input emittance	$200\pi$ mm·mrad
Vane length	225.6 cm
Intervane voltage	42.0 kV
Mean aperture ( $r_0$ )	8.0 mm
Max. modulation ( $m$ )	2.35
Focusing strength ( $B$ )	6.785
Final synchronous phase	$-29.6^\circ$
Unloaded Q	5000
Shunt impedance	$\sim 50$ k $\Omega$
Required rf power	$\sim 18$ kW




Resonant frequency  $f_0$  : 33.8 MHz  $\rightarrow$  36.5 MHz  
 $m/q \approx 7$  ions accelerated to 100 keV/u without changing vane electrodes.  
 Unloaded Q : 5400  $\rightarrow$  5000 (measured)

# Drift-tube linacs


- Low- $\beta$  : 0.015~0.038
- CW-QWR, 36.5 MHz
- Directly coupled with rf amplifier for saving space and cost

Frequency (Resonator)  $\leftrightarrow$  Load impedance (coupler, amp.)

Carefully set the target frequency




DTL1 model of MWS



	DTL1	DTL2	DLT3
Frequency (MHz)	36.5	36.5	36.5
Duty (%)	100	100	100
<i>m/q</i> ratio	7	7	7
Input energy (keV/u)	100	220	450
Output energy (keV/u)	220	450	680
Length (cm)	80	110	130
Height (mm)	1320	1429	1890
Gap number	10	10	8
Gap length (mm)	20	50	65
Gap voltage (kV)	110	210	260
Drift tube aperture (mm)	17.5	17.5	17.5
Peak surface field (MV/m)	8.9	9.4	9.7
Synchronous phase (deg.)	-25	-25	-25


# RF voltage stability and phase stability

## RF fluctuation of RILAC2 over one day



Voltage stability :  $< \pm 0.1\%$

Phase stability :  $\sim \pm 0.1^\circ$




Sufficient to attain the target values





# History of RILAC2 beam commissioning

Successfully commissioned on schedule



# First beam of RILAC2



Started on December 21, 2010

Succeeded in accelerating the first beam on day 1.

Beam transmission efficiency ~75%


Beam profile measured by a wire scanner.

# Decision of operation parameters


Started with parameters of designed value.

Parameters were made fine adjustments to increase beam transmission by measuring the beam current.

RFQ voltage setting vs. beam current downstream of bending magnet.



DTL3 rf phase setting vs. beam current downstream of bending magnet.



Parameters are consistent with designed value.


# Beam loss caused by electron capture reactions

Loss of the uranium beam occurred in each section between the bending magnets of HEBT due to low vacuum level.

→ about 10% in each section

Example : a section in HEBT

$\sim 5 \times 10^{-5}$  Pa Aug. 29, 2011




Five times improved



by appending a TMP



$\sim 1 \times 10^{-5}$  Pa Apr. 27, 2012



# Beam transmission efficiency


Improved by optimizing rf parameters and improving the vacuum level

Typical  $4\sigma$  emittance of uranium beam from the SC-ECRIS.



$^{124}\text{Xe}$  : 75% (2010/12)  $\Rightarrow$  78% (2011/05)

$^{238}\text{U}$  : 74% (2011/08)  $\Rightarrow$  80% (2012/04)




# Beam energy matching



Fine tuning of injection energy to RRC is required.  
Beam energy from RILAC2 was decided by time-of-flight measurement and adjusted so as to obtain an optimal turn pattern of RRC.

RRC turn pattern,  $^{124}\text{Xe}$  beam (2011/05)

$1/(36.5 \text{ MHz})$



Timing spectra measured by plastic scintillators




Optimal energy  
669 keV/u

# Deployment of RILAC2 for RIBF experiment

RILAC2 successfully started supplying beams from October 2011.

- 2011/10/5 ~10/6 : First experiment using RILAC2 ( $^{238}\text{U}$  10.75 MeV/u)
- 2011/10/9 ~12/8 : First RIBF experiment ( $^{238}\text{U}$  345 MeV/u)
- 2011/12/8 ~12/19 : RIBF experiment ( $^{124}\text{Xe}$  345 MeV/u)

## Maximum beam intensity (pnA)



$^{238}\text{U}$  beam (~25  $\mu\text{A}$ @IS)

0.8 pnA  $\Rightarrow$  3.5 pnA

$^{124}\text{Xe}$  beam (~60  $\mu\text{A}$ @IS)

15.4 pnA

Much higher intensity are expected

Beam break time resulting from downtime of RILAC2

$\Rightarrow$  < 0.3% of the total scheduled beam time

# Summary

- New linac injector RILAC2 has been successfully commissioned in 2011.
- Independent operation of RIBF experiments and the SHEs research becomes possible.

Beam time schedule

										November/11月 2011 (revised on Nov/25)																																																	
Proposal Number	Experiment Description	Course	Particle	Energy (MeV/u)	Intensity	Time frame (days)	Start time	End time		1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30																				
<b>RILAC single op.</b>																																																											
NP0702-LIBAC12	森田 浩介 H. Morita	GARIS	<sup>70</sup> Zn	5.5	nan		17:00	18:00																																																			
<b>AVF single op.</b>																																																											
NP1000-AVF09	Nuyen Ngoc Day (S. Hongo)	CRIB	<sup>28</sup> Ne	6.0	20000 pps	17	9:00	11:00																																																			
NP0702-AVF04	岡田 安夫 H. Okada	CRIB	Ar	10.4	20000 pps	2	17:00	18:00																																																			
宇生 康樹11	奥野 善晴 S. Okuno	E7B	Ca	6.5	10000 pps	0.5	17:00	18:00																																																			
栗山 英樹11	大田 善晴 R. Ota	E7B	Ca	6.5	10000 pps	0.5	17:00	18:00																																																			
<b>RIBF</b>																																																											
MS11	久保 聡 T. Kubo	BigRIPS	<sup>238</sup> U	34.5	5 beam pps	14	9:00	11:00																																																			
NP0702-RIBF03	洲田 健一郎 K. Yoneda	BigRIPS	<sup>238</sup> U	34.5	5 beam pps	10	9:00	12:00																																																			
NP0702-RIBF11	斎藤 保二 S. Saitoh	BigRIPS	<sup>238</sup> U	34.5	5 beam pps																																																						
BigRIPS Contact										前木 宏 H. Suzuki										前木 宏 H. Suzuki																																							
連絡先 contact										中井 K. Inoue										渡邊 孝 Watanabe										須野 Sudo										佐藤 太 K. Sato										高橋 敏									

← SHEs research

← RIBF experiments


- Intensity of very heavy ions such as U and Xe are increasing reliably.



# Refs

# RI beam factory (RIBF)

- To produce the world's most intense RI beams over the entire range of atomic masses using heavy ion beam accelerated up to  $v/c \approx 0.7$




Entire view of RIBF

# RI beam factory (RIBF)

- To produce the world's most intense RI beams over the entire range of atomic masses using heavy ion beam accelerated up to  $v/c \approx 0.7$

U, Xe acceleration mode :  $E = 345 \text{ MeV/u}$



# RI beam factory (RIBF)

- To produce the world's most intense RI beams over the entire range of atomic masses using heavy ion beam accelerated up to  $v/c \approx 0.7$

## Mode for synthesis of super-heavy elements (SHEs)


M. Kase *et al.*, THPPP040.

RILAC: RIKEN  
heavy ion linac,  
(1981)

RIBF injector  
GARIS } shared

GARIS spectrometer  
for SHE research

K. Morita *et al.*, J. Phys. Soc. Jpn. 78, 064201 (2009).



H. Imao *et al.*, THPPP084.

Entire view of RIBF

# RI beam factory (RIBF)

- To produce the world's most intense RI beams over the entire range of atomic masses using heavy ion beam accelerated up to  $v/c \approx 0.7$

Independent operation of RIBF experiments and SHE research


RILAC2: New linac injector for RIBF

RILAC: RIKEN heavy ion linac, (1981)

RIBF injector  
GARIS } shared

GARIS spectrometer for SHE research


K. Morita *et al.*, J. Phys. Soc. Jpn. 78, 064201 (2009).



# Ring cyclotrons



fIRC



IRC



SRC

	RRC	fIRC	IRC	SRC
K-number (MeV)	540	570	980	2600
Sector magnets	4	4	4	6
Velocity gain	4.0	2.1	1.5	1.5
Trim coils (/sector)	26	10	20	4(SC) 22(NC)
RF resonators	2	2+FT	2+FT	4+FT
Frequency range (MHz)	18-38	54.75	18-38	18-38


SC = superconducting

NC = normal conducting


FT = flat-top resonator

# Acceleration mode at RIBF


Variable-energy mode :  
 $\alpha$ ,  $^{18}\text{O}$ ,  $^{48}\text{Ca}$ ,  $^{86}\text{Kr}$   
 up to 400 MeV/u @SRC




Fixed-energy mode :  
 $^{238}\text{U}$ ,  $^{124}\text{Xe}$   
 345 MeV/u @SRC



Light ion mode :  
 $\text{Pol-d}$ ,  $^{14}\text{N}$   
 250-440 MeV/u @SRC



# Present acceleration mode at RIBF





# Influence of RF instability

0.1° phase difference on DTL3  $\Rightarrow$  0.08% voltage difference on DTL3

$\Delta V$  0.1% on DTL3

$\rightarrow \Delta\phi \sim 4^\circ$  @ injection of RRC

$\rightarrow \Delta r \sim 3.7$  mm @ extraction of RRC

(Turn separation @ extraction of RRC : 6.7 mm)



Critical degradation of extraction efficiency


# Modification of RFQ

Put a block tuner into every gap between the posts  
→ Size of block was optimized by 3D EM calculation (MWS) and cold-model test



Aluminum test block  
(Cold model)

$f_0$ : 36.5 MHz  
Block size:  
240 mm × 260 mm × 114 mm





RFQ model for MWS calculation  
(7 M meshes)

Measured (original RFQ)  
 $f_0$ : 33.5 MHz [not modulated vane]  
 $f_0$ : 33.8 MHz [modulated vane]


Calculation (not modulated vane)  
 $f_0$ : 33.2 MHz (-0.9%) [w/o block]  
 $f_0$ : 36.0 MHz (-1.5%) [with block]

Required rf power @ 42kV: 17.5 kW (80%-Q)  
Rf amplifier : 40 kW max.

# Detailed design of block tuner



- Heat load of five block tuners :  $\sim 2.1 \text{ kW@42 kV}$
- Cooling of block (assumed as  $\phi 11.6 \text{ mm}$ , 4.85 m, 50 bend)  
 Cooling water 18 L/min (inlet 0.5 MPa, outlet 0.2 MPa)  
 Water temp.  $\sim 2 \text{ }^\circ\text{C}$  up, inner surface temp.  $\sim 1 \text{ }^\circ\text{C}$  up
- Weight saving : 64 kg  $\rightarrow$  33 kg
- 3D CAD drawing (Autodesk inventor)




Block tuner made of oxygen free copper



# Test of RFQ linac

02 Sep, 2010 @ AVF cyclotron vault


Block tuner




Connection pipe for cooling water



Inner construct of RFQ linac




S11 result of RFQ



Frequency : 36.5 MHz  
Loaded-Q : 2500 (S21)

High power test (pulse)



High power test (CW)






- Assembly : performed in March 2010
- Vacuum test : acceptable ( $< 8 \times 10^{-6}$  Pa)
- Resonant frequency : corresponds to 36.5 MHz
- Low-level circuits & rf amplifier : ready
- High power test : **achieved the rated voltage of 42 kV!!**

# Drift tube linac

- DTL1, 2 : new fabrication
- DTL3 : modify CSM-D1 tank
- CW-QWR
- Low- $\beta$  : 0.015~0.038
- 1.1 ~ 1.2 Kilpatrick
- Direct coupling scheme for saving cost and space

## Kilpatrick limit at tens MHz




	DTL1	DTL2	DTL3
Frequency (MHz)	36.5	36.5	36.5
Duty (%)	100	100	100
$m/q$ ratio	7	7	7
Input energy (keV/u)	100	220	450
Output energy (keV/u)	220	450	680
Length (cm)	80	110	130
Height (mm)	1320	1429	1890
Gap number	10	10	8
Gap length (mm)	20	50	65
Gap voltage (kV)	110	210	260
Drift tube aperture (mm)	17.5	17.5	17.5
Peak surface field (MV/m)	8.9	9.4	9.7
Synchronous phase (deg.)	-25	-25	-25


Surface current of DTL1 (MWS : 10M meshes)

# Design of DTL tanks

- Direct coupling scheme  
→ resonant frequency decreases because of their series/parallel capacitance
- Target frequency was adopted such that this decrease was compensated
- The decrease was estimated to be -225 kHz by comparing measurement and MWS calculation






DTL3 model for MWS



coupler@156.2 mm  
 Shorting plate [mm]  
 +120.0° +105.0° +90.0° +75.0° +60.0°  
 +135.0° +0.50j +0.80j +1.00j +1.25j +1.50j  
 +150.0° +0.25j +0.50j +0.75j +1.00j +1.25j  
 +165.0° +0.10j +0.25j +0.50j +0.75j +1.00j  
 +180.0° -0.10j -0.25j -0.50j -0.75j -1.00j  
 -165.0° -0.25j -0.50j -0.75j -1.00j -1.25j  
 -150.0° -0.50j -0.75j -1.00j -1.25j -1.50j  
 -135.0° -0.80j -1.00j -1.25j -1.50j -1.75j  
 -120.0° -1.00j -1.25j -1.50j -1.75j -2.00j  
 -105.0° -1.25j -1.50j -1.75j -2.00j -2.25j  
 -90.0° -1.50j -1.75j -2.00j -2.25j -2.50j  
 -75.0° -1.75j -2.00j -2.25j -2.50j -2.75j  
 -60.0° -2.00j -2.25j -2.50j -2.75j -3.00j  
 -45.0° -2.25j -2.50j -2.75j -3.00j -3.25j  
 -30.0° -2.50j -2.75j -3.00j -3.25j -3.50j  
 -15.0° -2.75j -3.00j -3.25j -3.50j -3.75j  
 +15.0° -3.00j -3.25j -3.50j -3.75j -4.00j  
 +30.0° -3.25j -3.50j -3.75j -4.00j -4.25j  
 +45.0° -3.50j -3.75j -4.00j -4.25j -4.50j  
 +60.0° -3.75j -4.00j -4.25j -4.50j -4.75j  
 +75.0° -4.00j -4.25j -4.50j -4.75j -5.00j  
 +90.0° -4.25j -4.50j -4.75j -5.00j -5.25j  
 +105.0° -4.50j -4.75j -5.00j -5.25j -5.50j  
 +120.0° -4.75j -5.00j -5.25j -5.50j -5.75j

Rs: 1.77 MΩ  
 Qo: 20000(100.0)  
 Cc: 0.46 pF  
 Zw/L : 50.00 Ω/1.700 m




# Test result of DTL tanks


For three tanks

- Resonant frequency : conformable to designed value 36.5 MHz
- High power test : achieved the rated voltage


Frequency response of DTL1



Field distribution of DTL1




Coupling of DTL1 (φ170mm coupler)




Measured characteristics

	DTL1	DTL2	DTL3
Frequency range (MHz)	35.64—36.87	35.5—36.8	36.25—36.69
Unloaded Q	13000	20350	22500
Shunt impedance (MΩ/gap)	0.94	1.65	1.72
Effective shunt impedance (MΩ/m)	135	176	102
Required rf power (kW)	6.5	13.4	19.6



Pick-up signal




Perturbation measurement

# Rebunchers

## REB1


- QWR
- $f_0$  : 36.5 MHz
- $\beta$  : 0.0147,  $\beta\lambda/2$  : 60 mm
- Rated voltage : 100 kV total
- Gap number : 4
- Gap length : 20 mm, 10 mm
- Drift tube aperture : 17.5 mm
- $Q_0$  : 8500 (MWS)
- Shunt impedance : 550 k $\Omega$  (MWS)
- Required rf power : 570 W (100%-Q)
- Power amp. : 1 kW max.



REB1 design

## REB2

- QWR
- $f_0$  : 36.5 MHz
- $\beta$  : 0.0382,  $\beta\lambda/2$  : 156 mm
- Rated voltage : 200 kV total
- Gap number : 4
- Gap length : 20 mm
- Drift tube aperture : 20 mm
- $Q_0$  : 11400 (MWS)
- Shunt impedance : 950 k $\Omega$  (MWS)
- Required rf power : 1500 W (100%-Q)
- Power amp. : 3 kW max.



REB2 design




# Pictures : fabrication and installation



DTL1 tank



DTL2 tank




DTL1 top flange




DTL1 coupler




Inside of DTL1




Inside of DTL1



Inside of DTL3



Power amp.



@AVF cyclotron vault

DTL3

DTL2

DTL1

REB1

RFQ linac

# History of beam commissioning

## RILAC2 beam commissioning

Date	Machine studies, events
Dec. 17, 2010	Construction of RILAC2 was finished.
Dec. 21, 2010	Beam commissioning was begun using $^{124}\text{Xe}^{20+}$ . <b>First beam.</b>
Dec. 22, 2010	RILAC2 solo acceleration test using $^{124}\text{Xe}^{20+}$ .
Jan. 21, 2011	RILAC2 solo acceleration test using $^{124}\text{Xe}^{20+}$ .
Jan. 24 — Feb. 11, 2011	Installation and test of a rebuncher2.
Feb. 14 — 16, 2011	RILAC2-RRC-fRC acceleration test using $^{124}\text{Xe}$ .
May. 7 — 21, 2011	RILAC2-RRC-fRC-IRC-SRC, <b><math>^{124}\text{Xe}</math> beam was extracted from SRC.</b>
Jun. 15 — 30, 2011	RILAC2-RRC-fRC, first acceleration test of $^{238}\text{U}$ . Test of charge stripper.
Aug. 26 — 29, 2011	RILAC2-RRC acceleration test using $^{238}\text{U}$ .
Sep. 24 — 26, 2011	RILAC2-RRC acceleration test using $^{238}\text{U}$ . Test of charge stripper.
Oct. 5, 2011 —	Supplying beams for experiments.