**2012 International Particle Accelerator Conference** 

### PLS-II (Upgrade of PLS)Commissioning

### Seunghwan Shin for the PLS-II commissioning team

#### 2012. 5. 22



### Project and budget @ PAL

XFEL (On going) 400 M\$

Human

PLS-II (Completed) 100 M\$



# **PAL : Chronology**

#### I. PLS

Project started	Apr. 1	1988
<ul> <li>Ground-breaking</li> </ul>	Apr. 1	1991
• 2-GeV Linac commissioning	Jun. 30	1994
<ul> <li>Storage ring commissioning</li> </ul>	Dec. 24	1994
User service started	Sep. 1	<u> 1995</u>
1st PLS Upgrade Complete		
$\checkmark$ Energy ramping to 2.5 GeV	Sep. 1	2000
✓ 2.5-GeV injection	Nov. 1	2002

#### II. 2<sup>nd</sup> Major Upgrade of the PLS (PLS-II)

<ul> <li>User service started</li> </ul>	Mar.	2012
3.0 GeV PLS-II Upgrade Complete	Dec.	2011
• 3.0 GeV PLS-II Upgrade begin	Jan.	2009

#### III. PAL-XFEL Going On

10GeV Linac Based 0.1 nm x-ray FEL (2011 ~ )



### PLS-II upgrade project ('09~'11)



# Commissioning team and contributor

#### PAL

- S. Kwon
- D-T. Kim
- D-E. Kim
- M. Kim
- S-H. Kim
- S-C. Kim
- J. Kim
- C. Kim
- B. Park
- S-S. Park
- S-J. Park
- E. Park
- Y. Son
- J. Yoon
- B. Lee
- E. Lee

- J. Lee
  - H. Lee
  - Y. Joo
  - J. Choi
  - T. Ha
  - W. Hwang
  - I. Hwang
  - J. Lee
  - B. Oh
  - C. Lee
  - H. Lee
  - J-Y. Kim
  - + PAL staff

#### THILAND

- H. Weidemann
- C. Somjai

#### SSRF

- H. Jie
- G. Liu

#### SSRL

- J. Safranek
- J. Sebek
- R. Hettel

#### SOLEIL

- L. Nadolski
- N. Hurbert

#### NSLS-II

- T. Shaftan
- J. Choi
- ASLS
- E. Tan

#### SLS

• M. Boege

#### Spring-8

- M. Takao
- T. Nakamura
- K. Kobayashi
   KEK
- J. Urakawa
   ALS
- G. Portmann
- W. Wan

#### APS

- L. Emery
- G. Decker

#### TPS

- P. Chou
- C. Kuo



# Support from accelerator society

### ○ Commissioning tool

- Matlab middle layer
- Labca

### ○ Digital BPM

- Libera Brilliance
- Many functions : Orbit interlock, post mortem
- First turn, TBT, FA (10K Hz), SA (10 Hz)

### ○ Digital timing system

- Easy to control for all machine timing in control room
- Collaboration with SSRF

### ○ Gradient dipole magnet

- Useful information from CLS, ALBA and Sprear-3
- Collaboration with IHEP

### ○ Many other encouragements





# **Commissioning milestones**

### ⊖ **2011**

- 25 January, PLS-II installation begins
- 23 May, Linac commissioning begins
- 13 June, 3 GeV beam
- 25 June, SR installation finished and BTL commissioning begins
- 1 July, First turn
- 5 July, Kicker PS accident
- 5 August, First accumulation
- September, Shutdown for installating insertion device
- 7 October, 100 mA stored
- 24 October, First photons to beamline
- December, Shutdown for installating insertion device

### O **2012**

- 14 February, Commissioning with users
- 21 March, Start of operations



### **PLS-II Linear accelerator**



Length - 164 m + 39
B.O.G.E.V. full energy mection
D.A.S.S.G. MHz (S-band)
D.Hz, 1.5 ns, 1Å pulsed beam
Norm. emmittance 120µmrad





# Linac & BTL commissioning

#### ○ First beam from gun (23 May)



Our measurement was not a picture of an E-beam profile. It was a picture of a boa constrictor digesting an elephant.



○ Emittance measurement (H/V: 600/800 nm @ 100 MeV)







# Linac & BTL commissioning

#### ○ 3 GeV beam (13 June)



#### ○ Beam at injection (29 June)



#### ○ Summary





# **PLS-II Storage Ring**



- Beam Energy 3.0GeV
- Beam Current 400mA
- Lattice DBA
- Superperiods 12
- Emittance 5.8 nm·rad
- Tune 15.245 / 9.18
  - RF Frequency 499.97 MHz
- Energy spread 0.1%
- 0.1%





## First turn & Kicker fire

#### ○ First turn (1 July)



○ Kicker fire (5 July)





#### Sextupole on / Bending 3.00 -> 3.04 GeV





### **Beam storage**



151 m\







### **Unexpected obstacle**







#### $\bigcirc$ Fine orbit correction

- 96 BPMs and 96 Slow correctors
- 96/93 Singular values













#### ○ LOCO application; Beta correction





#### ○ LOCO application; Dispersion and coupling correction





#### ○ PLS-II RF chracteristics

- 1.85 MV gap voltage
- 4 cavities
- RMS 0.1 % amplitude
- RMS 0.1 degree
- High power RF
- Digital field control

_	Specification	Phase-I(~2012)	<b>Phase-II(2013~)</b>
) –	Energy/Current	3.0GeV/100mA	3.0GeV/200mA
_	Losses with IDs	1,242keV	1,242keV
e _	Beam Power	124kW	248kW
<b>C</b> _	RF Cavities (Q'ty)	NC x 5	SC x 2
	RF Power Sources	(75x2)+300kWx2	300kWx2
_	Cryomodule	installing	~1.8MV/each
_	Cryogenic	commissioning	~700W





### Vacuum system





## **Orbit stability**





### Instability







# **Beam line commissioning**

#### ○ 30 Beam line including 14 IDs (10 IVUs)



#### ○ Spectrum from SFA IVU











## **Top-up commissioning**



#### ○ Radiation safety issue

0.03 - Reduction of vertical emittance 0.02 (Slit before SR) 0.01 Energy .3 - Reduction of gua pulse (ک) 0.00 8 (Current 2ns pulse) Time 0.83 ns -0.01 - Enforecement of shielding -0.02 (Keep same condition) -0.03 -0.8 -0.6 -0.4 0.2 0.6 0.8 10 15 -0.2 0.0 0.4 20 ○ Stored beam perturbation Time (ns)

- On plan to improve injection system

# Post commissioning; User operation





MTTR (min) 42



MTBF (hr) 84







# Post commissioning; Ground motion





## Summary

○ Current status / Commissioning Goals / PLS-II Goals

- Beam energy : 3.0 / 3.0 / 3.0 GeV
- Current : 100 / 100 / 400 mA
- Storage Ring Emittance : 5.8 / 5.8 / 5.8 nm·rad
- Operation mode : Decay / Top-up / Top-up
- No. of Insertion Device : 14 / 14 / 20
- Orbit stability : 2 / 2 / < 1  $\mu$ m





We really would like to appreciate all efforts and helps from worldwide accelerator physicists.

PAL staffs, even skipping their vacation during PLS-II commissioning, showed much passions with expertise and energy towards the commissioning with fine work.

# Thanks so much !