



---

# Overview of worldwide accelerators for ADS

**Weimin Pan**

**IHEP, Chinese Academy of Sciences**

**IPAC14, June. 15-20, 2014**

Institute of High Energy Physics,  
Chinese Academy of Sciences



# Acknowledgements

## Special THANKS to

- ☺ **Hamid Aït Abderrahim, Lucia Popescu, Luis Medeiros Romão, Dirk Vandeplasseche, Roberto Salemme, Dominik Mader (MYRRHA, SCK•CEN, Belgium)**
- ☺ **H. Sagnac (CNRS/IN2P3, IPN Orsay, France)**
- ☺ **Toshinobu Sasa, Hiroyuki Oigawa, Y. Kondo (J-PARC Center, Japan Atomic Energy Agency, Japan)**
- ☺ **Masahito Tomizawa (KEK Acc. Lab., Japan)**
- ☺ **Yuan He (Chinese Academy of Science, China)**
- ☺ **R. Garoby (SPL CERN, Switzerland)**
- ☺ **Mike Seidel (PSI, Switzerland)**
- ☺ **Yong-Sub Cho, etc (KOMAC/KAERI, Gyeongju, Korea)**



# Acknowledgements

## Special THANKS to

- ☺ T. Y. Song, etc (Korea Atomic Energy Research Institute ,Daejeon, Korea )
- ☺ Stuart Henderson (Fermilab,US)
- ☺ Sang-ho Kim (SNS/ORNL, US)
- ☺ Yousry Gohar (Argonne National Laboratory, US)
- ☺ S.Sidorkin, E.Koptelov, L.Kravchuk, A.Rogov (Institute for Nuclear Research RAS, Moscow, Russia )
- ☺ JONG-SEO CHAI (SUNGKYUNKWAN University)
- ☺ P.K. Nema, S.B.Degweker, Pitambar Singh, P.Satyamurthy and Amar Sinha BARC, Mumbai, India)
- ☺ I. Mardor, etc (Soreq NRC, Yavne, Israel)
- ☺ M. Arik, etc (Bogazici University, Istanbul, Turkey)

– And many others...



# Outline

---

1. Brief introduction to ADS
2. Basic requirements of ADS accelerator
3. Introduction of worldwide ADS accelerator progresses
4. Summary






---

# 1. Brief introduction to ADS

## (Accelerator-driven Subcritical System)

# Nuclear Power in the world


- ☑ 2009: ~14% electric power from the nuclear energy
- ☑ Till Oct., 2010: 441 reactors, 376.3GW<sub>e</sub>



➤ Nuclear waste is a bottleneck for nuclear power development.

# Nuclear Waste Management

## Motivation for transmutation




➤ ADS is considered as a good option for nuclear waste transmutation, but never tested, many challenges faced.



中国科学院高能物理研究所



## ADS system



**Main two aims for ADS :**

Burn-off of long-lived actinide waste from reactors ;

Energy production from Thorium fuel.






---

## 2. Basic requirements of ADS accelerator

# Power Map of Proton Accelerators



Institute of High Energy Physics,  
Chinese Academy of Sciences





**Generally, transmutation demonstration facility requires a beam power of 1-2 MW to deliver a thermal power of 50-100 MW.**

---

**A example : MYRRHA Project : 600 MeV /1.5 MW beam power, 85 MW thermal power.**

**CW beams are preferential for ADS, because target for pulsed heating is a challenge space charge effect is weaker in CW**



## Restrictions to ADS particle accelerators :

---

- High beam power : high energy and/or high beam current
- Very high stability: very few interruptions during long run
- Very low beam loss:  $<1\text{W/m}$  .

—— **special design for high power ADS!**



## Reliability, trip performance


	Transmutation Demonstration	Industrial Scale Transmutation	Industrial Scale Power Generation with Energy Storage	Industrial Scale Power Generation without Energy Storage
Beam Power	1-2 MW	10-75 MW	10-75 MW	10-75 MW
Beam Energy	0.5-3 GeV	1-2 GeV	1-2 GeV	1-2 GeV
Beam Time Structure	CW/pulsed (?)	CW	CW	CW
Beam trips ( $t < 1$ sec)	N/A	< 25000/year	<25000/year	<25000/year
Beam trips ( $1 < t < 10$ sec)	< 2500/year	< 2500/year	<2500/year	<2500/year
Beam trips ( $10 \text{ s} < t < 5 \text{ min}$ )	< 2500/year	< 2500/year	< 2500/year	< 250/year
Beam trips ( $t > 5 \text{ min}$ )	< 50/year	< 50/year	< 50/year	< 3/year
Availability	> 50%	> 70%	> 80%	> 85%



中国科学院高能物理研究所

## beam trips

Reliability goal: 0.01...0.1 trips per day!





# High Availability

## Control strategies for high availability

- Over-design
- reliable components in key parts, much over their limits,
- redundant elements,
- perfect protections,
- fault predicting function.



Table 1. The comparison of accelerator technologies for ADS

Technology	Cyclotron	Synchrotron	FFAG	Linac
Advantages	High current	High energy	High current and high energy	High current and high energy
Disadvantages	Energy limited	Current limited	Not yet proven	Expense
Examples	PSI	CERN PSB	EMMA	ESS, SNS

## Linac

- Good beam quality, low beam loss
- Expensive (Large real estate, large RF system)

## Cyclotron

- CW, stable, cost effective, small
- Heavy magnet, beam energy is limited

## Synchrotron

- Higher energy
- High intensity injection is limited

## FFAG many merits but not proven yet





## Today's Linear Accelerators :

---

- SRF linac is quickly developed and has most potential
- large aperture, low loss, CW possible
- high beam power --- couplers are critical

The main disadvantage is high expense, but mass production will be lower .



---

## 3. Introduction of worldwide ADS accelerators progresses



# MYRHHA

---

## — *Multipurpose Hybrid Research Reactor for High-tech Applications (MYRHHA) Project*

- *European Transmutation Demonstrator —by coupling the three components (accelerator, spallation target and sub-critical reactor) at power level scalable to an industrial demonstrator*
  - demonstrate the physics and technology of ADS for transmuting long-lived radioactive waste .

## MYRRHA ADS – Technical specifications

Accelerator	
<i>particles</i>	protons
<i>beam energy</i>	600 MeV
<i>beam current</i>	4 mA
<i>mode</i>	CW
<i>MTBF</i>	> 250 h

Reactor	
<i>power</i>	~85 MW <sub>th</sub>
<i>k<sub>eff</sub></i>	0.955
<i>spectrum</i>	fast (flexible)
<i>fuel</i>	MOX
<i>coolant</i>	LBE




Target	
<i>main reaction</i>	spallation
<i>output</i>	$2 \cdot 10^{17}$ n/s
<i>material</i>	LBE (coolant)
<i>power</i>	2.4 MW




**Multipurpose  
Flexible  
Irradiation  
Facility**

- Transmutation concept
- Irradiation facility for GEN-IV materials
- Neutron irradiated silicon
- Radioisotopes for nuclear medicine
- Fundamental research



## MYRRHA ADS – Schedule








中国科学院高能物理研究所

## MYRRHA - Accelerator





# MYRRHA proton beam requirements

→ High power proton beam (up to 2.4 MW)

Proton energy	600 MeV
Peak beam current	<del>0.1 to 4.0 mA</del>
Repetition rate	1 to 250 Hz
Beam duty cycle	$10^{-4}$ to 1
Beam power stability	$< \pm 2\%$ on a time scale of 100ms
MTBF	$> 250$ h
# of allowed beam trips on reactor longer than 3 sec	10 maximum per 3-month operation period
# of allowed beam trips on reactor longer than 0.1 sec	100 maximum per day
# of allowed beam trips on reactor shorter than 0.1 sec	unlimited

→ Extreme reliability level




中国科学院高能物理研究所




# Beam dynamics development


Reference design, 2012  
by C. Zhang




Alternative design, 2013



Consolidated alternative design, 2013



Smooth design, 2014





## The ECR proton source



### Monogan 1000

#### ECR Ion souce – 30keV, 20mA

- Electron Cyclotron Resonance, 2.45 GHz
- multi-electrodes extraction system
- flat magnetic profile configuration by PMs
- tapered axial RF injection
- Einzel electrostatic focusing lens



courtesy of PantechNIK SA

accelerating voltage	30 kV (40 kV capable)
beam current	20 mA DC
RF	2.45 GHz, 1200 W
transverse emittance @ 5 mA	<b>0.1 <math>\pi</math>·mm·mrad RMS norm.</b>
magnetic system	Permanent Magnets
autonomous control system	NI CompactRIO
provisions for reliability/repairability	
beam diagnostics devices incl.: Faraday Cup, Allison scanner	



## Acceptance Tests







Figure 22: Source parameters at 15 mA @ 30 keV

- Beam characterization in a short test line (source, dipole, FC, Allison scanner, dump)
- Max p beam current achieved: 16mA
- Long stability run (24hrs), standalone system, up to 12 mA
- Excellent stability shown with brief recovery time in case of electrical discharges




Source 4: Beam Current 0 to 14 hours



Source 5: Beam Current 14 to 21 hours (beam current for source and beam for beam)


## Acceptance Tests

SPECTRUM




- **Total efficiency : 84%**
  - Includes beam transport efficiency (total current from power supply divided by the sum of measured intensity) and HV losses (bleeder)
- Ionisation efficiency (ion intensity divided by total measured intensity)
  - $H^+ = 63\%$
  - $H2^+ = 30\%$
  - $H3^+ = 7\%$



# Spoke Cavity Prototype EM Optimization



Numerical Model : Symetries and BC



Geometrical Parameters



## Optimized RF parameters

Optimal beta	<b>0.37</b>
Vo.T [MV/m] @ 1 Joule & optimal beta	<b>0.693</b>
Epk/Ea	<b>4.29 *</b>
Bpk/Ea [mT/MV/m]	<b>7.32 #</b>
G [Ohm]	<b>109</b>
r/Q [Ohm]	<b>217</b>
Qo @ 2K for Rres=20 nΩ	<b>5.2 E+09</b>
Pcav for Qo=2 E+09 & 6.4 MV/m [W]	<b>9.35</b>
Lacc=0.315m= beta <sub>optimal</sub> · c · f	







\* Goal at 4.4, # Goal at 8.3

**Goal:  $E_{acc\ nom.} = 6.2\ MV/m$ ,  $E_{acc\ fault\ tol.} = 8.2\ MV/m$**




# Spoke Cavity Prototype Mechanical Optimization

Simulation Case		
Bare Cavity Leak Test	0.1 Mpa External	52 MPa
Cavity Leak Test	0.1 Mpa External	< 33 MPa
Helium Tank Leak Test	0.1 Mpa External	< 35 MPa
Cavity Cool down	0.12 MPa	< 33 MPa
Cryogenic Accident	0.15 MPa	< 41 MPa
First Eigen Mode	###	232 Hz
Cavity Buckling Critical Pressure	###	3 Bars



## Spoke Cavity Prototype Overview



**Cavity Wall thickness 3 mm (Nb RRR > 250)**

**Helium Tank Wall thickness 4 mm**

## Power Coupler



A power coupler 350 MHz, 20 kW CW (designed) was manufactured and tested at 8 kW (limited by amplifier) CW on a 350 MHz, beta 0.15 Spoke cavity.

1 port for electron emission measurement pick up

1 water cooling loop for the window

Plain Copper Antenna








MAX

MYRRHA ACCELERATOR EXPERIMENT  
RESEARCH & DEVELOPMENT PROGRAMME

## Linac components: elliptical



**J-PARC**

高能物理研究所



## Plan of Transmutation Experimental Facility (TEF) as Phase-II of J-PARC



### Transmutation Physics Experimental Facility: TEF-P

Purpose: To investigate physics properties of subcritical reactor with low power, and to accumulate operation experiences of ADS.

Licensing: Nuclear reactor: (Critical assembly)

Proton beam: 400MeV-10W

Thermal power: <500W

### ADS Target Test Facility : TEF-T

Purpose: To research and develop a spallation target and related materials with high-power proton beam.

Licensing: Particle accelerator

Proton beam: 400MeV-250kW

Target: Lead-Bismuth Eutectic (LBE, Pb-Bi)

Critical Assembly

Multi-purpose Irradiation Area

Pb-Bi Target

Proton Beam

10W  
250kW






## Phase I

- day-1**

Linac	<b>180MeV</b> , 30mA, 25Hz
RCS	3GeV, <b>0.6MW</b>
MR	40GeV, 400kW
- Next Stage**

Linac	<b>400MeV</b> , 50mA, 25Hz
RCS	3GeV, <b>1.0MW</b>
MR	40GeV, 670kW



## Phase II


- Nuclear Transmutation Facility(ADS)**  
 → Linac 600MeV, 50Hz
- Extension of Hadron and Neutron Facility**
- MR 50GeV, 750kW**

## Linac structures and parameters

• <b>Ion Source:</b>	<i>Volume Production Type</i>
• <b>RFQ:</b>	<i>Stabilized Loop</i>
• <b>DTL:</b>	<i>Electro-Quad in DT, 3 tanks</i>
• <b>Separated DTL(SDTL):</b>	<i>no quad in DT, short tank(5cells), 32tanks</i>
• <b>Annular Coupled Structure (ACS):</b>	<i>axial symmetric</i>
• <b>Super Conducting Linac (SCL):</b>	<i>wide aperture, high acceleration gradient</i>

• <b>particles:</b>	<i>H<sup>-</sup></i>
• <b>Energy:</b>	<i>181 MeV (RCS injection) 400 MeV (RCS injection) 600 MeV (to ADS)</i>
• <b>Peak current:</b>	<i>30 mA @181MeV 50 mA @400 MeV</i>
• <b>Repetition:</b>	<i>25 Hz (RCS Injection) 50 Hz(RCS Injection + ADS application)</i>
• <b>Pulse width:</b>	<i>0.5 msec</i>


developed a lot of key components and integrations





## Upgrade plan of J-PARC linac

- Energy is upgraded with ACS, current is upgraded with new ion source and RFQ.



## Construction Schedule (Tentative Plan)

Fiscal Year	2012	2013	2014	2015	2016	2017	2018	2019	2020	2021	2022	2023	2024
Beamline TEF-T	R&D, Design			Construction									
							Operation						
TEF-P	R&D, Design			Licensing									
							Construction					Operation	

- The construction of Beam line and TEF-T will be started in 2014 and the operation with 1/4 beam power will be started in 2017
- To start the construction of TEF-P in 2017, just after the completion of TEF-T, a few years of licensing activities should be started in 2015



# ***KIPT Experimental Neutron Source Facility at Kharkov, Ukraine***

---

- ✓ *Provide capabilities for performing basic and applied research using neutrons*
- ✓ *Perform physics and material experiments inside the subcritical assembly and neutron experiments using the radial neutron beam ports of the subcritical assembly*
- ✓ *Produce medical isotopes and provide neutron source for performing neutron therapy procedures*
- ✓ *Support the Ukraine nuclear power industry by providing the capabilities to train young specialists*





# Linac Machine Parameters



**a 100MeV/100 kW electron linac for KIPT is used as the driver of a neutron source based on a subcritical assembly.**


Parameters	Values	Units
RF frequency	2856	MHz
Beam energy / power	100 / 100	MeV / kW
Beam current (max.)	0.6	A
Energy spread (p-to-p)	$\pm 4$	%
Emittance	$5 \times 10^{-7}$	m-rad
Beam pulse length	2.7	$\mu\text{s}$
RF pulse length	3	$\mu\text{s}$
Pulse rep. rate	625	Hz
Klystron	$6 \times 30\text{MW} / 50\text{kW}$	Units
Accelerating structures	$10 \times 1.336\text{m}$	Units
Gun high voltage	$\sim 120$	kV
Nominal gun beam current	$\sim 1\text{--}1.2$	A



# Injector Testing Facility and Testing Results



The injector testing facility installed



**~780mA obtained with ~90% transport efficiency at the injector exit**

- The maximum beam current obtained at the injector exit is ~2A with 2.7 μs beam pulse.
- Energy spread is ~2% @ 1σ



# ***HYPER*** (*Hybrid Power Extraction Reactor*)

---


The Korea Atomic Energy Research Institute (KAERI) performs HYPER for **the transmutation of nuclear waste and energy production**, to develop the elemental technologies for the subcritical transmutation system and **build a small bench scale test facility (5 MW). 1 GeV/16 mA proton beam is designed to be provided for HYPER.**




## ***KOMAC*** (Korea multi-purpose accelerator complex)

KOMAC accelerator facility was put into the operation from July 2013, which **consists of a 100MeV proton linac** including a 50keV ion source, a 3MeV RFQ and a 100MeV DTL, and 20MeV and 100MeV beam lines. The goal of the Beam commissioning is **delivering 100MeV 1kW proton beams to a bump in a 100MeV target room.**





50-keV injector including ion source and LEBT.



DTL in the accelerator tunnel



High power rf system

### Parameters of KOMAC Linac

Frequency 350 MHz

Beam Energy 100 MeV

Operation Mode Pulsed

Max. Peak Current 20 mA

Pulse Width <1.33 ms (< 2.0 ms for 20 MeV)

Max. Beam Duty 8% (24% for 20 MeV)


Max. Beam Power 160 kW ( 96 kW for 20

MeV )



# Proton Linac in India ADS Program

Indian-ADS (especially thorium-cycle)



(Courtesy of P. Singh, BARC)



中国科学院高能物理研究所



# Accelerator Development for ADS

## 30 mA /20 MeV Linac injector (LEHIPA) and High energy Linac (1 GeV)

Design completed & fabrication is in progress

ECR Ion Source



LEBT





RFQ



Drift Tube Linac



50 kW RF Coupler



60 kW RF System



1.3 MW Klystron







## Developing Technique for SC RF Cavity Fabrication




Toolings



Forming Process



Formed Niobium  
Half Cell




EBW chamber



Welded dumbbell

# Roadmap for ADS Developments



Note: Design and engineering phases are not factored.  
R&D for enabling technologies to precede the onset of projects.  
R&D on fuel cycle, fuel design and fabrication to meet appropriate schedule.

*Courtesy of P.K. Nema,  
BARC Mumbai*



## A PROVISIONAL STUDY OF ADS WITHIN TURKIC ACCELERATOR COMPLEX PROJECT

# ***TAC** (Turkic Accelerator Complex project)*

Planning to have **four facilities**:

**SASE FEL Facility; Third Generation Synchrotron Radiation Facility (SR); Super-Charm Factory ( $\sqrt{s} = 3.77$  GeV) ; GeV scale proton accelerator which has two-fold goal: Neutron Spallation Source (NSS) and ADS.**

**The proton accelerator construction will have 3 MeV, 100 MeV, and 1 GeV phases.**






中国科学院高能物理研究所



## The TAC proton accelerator: GeV energy high intensity (>1mA) proton linac.






中国科学院高能物理研究所



# Roadmap of ADS Project in China



“Strategic Priority Research Program”  
of the Chinese Academy of Sciences



## Special features and design goals


- Medium-energy, very high beam power, very high reliability, CW beam
- Reliability and availability much higher than actual accelerators in operations

Particle	Proton
Energy (GeV)	1.5
Current (mA)	10
Beam power (MW)	15
Duty factor (%)	100
Beam Loss (W/m)	<1
Beam trips/year	
1 s < t < 10 s	<25000
10 s < t < 5 m	<2500
t > 5 m	<25



# Layout of ADS Accelerator

- The proton accelerator is being built by IHEP and IMP together.
- Project started from early 2011.



Final project has two identical injectors. Two designs of injector is due to technical uncertainty at very low energy segment.




# Two options of 10-MeV Injectors




## Injector I at IHEP, Beijing

Base on 325 MHz and Superconducting Spoke cavity



## Injector II at IMP, Lanzhou

Base on 162.5 MHz and Superconducting HWR cavity







## Progresses of accelerator (Injector I & II)


### key technologies :

- I. CW RFQ with a high intensity——**Great chellage !**
- II. Very Low beta SC cavities —— Spoke cavity & HWR ——**lowest beta!**




## 1) RFQ for Injector I

**4** technical modules, **64** tuners,  
**4** RF power couplers, **4** dipole  
rods on each plate .



The beam transmission is about 98.7%

Parameters	Value
Frequency (MHz)	325
Injection energy (keV)	<b>35</b>
Output energy (MeV)	<b>3.2128</b>
Pulsed beam current (mA)	<b>15</b>
Beam duty factor	100%
Inter-vane voltage $V$ (kV)	<b>55</b>
<b>Beam transmission</b>	<b>98.7%</b>
Average bore radius $r_0$ (mm)	2.775
Vane tip curvature (mm)	2.775
Maximum surface field (MV/m)	28.88 (1.62 Kilp.)
Input norm. rms emittance (x,y,z) ( $\pi$ mm.mrad)	0.2/0.2/0
<b>Output norm. rms emittance(x/y/z) (<math>\pi</math>mm.mrad/MeV-deg)</b>	<b>0.2/0.2/0.0612</b>
Vane length (cm)	467.75 <sub>5</sub>
Accelerator length (cm)	<b>469.95</b>



RFQ on site and aging



**Conditioning goal: 270kW**  
**Status: 80% of the full power.**





## 2) RFQ for Injector II


Parameter	Value
Ion species	Proton
frequency [MHz]	162.5
Inter-vane voltage $V$ (kV)	65
Average bore radius $r_0$ (cm)	0.5731
Vane tip curvature (cm)	0.4298
$\rho / r_0$	0.75
Vane length / Total length (cm)	419.2 / 420.8
$m_{\max}$	2.38
Number of cells	192 (including 2 T cell)
Maximum surface field (MV/m)	15.7791
Synchronous phase ( $^\circ$ )	from -90 to -22.7
$a_{\min}$ (cm)	0.3158
Transverse acceptance (RMS, x/y, $\pi$ mm.mrad)	0.3/0.3
Input norm. RMS emittance (x/y, $\pi$ mm.mrad)	0.3/0.3
Output norm. RMS emittance (x/y/z, $\pi$ mm.mrad, keV.ns)	0.31/0.31/0.92
Overall beam transmission @ 0 / 15 mA	99.7% / 99.6%



Structure

4 modules, 4200mm long  
80 Tuners, 32 Pi-mode  
Rods, 2 RF input ports  
in Module 2, 8 vacuum  
ports







Four modules has been finished. The flatness is  $\pm 1\%$ , and symmetry is  $\pm 1.5\%$  w/o tuners.

Conditioning goal: **91kW**  
Status: **full power in CW**.  
commisioning beam now.

# ECRIS+LEBTs finished commissioning




Two ECR Proton Ion Sources was commissioned at IMP and IHEP.


**25 mA proton with 35 keV** has been extracted.



# Beam Commissioning of 162.5 MHz RFQ



**Got cw beam of 2.3 mA (10/06/2014)**




Red: DCCT1; Green: DCCT2  
Efficiency > 95%

Yellow: BPM1; Green: BPM2;  
Blue: BPM3; Energy=2.16 MeV

Signal from pillbox  
Momentum spread ~2%

**Pulsed beam mode: max. beam  $\sim 8$  mA,  
max. pulse length is 400 ms at repetition of 1 Hz**



**The Purple is the signal of the DCCT2 at exit of RFQ. the Blue is the temperature of the Faraday Cup, means average beam power,  $\sim 8$  degree C increasing in maximum .**







### 3) Spoke012 Cavity ( $\beta=0.12$ ) for Injector I

Main Geometrical parameters	Units	Value
Diameter of cavity	mm	468
Length of cavity	mm	180
Diameter of beam tube	mm	35
RF parameters	Units	Value
$E_{\text{peak}}/E_{\text{acc}}$		4.54
$B_{\text{peak}}/E_{\text{acc}}$	mT/(MV/m)	6.37
G	$\Omega$	61
Transition Time Factor		0.76
$R/Q@\beta=0.12$	$\Omega$	142


Note: Effective length for  $E_{\text{acc}}$  is defined as  $\beta\lambda$



The Convex end wall (right) is dopted, which has better mechanical performance than the flat one (left).




E-field



B-field



## Fabrication of Spoke012 cavity finished on Nov. 8, 2012




$$df/dp = 10\text{Hz/mbar}$$






## Vertical test result of Spoke012



✓  $Q_0 = 5.8 \times 10^8$  @6MV/m, 4K;  $Q_0 = 3.4 \times 10^8$  @7MV/m, 4K



## Horizontal test result on Sept. 12, 2013 ——the first horizontal test for the low beta proton SC cavity



✓  $Q_0 = 2.2 \times 10^8$  @ 6.5 MV/m, 4K;  $Q_0 = 8.5 \times 10^8$  @ 5 MV/m, 4K.






## 4) Spoke021 Cavity ( $\beta=0.21$ ) of Main Linac



Para.	Value
$E_p/E_{acc}$ / (void)	4.38
$H_p/E_{acc}$ / mT/(MV/m)	9.37
$\beta_{opt}$	0.243
Gap = $c \cdot \beta_{opt}$ / f (mm)	224
$r/Q$ / $\Omega$	191
$G$ / $\Omega$	71



✓ V-T :  $B_p=98$  /mT,  $Q_0=5e8$ ; Max.  $B_p=107$  /mT






## 5) Elliptical Cavity ( $\beta=0.63$ & $0.83$ ) of Main Linac

650MHz ( preparing for test)



## 6) HWRs for Injector II



<b>f (MHz)</b>	<b>162.5</b>
<b><math>\beta_{\text{opt}}</math></b>	<b>0.101</b>
<b>E<sub>peak</sub> / E<sub>acc</sub></b>	<b>5.9</b>
<b>B<sub>peak</sub> / E<sub>acc</sub></b>	<b>12.1</b>
<b>G = R<sub>s</sub> × Q<sub>0</sub> (Ω)</b>	<b>28.4</b>
<b>R / Q<sub>0</sub></b>	<b>153</b>
<b>Q<sub>0</sub> (4.4K, R<sub>s</sub>=71.4 nΩ)</b>	<b>4E8</b>
<b>V<sub>acc</sub> (MV)</b>	<b>0.78</b>
<b>E<sub>peak</sub> (MV/m)</b>	<b>25</b>
<b>B<sub>peak</sub> (mT)</b>	<b>50</b>
<b>P<sub>diss</sub>(W) (4.4K, R<sub>s</sub>=71.4nΩ)</b>	<b>10</b>

$$\otimes \quad E_{\text{acc}} = V_{\text{acc}} / (\beta_{\text{opt}} \times \lambda)$$






## VT results of HWR




$df/dp = 10 \text{ Hz/mbar}$



#03~#05 have been qualified and #05 has been jacked and put into TCM<sup>1</sup>








**Four HWRs with ribs on both surfaces has been fabricated**

# Horizontal Testing for HWR

Op. Temperature	4.4 K
Op. Pressure	1.25 bar
Cooling	bath
Pressure	$\pm 1.5$ mbar
Dynamic load	10 W
Solenoid storage	27KJ



finished



Epeak vs  $Q_0$  from VT to HT





## 7) High Power Input Couplers for Injector I & II

**Spoke cavity couplers tested over 10 kW CW power,**  
one operated in spoke012 cavity horizontal test.



coupler operated with cavity



**RFQ coupler's  
windows tested  
up to 100 kW  
CW power.**



**HWR couplers tested  
over 20 kW CW, and put  
into HT of HWR .**

## 8) Cryogenic Station (850 W at 4.5 K)



**Helium Recovery System  
putting into operation**





## *Other International ADS Programs?*


---

*IAEA reported that 18 countries are performing ADS R&D*

*Also, there are many similar accelerator technologies (as ADS ) used for other purposes.*

**SNS SCL** many parts, equipment, design are based on CEBAF, TESLA, APT, LEDA, KEK experiences

Front-End:  
Produce  
a 1-msec long,  
chopped, H-beam



- **Most powerful spallation neutron source**
- **259-m long linac + accumulator**
- **Short pulse**
- **71-m long Space is reserved for additional cryomodules to give 1.3 GeV**




# Project-x

院高能物理研究所

## Project-X (Courtesy of S. Nagaitsev)

- 3 GeV CW superconducting H- linac with 1 mA average beam current.
- 3-8 GeV pulsed linac capable of delivering 300 kW at 8 GeV
- Upgrades to the Recycler and Main Injector to provide  $\geq 2$  MW to the neutrino production target at 60-120 GeV.
- Day one experiment to be incorporated utilizing the CW linac



⇒ Utilization of a CW linac creates a facility that is unique, with performance that cannot be matched in a synchrotron-based facility.



# Project-x

## A Zoo of RF Structures for $\beta < 1$ Acceleration

Normal Conducting Structures



$\beta=0$

0.05


0.1

0.25

0.5

0.8

$\beta=1$




Superconducting Structures



PSI


# PSI Ring Cyclotron

<b>8 Sector Magnets:</b>	<b>1 T</b>
<b>Magnet weight:</b>	<b>~280 tons</b>
<b>4 Accelerator Cavities:</b>	<b>860 kV (1.2 MV)</b>
<b>1 Flat-Top Resonator</b>	<b>150 MHz</b>
<b>Accelerator frequency:</b>	<b>50.63 MHz</b>
<b>harmonic number:</b>	<b>6</b>
<b>kinetic beam energy:</b>	<b>72 → 590 MeV</b>
<b>beam current max.:</b>	<b>2.4 mA</b>
<b>extraction orbit radius:</b>	<b>4.5 m</b>
<b>outer diameter:</b>	<b>15 m</b>
<b>RF efficiency Grid/Beam</b>	<b><math>0.90 \times 0.64 \times 0.55 =</math> 32%</b>
<b>rel. losses @ 2.2mA:</b>	<b><math>\sim 1..2 \cdot 10^{-4}</math></b>
<b>transmitted power:</b>	<b>0.32 MW/Res.</b>



## ESS

## ESS Linac





	Energy (MeV)	No. of Modules	No. of Cavities	$\beta_g$	Temp (K)	Cryo Length (m)
<b>Source</b>	0.075	1	0	—	~300	—
<b>LEBT</b>	0.075	—	0	—	~300	—
<b>RFQ</b>	3.6	1	1	—	~300	—
<b>MEBT</b>	3.6	—	3	—	~300	—
<b>DTL</b>	90	5	5	—	~300	—
<b>Spoke</b>	220	13	2 (2S) $\times$ 13	0.5 $\beta_{opt}$	~2	4.28
<b>Medium <math>\beta</math></b>	570	9	4 (6C) $\times$ 9	0.67	~2	8.52
<b>High <math>\beta</math></b>	2000	21	4 (5C) $\times$ 21	0.86	~2	8.52
<b>HEBT</b>	2000	—	0	—	~300	—




## IFMIF

High >20 dpa/hr, 0.5 L  
 Medium > 1 dpa/hr, 6 L  
 Low < 1 dpa/hr, > 8 L


IFMIF/EVEDA  
Prototype Accelerator

Cryomodule under construction for the accelerator prototype  
 The first one of the IFMIF SRF Linac~5 m Long  
 4.5 MV/m, reliability, limits the coupler power  
 Large beam aperture 40-48 mm  
 $Q_{\text{ex}}=6.3 \times 10^4$



SPL

## Linac4: Block diagram



H<sup>-</sup> ion current:  
40 mA (avg.),  
65 mA (peak)

Length: 80 m

19 klystrons [13 x 1.3 MW (LEP), 6 x 2.8 MW (new)]

Normal conducting accelerating structures of 4 types: RFQ, DTL, CCDTL, PIMS

Single frequency: 352.2 MHz

Duty cycle: 0.1% phase 1 (Linac4), 3-4% phase 2 (SPL), (design: 10%)




SPL

## SPL block diagram



- SC-linac [160 MeV ® 5 GeV] with ejection at intermediate energy



- Medium beta cavities:  $\beta = 0.65$
- High beta cavities:  $\beta = 1$

“New” TDR to be published during Q2/2014


SPL

## Niobium cavities at CERN



## REPAIR OF FIRST MONOCELL

Material defects observed after electro-polishing.  
Repaired with new e-beam welding machine from outside (W#1 and W#3) and inside (W#2)




## CAVITY FABRICATION AT CERN


Half-cells and beam tubes fabricated by spinning.



RF measurements.



Tooling for EB welding of Nb cavity is fabricated.



# SARAF-PHASE 2 LINAC DESIGN

**Particles : deuterons and protons**

**Input energy : 20 keV/u**

**Input emittance (rms, norm.) : 0.2 pi.mm.mrad**

**Output energy : 1.3 MeV/u**

**Emittance growth < 25%**

**Time structure : pulsed and cw**

**Beam current : 0.04 – 5 mA**

**Beam losses :**

**< 150 nA/m for  $E < 5$  MeV (0.4-0.75 W/m)**

**< 40 nA/m 10 MeV (0.2-0.4 W/m)**

**< 5 nA/m 20 MeV (0.05-0.1 W/m)**

**< 1 nA/m > 20 MeV (0.02-0.04 W/m)**

**<< 1 W/m !!!**



## Summary to ADS accelerators

1. The ADS program is to speed up from the basic study to the real facility.
2. The key technologies in high power proton accelerator are severe challenges for us.
3. Many good technologies have been developed, e.g. SNS demonstrated  $<1$  W/m beam loss in MW-class pulsed accelerator: Could go higher power; SRF became a choice especially for high power and high duty factor machines
4. There are many common interests in the high power proton acceleration technology for the labs involved in proton accelerator. Close international cooperation is very important and expected.






---

I 'm sorry for uncovering  
all ADS plans probably.



---


# Thanks for your attentions!



# Accelerator architectures for high power

---

- **Linear accelerator only (long pulse beam, pulsed or CW) –**  
LANSCE, PEFP, ESS, Project X driver, IMFIF, FRIB, SNS-STS, China ADS
  - **Linear accelerator + accumulator (short pulse, pulsed)**  
SNS, PSR/LANL, CSNS
  - **Lower energy linear accelerator + RCS (short pulse, pulsed)**  
ISIS, J-PARC, CSNS
  - **Circular accelerator: Cyclotron (or FFAG) (long pulse, CW)**  
PSI, (future FFAG in somewhere)
-



---

## For Injector I:

**Emittance (RMS) at entrance of MEBT1:**

**0.198 / 0.199 / 0.159 pi.mm.mrad ( x / y / z )**

**10MeV: 3.4% / 3.0% / 5.0% (no error case)**  
**( x / y / z )**

---