

CEBAF SRF Performance During Initial 12GeV Commissioning

Rama Bachimanchi – Jefferson Lab , Newport News, VA

IPAC 2015, May 3-8

R.Bachimanchi, IPAC, May 2015, Richmond, VA


Outline

- **12 GeV Project**
- **C100 RF system**
- **C100 Commissioning**
- **Operational Experience**
- **Summary**

R.Bachimanchi, IPAC, May 2015, Richmond, VA

12 GeV Upgrade Project

6 GeV → 12 GeV



- **11 New cryomodules (C100)**
- **New RF power sources (13 kW)**
- **Refrigeration**
- **Magnets**
- **Additional arc-beamline**
- **Extraction system**
- **New experimental area Hall D**

R.Bachimanchi, IPAC, May 2015, Richmond, VA

C100 Cryomodule



- Seven cell Cavity, 0.7 m long (high Q_L)
- 8 Cavities per Cryomodule
- Fits the existing Cryomodule footprint


R.Bachimanchi, IPAC, May 2015, Richmond, VA

High Q_L Challenges




Fundamental frequency f_0	1497 MHz
Accelerating gradient E_{acc}	> 20 MV/m
Input coupler Q_{ext}	3.2×10^7
Active length	0.7 m
r/Q	1300 Ω/m
Tuning sensitivity	0.3 Hz/nm
Pressure sensitivity	420 Hz/torr
Lorentz force frequency sensitivity K_L	$\sim 2 \text{ Hz}/(\text{MV}/\text{m})^2$

Field startup




Field stability



Phase noise plot of microphonics

R.Bachimanchi, IPAC, May 2015, Richmond, VA


RF System for C100 Cavity



- One LLRF / Cavity
- One Klystron / Cavity
- One System / Zone
 - Stepper
 - Piezo
 - Heater
 - HPA
 - Interlocks

R.Bachimanchi, IPAC, May 2015, Richmond, VA


RF System



- Single Zone
 - Eight 13 kW Klystrons
 - Four HV Power Supply
- Total (10 + 1 zones)
 - 80 Klystrons (13 kW)
 - 8 Klystrons (8 kW ,C100-0)

R.Bachimanchi, IPAC, May 2015, Richmond, VA


RF System



- Single Zone
 - 8 LLRF Controllers
 - Stepper Controller
 - Piezo Amplifier
 - Interlocks Controller
 - High Power Amplifier Controller
 - Cryomodule Heater Controller
- Total (11 zones)
 - 88 LLRF Controllers

R.Bachimanchi, IPAC, May 2015, Richmond, VA

RF System



- RF Board
- FPGA Board
- PC/104
- Modular Interface Boards
- PC Power Supply

R.Bachimanchi, IPAC, May 2015, Richmond, VA

C100 Commissioning

Acronyms used in the slides

- SEL (Self Excited Loop)
 - Cavity resonates at it's own frequency (Phase Locked Loop like)
 - Constant forward power
- GDR (Generator Driven Resonator)
 - Cavities are locked to reference
 - Forward power not constant (reacts to detuning)

R.Bachimanchi, IPAC, May 2015, Richmond, VA

C100 Commissioning

- RF system commissioned into waveguide shorts
- SRF commissioning using LLRF
 - Emax for individual cavities
 - Field Emission measurements
 - Q_0 measurement
 - Operable gradient for cryomodule
 - **Performed in SEL**
- LLRF Commissioning & Machine operations
 - **Cavities are operated in GDR**

R.Bachimanchi, IPAC, May 2015, Richmond, VA

C100 Commissioning - Timeline

Year	Activity
2011	C100-1&2 were installed and commissioned
2012	C100-1&2 were operated during 6 GeV Nuclear Physics run. C100-2 was operated up to 108 MEV and 465 μ A May – Began 18 month CEBAF shutdown
2013	Installed and commissioned eight C100 cryomodules
2014	January completed C100 commissioning and began beam operation/commissioning March commissioned C100-0 (Installed in Injector)

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Gradients in C100 During Commissioning

Zone	SRF Commissioning	2.2 GeV/Pass
C100-1	110 MV	94.01 MV
C100-2	120	93.8
C100-3	124	76.58
C100-4	105	79.24
C100-5	110	100.31
C100-6	113	101.8
C100-7	113	103.81
C100-8	109	100.17
C100-9	117	101.15
C100-10	116	87.57
C100-0	116	82.3

R.Bachimanchi, IPAC, May 2015, Richmond, VA


Operational Experience -CEBAF Commissioning

- Commissioning
 - 2.2 GeV/pass
 - C100 - 934 MeV
 - C50 - 457 MeV
 - C20 - 808 MeV
 - Injector design energy – 123 MeV
- Opportunities for Improvement
 - Reducing Field Emission
 - Enhanced Cryomodule Heater Configuration
 - Microphonics Detuning
- Other Observations
 - RF Control Loop Optimization
 - Klystron Drive Cables

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Field Emission


- Field Emission heats Beamline
- Vacuum Pump faults
- Vacuum Interlock drops Zone out of RF



R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Field Emission



Cavity Gradients impacting Beamline Vacuum activity



R.Bachimanchi, IPAC, May 2015, Richmond, VA

Helium Processing

- Introduce helium gas into cavity vacuum space
- Run RF to clean cavity surfaces
- Warm up and pump down to remove residual gas
- Improves high-field Q, reduces x-ray production and greatly reduces incidence of arcing at the cold ceramic window




HELIUM PROCESSING PUMP CART AND MANIFOLD

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Helium Processing

- Performed on C100-5 cryomodule




C100-5 cavity 6
Before and after
He processing

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Cryomodule Heater Configuration

- C100-1
- Cavities 6 and 7 have very high detuning

Total heat vs Detuning in SEL




R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Cryomodule Heater Configuration


- When RF was off
 - Only Electric Heat

He Level Percentage



- When RF was on
 - RF + Electric Heat


He Level Percentage



R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Cryomodule Heaters

- Single Heater Control for the Cryomodule
- Return riser became a choke point as additional heat was applied
- **Solution - Individual Cavity Heater Control**




R.Bachimanchi, IPAC, May 2015, Richmond, VA

Microphonics - Mechanical Tuner Modification

- Design allows for 25 Hz Peak Detuning
- Actual peak detuning (**18 Hz**) was higher than expected in first cryomodules (C100- 0,1,2,3)
- A detailed vibration study was initiated which led to the following design change
- A minor change to the **tuner pivot** plate substantially improved the microphonics detuning for the CEBAF C100 Cryomodules
- While both designs meet the overall system requirements the improved design has a larger RF power margin

Microphonic Detuning	C100-1	C100-4
RMS (Hz)	2.985	1.524
6s(Hz)	17.91	9.14



R.Bachimanchi, IPAC, May 2015, Richmond, VA


Operational Experience – Microphonics Detuning and Construction



C100 Cavity Gradients

- The drops show the cavity faulting during the day due to construction.
- RF Power could not compensate for the rapid detuning

C100 - 0 Cavity Gradients



R.Bachimanchi, IPAC, May 2015, Richmond, VA


Operational Experience – Microphonics Detuning

- Reduced Gradients in C100-0


Plan

- Collect Microphonics data from all C100s
- Investigate Piezo Algorithm
- Possibly switch out C100-0 for later production C100


C100-0
Cavity
gradients in
MV/m



C100-4
Cavity
gradients in
MV/m



C100-8
Cavity
gradients in
MV/m




R.Bachimanchi, IPAC, May 2015, Richmond, VA

RF Control Loop Optimization

- We observed 4 kHz oscillation when LLRF is locked
- Higher gain
 - Reduced 4 kHz oscillation
 -but control system less stable
- Loop Phase mismatch between SEL and locked condition
 - Simulation didn't show
 - Latency issue between the two logic chains in the FPGA
 - Systematic 30 degree difference

Microphonics – compensated

4 kHz




Forward Power in GDR

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Operational Experience - Crosstalk on Klystron drive cables

- Crosstalk on Drive Cables
 - Causing cavity trips on GMES fault
 - Repaired connectors and problem went away
- Crosstalk on Klystron Internal Cable
 - Terminated the input
 - Still had 15-25 watts forward power and gradient in the cavity!
 - Investigating pulling klystron solenoid and replacing cables with better shielded cables



R.Bachimanchi, IPAC, May 2015, Richmond, VA

Future Plans

- Helium Processing this summer to minimize Field Emission
- Installation of Individual Cryomodule Heater Control System
- Microphonics Detuning analysis, Piezo Algorithm studies and Implementation
- Control Loop Optimization
 - Investigate the loop phase mismatch between SEL and GDR
- Klystron Drive Cables
 - Detect the source of crosstalk

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Summary

- CEBAF Initial commissioning goals achieved
 - 2.2 GeV/pass
 - 123 MeV from Injector
 - CD4A – 5 months ahead of schedule
- Beam delivery to experimental halls
- Plans for improving operability

R.Bachimanchi, IPAC, May 2015, Richmond, VA

**Special Thanks to
Trent Allison, Ed Daly, Mike Drury,
Arne Freyberger, Curt Hovater, George
Lahti, Clyde Mounts,
Rick Nelson, Tomasz Plawski and
Mike Spata for their contributions in this
presentation**

R.Bachimanchi, IPAC, May 2015, Richmond, VA

Questions?

R.Bachimanchi, IPAC, May 2015, Richmond, VA