



Argonne

BERKELEY L

# **Technical Challenges of the** LCLS-II CW X-ray FEL

Tor Raubenheimer for the LCLS-II Collaboration

May 6<sup>th</sup>, 2015






# Introduction LCLS-II starts from the LCLS X-ray FEL

The LCLS is the world's 1<sup>st</sup> x-ray Free Electron Laser (FEL)


- LCLS electron source
  is the SLAC *Cu* linac
- Includes one fixed gap undulator
- Six experimental

### stations



X-ray Range	250 to 11,300 eV	
FEL Pulse Length	< 5 - 500 fs	
FEL Pulse Energy	~3 mJ (2 * 10 <sup>12</sup> @ 10 keV)	
Repetition Rate	120 Hz	

## LCLS Operations Photon Science and Accelerator Science



2009 / Run 1\*

2014-2015 / Run 10\*\*

Total # of Scientists Involved in LCLS Proposals Per Run

\* Run 1, the first operating period at LCLS, was October-December 2009.
 \*\* The Run 10 operating period is scheduled October 2014-March 2015.

IPAC'15 May 4-8, 2015

\*\*\* October 2009-October 2013 total number of scientific researchers engaged in approved research at LCLS.

2009-2013 Total Researchers\*\*\*

New SCRF linac and injector in 1<sup>st</sup> km of SLAC linac tunnel

Injector at

2-km point

Existing Linac (1

with modification

# Linac Coherent Light Source Facility and LCLS-II Upgrade (1st light 2019)

Undulators (130)

## Near Experiment Hall


K-ray Transport

Far Experiment Hall


### LCLS-II Accelerator Layout New Superconducting Linac → LCLS Undulator Hall

- Two sources: MHz rate SCRF linac and 120 Hz Cu LCLS-I linac
- Hard and Soft X-ray undulators can operate simultaneously in any mode

Undulator	SC Linac (up to 1 MHz)	Cu Linac (up to 120Hz)
Soft X-ray	0.20 - 1.3 keV with >100 Watts	
Hard X-ray	1.0 - 5.0 keV with >20 Watts	1 - 25 keV with mJ-class X-ray pulses




### LCLS-II X-ray Coverage Using SASE and Self-Seeding



## **LCLS-II Scientific Opportunities Workshop**

- Upgrades paths for existing LCLS instruments
- Enhancements for beam operations
- Guidance on operating modes for science opportunities




**LCLS-II Scientific Opportunities Workshops** 

February 9-13, 2015 SLAC National Accelerator Laboratory Menlo Park, CA



## **Project Collaboration**




The LCLS-II builds on the developments from the X-ray FEL program around the world

• Leveraged many of the LCLS design concepts

New challenges:

- CW superconducting RF system
- High brightness CW injector
- Variable gap undulators
- High beam power
- Dynamics in high brightness, low-energy electron beams


## LCLS-II SCRF Linac Layout Layout similar to LCLS (except SCRF)




**100-pC** machine layout: April 24, 2014; v21 ASTRA run; Bunch length L<sub>b</sub> is FWHM \*\* L0 cav. phases: ~(3°, -15°, 0, 0, 0, 0, 15°,0°)

- Two-stage BC w/ linearizer plus laser heater
- Uses (35) 1.3 GHz and (2) 3.9 GHz CM
  - CM design adopted from ILC/XFEL design and adapted for CW operations
  - Fabricated and tested at FNAL and Jlab
  - Prototype assembly complete December 2015 and testing through May, 2016

IPAC'15 May 4-8, 2015



## LCLS-II Cryomodule 1.3 GHz, modified for CW operation




Crymodules will be similar to EuXFEL with modifications for CW operation. EuXFEL producing 1 module/per week.

## **Superconducting RF Cavities**

Eight 1-m 1.3 GHz cavities within each CM for 280 cavities total

Backbone of the LCLS-II accelerator are the 9-cell 1.3 GHz superconducting rf cavities



Technology developed in Europe and transferred around world. Hundreds have been fabricated in US, Japan, Europe. LCLS-II and EuXFEL will use ~1200 combined

## **RF Power System** More than 1MW 1.3 GHz RF power for initial phase

Each cavity individually powered with 4 kW Solid-State Amplifier

• Specified for 0.01% energy stability and 20 fs timing stability




Example: 10 kW SigmaPhi Amp

Waveguide distribution system through 25' penetrations into linac tunnel



IPAC'15 May 4-8, 2015


### **Cryoplant and Cryogenic Distribution System** Exploring single and double cryoplant options



IPAC'15 May 4-8, 2015

Jlab CEBAF 12 GeV Upgrade 4.5 K coldbox (Linde) 'CHL 2' LCLS-II 4kW 2°K Cryoplant(s) will be based on JLAB CHL2 design


### Cryogenic Load $\rightarrow$ Maximize $Q_0$ CW linac is dominated by dynamic (RF) losses



Nitrogen-doping technology has huge impact on CW SCRF accelerators


See A. Grassellino's plenary talk from Monday: MOYGB2

# Working to understand Q<sub>0</sub> preservation into CM Details of residual field, cooldown, geometry, ...




# **LCLS-II Electron Injector**

 The LCLS-II Injector uses a 750 kV VHF RF gun based on the APEX project gun at LBNL



- Current APEX performance
  - Low dark current
  - Good cathode lifetime
  - Beam properties October


2015



### Injector Feasibility R&D

y (mm)

#### Nominal transverse parameters demonstrated at Cornell




# **LCLS-II Undulator Hall**

- The existing LCLS undulator will be removed from the hall
- LCLS-II adds two new variable gap undulators
  - X-ray energy tunability at a fixed electron beam energy




Existing LCLS Undulator



Two new LCLS-II Undulators in the tunnel


# **LCLS-II Undulator Layout**

**150 meter existing Undulator Hall** 



IPAC'15 May 4-8, 2015

## Variable Gap Hybrid Undulators Ongoing Development at LBNL and ANL




Variable gap undulators used in LCLS-II to provide greater wavelength tuning flexibility

Developing two alternates: Superconducting undulator (SCU) and a Horizontal gap vertically polarized undulator (VPU). See: E. Gluskin, TUXC1




## **X-ray Transport**

### Designed for 10 mJ peak and 200 W average X-ray power



# **High Power CW Linac**


### **Beam Collimation and Diagnostics**



- Diagnostics are based on existing for 10-300 pC/bunch
- Beam power and beam loss issues are critical
  - Designing multi-stage collimation system to control losses
  - Hybrid PM undulators sensitive to nearby losses (3 pA)
- Linac designed for 1.2 MW but undulators limited to 120 kW
  - 250 kW maximum power through linac in initial phase
  - Studying dark current and FE effects and radiation limits
- Beam dumps are modified versions of existing MW dumps

## **Collimation Studies**

### Reduce halo to 3pA loss in undulators




SLAC has a number of MW beam dumps constructed over decades of operation

 Require separated water systems with tritium separation and careful treatment of other radionuclides

30 ft

• Designed to be replaceable



FEL physics is well understood **provided** beams are well modeled

LCLS-II is being extensively modeled using 3D PIC codes

- Using 1-to-1 models with same number of macro-particles as beam electrons
- Verification runs are made using LBNL Edison Cray XC30



High brightness beams at modest energy and long transport

 $\rightarrow$  new longitudinal micro-bunching instabilities

Micro-bunching seen at LCLS and suppressed with laser heater  $\rightarrow$  adopted similar approach for LCLS-II


New effects being studied for LCLS-II using high-fidelity simulation codes (IMPACT and Elegant) and analytic models

- Sensitivity to higher-order optics
- Coupling to transverse fields

M. Venturini, J. Qiang, C. Mitchell

Simulations are being benchmarked using the LCLS at low energy

 Benchmarking configurations are chosen to exacerbate relevant physics Y. Ding, J. Qiang, D. Ratner



## Summary

LCLS has been a great success and has verified much of the critical electron beam dynamics and FEL physics

- LCLS-II being designed and constructed with strong US collaboration and support from international partners
- LCLS-II will expand beyond LCLS with:
  - CW SCRF technology
  - High brightness CW injector
  - Variable gap undulators
  - High power beams
  - Transport of 'low' energy high brightness beams

IPAC'15 May 4-8, 2015

Thank you for your attention

🛟 Fermilab

Jefferson Lab SLAC