

The SARAF CW 40 MeV Proton/Deuteron Accelerator

**A. Nagler, D. Berkovits, I. Gertz, I. Mardor, J. Rodnizki, L. Weissman
Soreq NRC, Yavne, Israel**
**K. Dunkel, M. Pekeler, F. Kremer, C. Piel, P. vom Stein
Accel Instruments, Bergisch Gladbach, Germany**

LINAC08, MO203, September 29th, 2008

SARAF – Soreq Applied Research Accelerator Facility



- To modernize the source of neutrons at Soreq and extend neutron based research and applications.
- To develop and produce radioisotopes primarily for bio-medical applications.
- To enlarge the experimental nuclear science infrastructure and promote the research in Israel.


Accelerator Basic Characteristics



A RF Superconducting Linear Accelerator

Parameter	Value	Comment
Ion Species	Protons/Deuterons	$M/q \leq 2$
Energy Range	5 – 40 MeV	
Current Range	0.04 – 2 mA	Upgradeable to 4 mA
Operation mode	CW and Pulsed	PW: 0.1-1 ms; rep. rate: 0.1-1000 Hz
Operation	6000 hours/year	
Reliability	90%	
Maintenance	Hands-On	beam loss < 1 nA/m

SARAF Layout




A. Nagler et al., LINAC 2006

SARAF project organization




Construction and Commissioning of a **(Beyond-)State-of-the-Art** accelerator within an **international business collaboration**

- Accelerator – Accel Instruments (Germany)
- Cryogenics – Linde Kryotechnik (Switzerland)
- Building and Infrastructure – U. Doron (Israel)
- Applications - Soreq




Overall Integration – Soreq


SARAF Phase I – Upstream View



SARAF Phase I – Downstream View




ECR Ion Source (ECRIS)



C. Piel EPAC 2006

F. Kremer ICIS 2007


K. Dunkel PAC 2007



LEBT – emittance measurement



magnetic
mass
analyzer




C. Piel EPAC 2006

F. Kremer ICIS 2007

K. Dunkel PAC 2007

P. Forck
JUAS
2003



EIS: measured emittance values







$\varepsilon_{\text{rms_norm_100\%}} [\pi \text{ mm mrad}]$

Particles Beam current	Protons X / Y	H_2^+ X / Y	Deuterons X / Y
5.0 mA	0.20 / 0.17	0.34 / 0.36	0.13 / 0.12
2.0 mA	0.13 / 0.13	0.30 / 0.34	0.14 / 0.13
0.04 mA	0.18 / 0.19		0.05 / 0.05

Specified value = 0.2 / 0.2 [$\pi \text{ mm mrad}$]

deuterons emittance results



deuterons




6.1 mA
open
aperture

B. Bazak
JINST 2008

aperture
cut to
5.0 mA

emittance analysis with the SCUBEEEx code by M. P. Stockli and R.F. Welton, Rev. Sci. Instr. 75 (2004) 1646

176 MHz Radio Frequency Quadrupole




RFQ commissioning results



Specifications in parentheses

Parameter	Protons
Output energy [MeV/u]	1.5 (1.5)
Maximal CW current [mA]	4.0 (4.0)
Transverse emittance, r.m.s., normalized, 100% [$\pi \cdot \text{mm} \cdot \text{mrad}$] (at 0.5 mA, closed LEBT aperture) (at 4.0 mA, open LEBT aperture)	0.17 (0.30) 0.25 / 0.29 (0.30)
Longitudinal emittance, r.m.s [$\pi \cdot \text{keV} \cdot \text{deg}/\text{u}$] (at 3.0 mA)	30 (120)
Transmission [%] (at 0.5 mA) (at 2.0 mA) (at 4.0 mA)	80 (90) 70 (90) 65 (90)
Required RF power (protons) [kW]	62 (55)
(deuterons) [kW]	248 (220)

Diagnostic plate (D-Plate) for beam commissioning




Proton energy at RFQ exit by TOF



Beam Energy Measurement using TOF
between 2 BPMs sum signals, 145 mm apart,

$$E = 1.504 \pm 0.012 \text{ MeV}$$


C. Piel PAC 2007



Button pickup for
2 mA pulse and
15 mm bore
radius gives a
signal high above
noise.

Bunch width
measured at
 $\beta=0.056$ is larger
than the predicted
value due to the
induced charge
broadening.

Current downstream RFQ vs. RFQ forward power for 3 mA injection



J. Rodnizki et al.
EPAC 2008


9/29/2008

RFQ power (PS forward) [kW]

A. Nagler et al., LINAC08, MO203

16

RFQ: Bunch profiles measurements



Wire scan profiles


C. Piel PAC 2007

Measurement results are backed up by simulations (TRACK)

FFC time profiles


Rodnizki et al.
EPAC 2008

Approximated rms ε_z extracted from bunch width measurements



Specified rms $\varepsilon_z = 120 \pi$ deg keV Value for simulations = 74π deg keV

RFQ voltage squared vs. forward power



Parting from the linear relation indicates onset of dark current due to poor conditioning


RFQ Conditioning – current status



- A few hundred conditioning hours for two years
- Conditioning schemes
 - Set maximum power and increase duty cycle
 - Set CW duty cycle and increase power
- Special actions to improve conditioning rate:
 - Rounding off sharp edges of rods bottom part
 - Cleaning of rods
 - Installation of circuit for fast recovery after sparks
- Maximal power reached so far:
 - **195 kW CW**
 - **280 kW with duty cycle of 15%**

75°C baking performed recently for 3 days. Effect on conditioning tp be measured soon

Prototype SC Module (PSM)




M. Peiniger, LINAC 2004
9/29/2008

M. Pekeler, SRF 2003
A. Nagler et al., LINAC08, MO203


General Design:

- Houses 6 HWR and 3 superconducting solenoids
- Accelerates protons and deuterons from 1.5 MeV/u on
- Very compact design in longitudinal direction
- Cavity vacuum and insulation vacuum separated



M. Pekeler, LINAC 2006

HWR – Basic parameters



- $f = 176 \text{ MHz}$ & bandwidth $\sim 130 \text{ Hz}$
- height $\sim 85 \text{ cm}$ high
- Optimized for
 - $\beta=0.09$ @ first 12 cavities (2 modules)
 - $\beta=0.15$ @ 32 cavities (4 modules)
- Bulk Nb 3 mm @ 4.45 K
- $E_{\text{peak, max}} = 25 \text{ MV/m}$ & $E_{\text{peak}} / E_{\text{acc}} \sim 2.5$
- $Q_0 \sim 10^9$
- Designed cryogenic Load $< 10 \text{ W} (@E_{\text{max}})$

HWR measured fields and dissipated power



Closed loop operation with a voltage controlled oscillator (VCO)

At Accel (single cavity)

At Soreq (inside PSM)

Cavity		vertical Test			max field	limit	Q at	Q at	losses at	losses at	
location	name	max field	losses at	Q at			20 MV/m	25 MV/m	20 MV/m	25 MV/m	
		[MV/m]	25 MV/m	25 MV/m	[MV/m]				[W]	[W]	
			[W]								
HWR1	LB-2	40	7,3	6,0E+08	30		8,0E+08	7,0E+08	3,5	6,3	
HWR2	LB-3	43	7,3	6,0E+08	28	coupler temp.	2,0E+08	1,4E+08	14,1	31,4	
HWR3	LB-5	33	6,3	7,0E+08	32		4,0E+08	2,0E+08	7,0	22,0	
HWR4	LB-7	46	6,3	7,0E+08	29		4,0E+08	2,0E+08	7,0	22,0	
HWR5	LB-4	36	5,5	8,0E+08	31		7,0E+08	4,0E+08	4,0	11,0	
HWR6	LB-6	38	7,3	6,0E+08	29	coupler temp.	7,0E+08	3,0E+08	4,0	14,7	
		sum	40,0						Σ	39,7	107,3
Target values		25		4.7E+08	25			4.7E+08		72	

C. Piel et al. EPAC 2008

Phase and amplitude stability results



**SARAF LLRF:
Generator driven
resonator (GDR)
cavity tuning loop**


Cavity	Vcav, MV	Epeak, MV/m	Phase Stab., °	Ampl. Stab., %
HWR 1	0.8	23.5	±0.3	0.5
HWR 2	0.7	20.6	±0.3	0.5
HWR 3	1.0	29.5	±0.3	0.5
HWR 4	0.9	26.5	±0.3	0.5
HWR 5	1.14	33.5	±0.2	0.5
HWR 6	1.03	30.3	±0.3	0.3

- Above results are for operation of one cavity at a time
- Stability measurement period was a few minutes for each cavity
- Stability values are peak-to-peak and are limited by ADC least significant bit


Recent commissioning: simultaneous operation of 6 HWRs at ~20 MV/m for several hours

Residual activation from beam loss

- A beam loss value of **0.4 nA/m** at 40 MeV generates **2 mRem/hr** after a 1 year irradiation



SARAF Phase II simulations with error analysis



Simulations shown in next slides:

- 4 mA deuterons at RFQ entrance.
- Last macro-particle=1 nA


B. Bazak *et al.*, Submitted for Publication
J. Rodnizki *et al.*, HB2008

Component	Error	Static	Dyn.
Quadrupole Magnets	Misalignment x,y,z [mm]	± 0.2	
	Rotation θ [mrad]	± 3	
	Magnetic field [%]	± 2	0.5
Solenoids	Misalignment x,y,z [mm]	± 0.2	
	Magnetic field [%]	± 2	0.5
HWR	Misalignment x,y,z [mm]	± 0.4	
	Rotation θ [mrad]	± 6	
	Field strength [%]	± 2	0.5
	Phase [degree]	± 1	0.25

Errors are double than in: J. Rodnizki *et al.* LINAC 2006, M. Pekeler HPSL 2005

Deuteron beam envelope radius at SARAF SC Linac

Solenoids 19



B. Bazak *et al.*, Submitted for Publication
J. Rodnizki *et al.*, HB2008

General Particle Tracer 2.80 2006,
Pulsar Physics S.B. van der Geer,
M.J. de Loos <http://www.pulsar.nl/>

Summary and Outlook



■ SARAf Phase I Commissioning status:

- Extensive proton beam commissioning through RFQ performed
- First deuteron and H_2^+ beams accelerated in RFQ
- On-going RFQ RF conditioning to enable CW deuteron and H_2^+ beams
- RF commissioning of the PSM to enable beam acceleration through it

■ Simulations of Phase II

- Beam loss criterion for hands-on maintenance is 0.4 nA/m at 40 MeV
- Tail emphasis simulations indicate beam loss below 1 nA/m