ReA3 – the rare isotope re-accelerator at MSU





U.S. Department of Energy Office of Science National Science Foundation Michigan State University

MICHIGAN STATE UNIVERSITY

Why reaccelerated beams at the NSCL?

- NSCL is a user facility based on rare isotope production by projectile fragmentation and projectile fission
 - NSCL has successful program with stopped beams LEBIT facility for Penning trap mass spectrometry of projectile fragments – laser spectroscopy under preparation



More than 900 RIBs have been made – more than 600 RIBs have been used in experiments

 ReA3 opens new science opportunities with rare isotopes produced by projectile fragmentation

- Nuclear astrophysics: key reactions at near-stellar energies
- Nuclear structure via Coulomb excitation or transfer reactions



U.S. Department of Energy Office of Science National Science Foundation Michigan State University



Concept and scientific motivation

- Reacceleration concept:
 - Beam stopper (linear gas stopper, cyclotron stopper or solid stopper)
 - High-intensity electron beam ion trap (EBIT) as $1+ \rightarrow n+$ charge breeder
 - Room temperature RFQ and Superconducting RF Quarter Wave Resonators in 3 cryomodules



ReA3 at the Coupled Cyclotron Facility

- Coupled cyclotrons primary beams : ~ 150 MeV/u secondary beams with E < 100 MeV/u
- ReA3 beams : 0.3 3 MeV/u for Q/A=1/4 rare isotope beams





U.S. Department of Energy Office of Science National Science Foundation Michigan State University

ReA3 at the Coupled Cyclotron Facility



ReA3 on the platform



ReA3 platform





U.S. Department of Energy Office of Science National Science Foundation Michigan State University



ReA3 – EBIT charge breeder

• Unique features:

- Continuous injection of ions
 - » high capture rate
- Variable extraction duty cycle
 - » µs pulse to quasi-continuous
- Short breeding time (<10 ms)
- High efficiency
 - > 50% in a single charge state





EBIT installation will be completed in October, Simulations are performed to optimize performance, Injection tests end of 2010!



U.S. Department of Energy Office of Science National Science Foundation Michigan State University

MICHIGAN STATE

EBIT electron beam tests

- Measurements of electron beam diameter
- High current tests with 0.9 A with negligible losses on the electrodes
- Electron beam simulation compared with measured beam properties









U.S. Department of Energy Office of Science National Science Foundation Michigan State University



Tests with 'mama' cathode



Injection calculation using SIMION





U.S. Department of Energy Office of Science National Science Foundation Michigan State University



Injection simulation results





U.S. Department of Energy Office of Science National Science Foundation Michigan State University

Low energy beam transport (LEBT)





U.S. Department of Energy Office of Science National Science Foundation Michigan State University

$\frac{\text{MICHIGAN STATE}}{\text{U N I V E R S I T Y}}$

Emittance Scans

- RFQ transverse acceptance >
 - $\epsilon_n = 1.0 \pi$ -mm-mrad
 - $\epsilon_g = 200 \pi$ -mm-mrad (@ RFQ input energy of 12 keV/u)
- Desired twiss parameters α = 0.6 and β = 0.06 m

– Measured beam emittances fit into RFQ transverse acceptance



MICHIGAN STATE

R S

V

U

Ν



U.S. Department of Energy Office of Science National Science Foundation Michigan State University

Emittance Scans

- RFQ transverse acceptance >
 - $\epsilon_n = 1.0 \pi$ -mm-mrad
 - $\epsilon_g = 200 \pi$ -mm-mrad (@ RFQ input energy of 12 keV/u)
- Desired twiss parameters α = 0.6 and β = 0.06 m
 - Measured beam emittances fit into RFQ transverse acceptance





U.S. Department of Energy Office of Science National Science Foundation Michigan State University

 $\frac{\text{MICHIGAN STATE}}{\text{U N I V E R S I T Y}}$

Multi Harmonic Buncher (MHB) test with timing wire detector











U.S. Department of Energy Office of Science National Science Foundation Michigan State University

MICHIGAN STATE

RT 4-rod RFQ ReA3





New design:

- Al-tank (no copper plating required)
- Simple adjustment of tuning plates, no alignment required
- High power operation

RFQ installed in beam line, Conditioning started, Beam tests in September 2010!



U.S. Department of Energy Office of Science National Science Foundation Michigan State University MICHIGAN STATE

Flatness tuning



Tuned voltage flatness at 80.374 MHz tuned with plungers out 2.5% 2.0% 1.5% 1.0% Delta U in [%] 0.5% 0.0% -0.5% -1.0% -1.5% 0 10 11 12 13 14 15 16 17 18 2 9 1 3 8 5 **Cell number**

tuning plate







U.S. Department of Energy Office of Science National Science Foundation Michigan State University



RFQ conditioning and low power beam transport



U.S. Department of Energy Office of Science National Science Foundation Michigan State University

MICHIGAN STATE

ReA3 SRF-cryomodules

ReA3 -

- 3 ReA3 Cryomodules
- 15 cavities
- 2 cavity types (QWR)
 - Beta=0.041 & 0.085
 - Same as FRIB design
- 8 solenoids
 - Same as used in FRIB

First two cryomodules completed, third in progress to be completed Q2FY2011

re-buncher

MICHIGAN STATE

UNIVERSITY

$\beta = 0.085 \text{ module}$

U.S. Department of Energy Office of Science National Science Foundation Michigan State University

ReA3 – QWRs testing

NSC FRIB

Michigan State University

ReA3 – SRF component tests

Test of systems in the modules:

- Power coupler conditioning and operation
- Magnetic shielding
- ➤ Low level rf
- Damping of microphonics
- > Q versus E_z measurements
- Determination of static heat load
- Multipacting analysis

For details see poster THP039 THP092

Magn. Shielding tests

ReA3 Coupler for $\lambda/4$

U.S. Department of Energy Office of Science National Science Foundation Michigan State University

 $\frac{\text{MICHIGAN STATE}}{\text{U N I V E R S I T Y}}$

SRF-LINAC infrastructure

SRF-LINAC infrastructure

Summary ReA3 status

- ➤ Test of EBIT electron beam system done, magnet commissioned, assembly ongoing → first operation October
- > Q/A-separator beam commissioning completed
- LEBT beam commissioning is presently performed
- RFQ tuning completed, conditioning ongoing, first beam tests in early September 2010

➤ SRF-linac:

- re-buncher rf-tests completed, first beam tests in conjunction with RFQ beam commissioning
- $-\beta = 0.041$ module installed, hardware tests are being performed
- $-\beta = 0.085$ under construction
- > Accelerated stable beams \rightarrow end of 2010
- Reaccelerated beams in 2011

ReA6/ReA12

