



Fermilab 1.3 GHz Superconducting RF Cavity and Cryomodule Program for Future Linacs

Camille M. Ginsburg (FNAL)
September 10, 2012


Fermilab 1.3 GHz SRF Overview

- International Linear Collider motivated substantial infrastructure development and progress
- Project X builds on this
 - 3 GeV CW linac requires high Q0 at gradients $15 < E_{\text{acc}} < 20$ MV/m; studies use 1.3 GHz cavities
 - 3-8 GeV pulsed section is 1.3 GHz, ILC cavities at $E_{\text{acc}} \sim 25$ MV/m
- Cavity preparation and qualification
 - Cavity inspection, surface processing, clean assembly, low-power bare cavity tests and pulsed high-power dressed cavity tests
 - Peripheral hardware, e.g., tuners and couplers, under development
- Cryomodule assembly
 - Well performing cavities assembled into cryomodules for pulsed high-power tests, and will be tested with beam.
- Status, accomplishments and plans

ANL/Fermilab 1.3 GHz cavity proc'ing infrastructure



electropolishing



clean assembly



tumbling machine



high-pressure rinse



ultrasonic rinse



vacuum furnace



new R&D EP tool at FNAL

Fermilab test and assembly infrastructure




vertical test



VTS1



VTS2 Dewar (=VTS3)



cavity tuning machine



cavity inspection (Kyoto/KEK)



HTS



Class-10 string assembly



cold mass assembly







final cryomodule assembly

ILC 1.3 GHz Cavity Performance Benchmark

1st pass

2nd pass







International cavities from established vendors using established processes
 2nd pass yield for **>35 MV/m** for integrated sample is (57 +/- 8)%
 for 2010-2012 alone is (69 +/- 13)%

ILC 1.3 GHz Cavity Performance Benchmark

1st pass

2nd pass




International cavities from established vendors using established processes
 2nd pass yield for **>25 MV/m** for integrated sample is (80+- 7)%
 for 2010-2012 alone is (92 +- 7)%


Americas 1.3 GHz Cavity Performance

Status Aug.30, 2012


Americas 9-cell Cavities First test



Americas 9-cell Cavities First test




Americas 9-cell Cavities Last test



- ❖ Fermilab stewardship for 80 ILC cavities plus 1-cell prototypes
- ❖ Cavity vendor qualification
 - AES (done), Niowave-Roark, PAVAC (ongoing)
- ❖ Excellent performance achieved
 - Strong collaboration with JLab, Cornell,...
 - Infrastructure development

1.3 GHz cryomodule assembly

CM1



- ❖ CM1 (8-cavity+dummy magnet)
 - Assembled at Fermilab from a DESY “kit” which included all parts from DESY and INFN
 - Was operated at NML
- ❖ CM2 string (8-cavity + magnet)
 - Cavities were processed and vertically tested at JLab
 - Dressed and horizontally tested at FNAL
 - Assembled and leak checked at FNAL
 - Good chance for first ILC spec CM in US
- ❖ CM3 is next



CM2



Acknowledgements and Advertisements

- Many thanks to our Fermilab, national, and international collaborators for their hard work and excellent contributions to the cavity and cryomodule development presented here
- For this presentation, material was provided by M. P. Kelly (ANL), R. Geng (JLab), T. Arkan, M.S. Champion, L.D. Cooley, C.Cooper, A. Hocker, T. Khabiboulline, J.P. Ozelis, T. Peterson, A. Rowe, D.Sergatskov, A. Sukhanov, V. Yakovlev (FNAL).
- We are greatly indebted to the technical staff in Technical Division who make everything work.
- Please see the following related talks/posters
 - V. Yakovlev MO1A03
 - A. Grassellino MOPB078
 - S. Henderson TU1A01
 - A. Yamamoto TH3A01