


A 3D architectural rendering of the IFMIF-EVEDA 9 MeV 125 mA deuteron LINAC. The image shows a large, complex industrial facility with multiple buildings, pipes, and structural elements, all rendered in a light blue and grey color scheme. The text is overlaid on the image in a bold, purple font.

STATUS OF THE IFMIF-EVEDA 9 MeV 125 mA deuteron LINAC


Linear IFMIF Prototype Accelerator (LIPAc)

- aims at generating materials irradiation test data for DEMO and future fusion power plants
- based on an accelerator-driven, D-Li neutron source to produce high energy neutrons at sufficient intensity and irradiation volume

High	> 20 dpa/an	0.5 L
Medium	> 1 dpa/an	6 L
Low	< 1 dpa/an	8 L


Deuteron source
140 mA, 100 keV

SRF Linac 40 MeV
(Half Wave Resonators)



Total neutron flux $\sim 10^{18}$ n/m²/s
with a broad energy peak near 14 MeV

LIPAc = prototype for IFMIF
includes all critical accelerator components
to be tested at nominal beam current at EA site



- **Objectives**


- Validate the IFMIF accelerators
(up to 1st accel module = the most critical portion)
- Qualify all associated technologies
- Characterize the beam by means of specific diagnostics

- **Main Tasks**


- Design and manufacturing of all components
- Integration of the whole Linac within the building and auxiliaries
- Commissioning in pulsed mode (H+, D+)
- Ultimate goal: Operation in CW of a 125 mA D⁺ beam at 9 MeV

The engineering validation activities conducted since mid-2007 under the framework of the Broader Approach Agreement and shared as follows:

- Accelerator components designed, manufactured and tested by European institutions (CEA, CIEMAT, INFN, SCK-CEN)
 - Injector (CEA)
 - Radio Frequency Quadrupole (INFN)
 - Medium-High Energy Beam Transport lines & Beam Dump (CIEMAT)
 - Superconducting RF Linac (CEA + CIEMAT)
 - 175 MHz RF Systems (CIEMAT)
 - Beam Instrumentation (CEA + CIEMAT)
- Conventional facilities (building and auxiliaries), Central Control System, RFQ couplers provided by Japan (JAEA)
- Design integration & interface management coordinated by F4E
- Coordination & integration on site by the Project Team hosted in Rokkasho




Conventional Facilities Accelerator system



Cryogenic plant 85 W @4.5 K + 38 l/h

ECR ion source


Extraction: 175 mA total (140 mA D^+ , 26 mA D_2^+ , 9 mA D_3^+)




New 5-electrode extraction system after sparking issues at 100 kV


- ⇒ high level of space charge compensation all along the LEBT line to meet the requirements: emittance (0.25π mm mrad) + RFQ matching
- injection of a specific gas in the line (krypton 4.10^{-5} hPa)
 - HV electrode in front of the RFQ to trap the electrons (e-repeller)

LEBT no beam loss, optimum injection into RFQ






Equipped LEBT





Ion source on HV platform



View-port after 1st solenoid

- **Beam Intensity:** Large ACCT (Φ 178 mm) at the RFQ entrance with specific magnetic shielding
- **Beam Profile** and species fraction (Doppler shift method): use of rad-hard CID cameras and CCD camera outside the vault with fiberscope
- **Emittance:** Allison scanner to sustain 17 kW beam power
- **Space charge compensation:** 4 Grid Analyzer to measure the energy of secondary ions or electrons repelled out of the beam



Need of pulsed mode with sharp rise/fall times

(to limit transient current which would be lost downstream)





with beam perfectly matched to the RFQ input conditions all along its duration

But **ECR ion source**: not able to produce such beam pulses


RF cutting technique in the RFQ: could jeopardize the RFQ operation

⇒ **electrostatic chopper** located in the Injector LEBT
(between the 2 solenoids)

In addition, as a chopper is able to produce short pulses $< 100 \mu\text{s}$
this option enables the use of interceptive diags



- First pulsed H⁺ beam in May 2011
First test campaign: pulsed beams 150 mA ,100 kV
or continuous beams 100 mA, 75 kV
- First pulsed D⁺ beam in May 2012 (125 mA, 100 kV, 1%)
- New 5-electrode extraction system installed in September
Test campaign starts again at mid-September for completion of the optimization and emittance measurement:
ion source plasma, krypton pressure, solenoid setting, ...
- Electrostatic chopper in-between the two solenoids to enable the LIPAc operation with short pulses of sharp rise/fall times
Tests of chopper (w/o beam) in September 2012
- Injector delivery at Rokkasho planned in March 2013



Main parameters selected



- ✓ Increasing voltage following an analytic law
- ✓ Strong focusing ($B=7$) to keep the tune depression > 0.4 for better control of space charge
- ✓ Min. beam loss & main resonances avoided in the accelerator section

This design allowed to obtain a good transmission with good margin

- ✓ But a lower focusing parameter B at the RFQ entrance will further facilitate beam injection from the LEBT

A low-B RFQ studied and adopted

- ✓ Studies of the transmission of the couple LEBT+RFQ show a more comfortable tunable range





Sensitivity to mismatch: scan of solenoid fields

RFQ

96 % transmission (140 mA)


Losses mainly in the first part,
at low energy

Input emittance $< 0.2 \pi$ mm mrad





However, emittance at the LEBT exit
must be kept low $< 0.3 \pi$ mm mrad

- 18 Cu modules ~10 m
- 22 slug tuners/quadrant
- 10 cryo-pumps
- 8 couplers




Cooling: ~ 600 kW RF power removed by means of 28 channels longitudinally drilled along the RFQ modules (water velocity ~3 m/s)

Cooling system (4 independent circuits) used for frequency tuning ($\pm 100\text{kHz}$) and field profile control



Cooling water channels


Full scale Al mockup to validate tuning procedure & mode stabilization by means of beadpull measurements



technological prototype
machined at INFN and local industries, brazed at CERN



2 prototypes scale 1/2
brazed in 1 single step




Vacuum ports



Vanes

- **High Energy super module** (6 modules homogenous aperture)
rough-machining by INFN (electric discharge machining)
final machining and brazing by Indusry
- **Intermediate Energy super module** (6 modules z-dependent aperture)
fully machined and brazed by INFN
- **Low Energy super module**
same procedure as High Energy modules



module #16 (High Energy SM)
machined & brazed

First module: 100 μm max deformation measured
still acceptable but at the limit of the specification
might be corrected for the next modules by using




- appropriate annealing cycle
- improved fixation tooling

3 modules (plus RF plug) completed in Nov 2012
for high power tests, planned at the beginning of
2013 at INFN-Legnaro.

2 RF couplers manufactured
delivered at INFN-Legnaro
at beginning 2013 for power tests


- (1) couplers only
- (2) Couplers + RFQ modules

manufacturing of the other couplers will start
just after approval of the acceptance tests.




very compact ~ 2 m, many components

- 5 quadrupoles & steering coils
- 2 bunchers, 2 movable scrapers
- BPMs (in the center of quads)
- turbomolecular pumps on bunchers (1300l/s /buncher)





Scrapers: to clean the beam from transverse halo and off-momentum particles (non-accelerated in the RFQ) before the SRF Linac



designed for 500 W beam power deposition
beam dynamics prediction < 10 W

Bunchers: 5-gap IH structure


- Voltage EoLT = 350 kV
- Cavity length < 350 mm
- CW & pulsed mode operation




Buncher: prototype under fabrication, power tests planned at mid-2013

Quadrupole: prototype completed and validated on a magnetic test bench

Scraper: manufacturing completed






8 resonators ($\beta=0.094$)
Tuning system
Coaxial coupler

8 solenoid packages
SC magnet (6 T)
Steerers and BPM

Uncommon procedure:

1. Match beam rms envelope, then
2. Minimise radial beam extension

→ **“Halo matching” instead of “Envelope matching”**



■ 8 s.c. Half Wave Resonators

- low- β HWRs = 0.094
- working temperature 4.4 K
- Accelerating field ~ 4.5 MV/m

■ 8 RF power couplers


- operating mode CW,
- RF power: 200 kW (70 kW LIPAc)

■ 8 Superconducting Solenoid Packages


- focusing solenoid
- H&V steerers
- cryogenic BPM

- **Cryostat** with all necessary equipment (supports, cryogenic distribution, alignment, vacuum, magnetic & thermal shields, instrumentations, etc)

Parameters	Target Value	Units
Frequency	175	MHz
β value of the HWR	0.094	
Accelerating field E_a	4.5	MV/m
Quality factor Q_0 for $R_s=20$ n Ω	$1.4 \cdot 10^9$	
Beam aperture HWR / Solenoid Package	40 / 50	mm
Freq. range of HWR tuning system	± 50	kHz
Max. transmitted RF power / coupler	200	kW
External quality factor Q_{ex}	$6.3 \cdot 10^4$	
Transmission Lines for HWR	coax 6" 1/8	
Magnetic field B_z on axis max.	6	T
$\int B \cdot dl$ on axis	≥ 1	T.m
Field at cavity flange	≤ 20	mT
BPM position accuracy	0.25	mm
BPM phase accuracy	2	deg
Total Static/Dynamic Heat losses	18 / 120	W




Cold tests at 4.2 K
Quench at ~ 260 A
(210 A nominal)




2 prototypes completed, tested when RF power sources will be available, end of 2012

- **Two cavity prototypes** completed in Summer 2010, delivered in Sept'10



- **Original tuner design:** relied on a capacitive plunger with a large membrane to allow an elastic deformation of ± 1 mm
- **First troubles** during cryogenic tests reported in May 2011




Potential risks



- high peak magnetic field at membrane center
- Helicoflex gasket in region of significant field
- NbTi flange: poor thermal conductivity
- Fabrication issue: neck region contains two NbTi/Nb welds in a recessed area

Results of HWR vertical tests with plunger

Last cold tests of HWR prototypes with modified plunger (March & April 2012)
Nb membrane, In gasket, suppression of high field at the membrane center



- Systematic thermal quenches at low field and drop of Q_0
 - Results point to a suspect plunger
 - potential problems occurring in the main cavity body cannot be also ruled out
- ➔ Following up the recommendations of a Review Panel, a new design based on **a conventional compression tuner** principle is under development





- Tuner only acts in one direction (compression)
- 800 kg on each side
- Lever ratio of ~ 30


Given the rigidity of the present resonator design, this solution implies a lengthening of the cryomodule lattice ~ 10 cm to ease the integration of the tuner between HWR tank & solenoid

**$\Rightarrow$ modification of the tank and cavity and
has to be compliant with JA regulations (mechanical stress)**


Total cryomodule extra-length ~ 80 cm








First quadrupole Triplet







Quadrupole Doublet



Last quadrupole Triplet



Maximum field
Inside the yoke ~1.8 T




Magnetic measurements on specific test bench at ALBA /CELLS (rotation coil and Hall probe) & Elytt installation (Hall probe)


Reasonable magnetic field in the magnet (~ 1 T in legs)
Only saturation in the shims on the pole edges
Non-linearity error $< 0.1\%$.

Beam stopper at the end of the straight
beamline: ~ 350 ms max time to detect
and stop the beam





Beam dump with its local shielding
water + polyethylene (neutron)
iron (gamma)



Cartridge

Inner & outer cones = Cu (edp)
Cooled by liquid water (high v, 3 bar)
 $T \sim 100^\circ\text{C}$ not too far from boiling

Remote disconnection system



- HEBT & Beam Dump in final stage of detailed design
- Cone prototypes built: electron beam welding and electro-deposition
- Hydraulic test cooling circuit





Hydraulic circuit: to study the fluid-dynamics aspects of the beam dump cooling (flow and pressure measurements, vibrations, heat transfer coef estimation,...)



- Current monitors (ACCT, DCCT, FCT)
- Beam Position monitors x 20
- Beam Profile monitors (ionization & fluorescence)
- Beam Loss monitors (ion chambers)
- Micro-Loss monitors (diamond)
- Bunch length monitor (Residual gas, GSI-like)
- Interceptive: SEM grid + slits (Espread, Emit)

Diagnostics Plate





IPM

Principle: ionization of the residual gas


Residual gas pressure: few 10^{-8} to 10^{-5} mbar

Resolution ~ 1 mm **Profile rate** $\sim$ few Hz


Apertures >10 cm for DP >15 cm for HEBT



Test at GSI (5 MeV/A, mA)



IPM in front of BD



Challenges: Large aperture (15×15 cm²)

- Radiation hardness ~ 7 kSv/h (neutrons)
- ceramic (HV + strip plates) field uniformity

FPM


Principle: fluorescence by interaction of the beam with the residual gas

2 read-out prototypes tested


- ICID (Intensified Charge Injection Device) camera (MCP + CID)
- PMT: multi anode 32 channels linear array

Campaign tests at CNA cyclotron Sevilla:

D⁺: 9 MeV and H⁺: 18 MeV




ICID camera



Extrapolation to LIPAc (125 mA) OK


new tests done at Sevilla (Oct 2011)

...improved profile measurements




- Prototype RF module (1 x 200kW) ready end of 2012
- First RF module (2 x 100kW) ready beginning of 2013
- 16 kW solid-state amplifier (buncher) ready at mid-2013

Parameter	Value
Operating Frequency	175 MHz
Bandwidth	± 250 kHz @ -1 dB
Phase Stability	$\pm 1^\circ$
Amplitude Stability	$\pm 1\%$
Power Linearity	1%
Full Output RF Power	200kW
Operating Modes	CW or pulsed mode
20kW CW Reflected Power	2 hours
RF Power Emergency Stop	<10 μ s
200kW Reflected Power	10 μ s



Market survey done
Call for tender soon





PC (Power Coupler for cavity)
CL (Current Leads for solenoid)

Process Flow Diagram

Heat loads estimation

	Cryomodule	Transfer line MCTL
Static heat loads at 4.4 K		
Heat radiation from 55 K (thermal shield)	3.75 W	8.3 W
Heat radiation from 300 K (beam pipe, PC)	5.8 W	+ 19.8 l/h
Conduction from 55 K (including CL and PC without current and RF)	6.7 W	
Conduction from 300 K (including CL and PC without current and RF)	5.4 W	
CL (0 amps)	5.25 l/h	
PC (no RF)	5.53 l/h	
Static total	30 W + 30 l/h	
Dynamic heat loads at 4.4 K		
RF	54.4 W	
CL (I nominal)	3.5 l/h add.	
PC (with RF)	3.7 l/h add.	
Dynamic total	54.4 W + 7.2 l/h	
TOTAL at 4.4 K	84.8 W + 37.2 l/h	





END