



ARIEL Superconducting Electron Linac for Rare Isotope Program at TRIUMF




LINAC'12, Tel Aviv,
Israel, 2012 Sept 12

Shane Koscielniak
for e-linac team



- **Motivation: RIB science at ISAC**
- **Challenges of high-power CW SRF**
- **ARIEL Civil Construction**
- **E-linac progress – if time permits**
- **Conclusion**

ARIEL triples RIB science at ISAC



ARIEL E-linac, LINAC 12, 2012 Sep 14

10-Year Vision: expanded RIB program with:




- three simultaneous beams
- increased number of hours delivered per year
- new beam species
- increased beam development capabilities

Implementation:


- Complementary electron linac driver for photo-fission
- New target stations and front end
- New proton beamline
- Staged installation

Photofission

Photofission of ^{238}U was proposed by W. T. Diamond 1999 as an alternative production method for RIB.



E-Linac Physics Requirements



Number of photo-fission /second versus electron energy for 100 kW e-beam on Ta convertor and U target.

For in-target fissions up to $5 \times 10^{13}/\text{s}$




Photo-fission products distribution using 50 MeV 10 mA electrons on Hg convertor & UC_x target

Beam power (MW)	0.5
Duty Factor	100%
Average current (mA)	10
Kinetic energy (MeV)	50

E-Linac: Accelerator Overview

Accelerator:


Two cryomodules
Two cavities/module,
10 mA, 40 MeV gain
 ≤ 400 kW beam power

Injector:

10 mA, 5-10 MeV gain
 ≤ 100 kW beam power

300 keV thermionic gun:
650 MHz modulated

NC Buncher




ARIEL Phase I:
25 MeV, 200kW

ARIEL Phase II:
50 MeV, 500kW

Installed Cryoplat for Phase I & II

E-Linac in e-hall



Adapt existing equipment designs when possible

- E-linac funding is based on the condition that it be useful to the nuclear physics AND high energy physics (e.g. ILC).
- Moreover, a design tenet was to adopt or adapt existing equipment design wherever possible.
- Hence the building block is a **modified** TTF style 9-cell cavity.



Challenges of CW operation

- Higher heat load in all RF components: cavity, input coupler, HOM absorber, etc
- Limited choice of c.w. klystrons, c.w. couplers

	Fission driver, 10 MV/m 4 cavity	ERL mode 20 MV/m 4 cavity	TESLA TDR 23.4 MV/m 12 cavity
RF Load (W)	41.6	166.4	4.95
2K Sum (W)	44.4	251.5	9.05
5K Sum (W)	29.1	34.5	15.94
Input Couplers	713	265	80.9
80K Sum (W)	717.6	601.2	183.02

Beam power related


2K & 80K sums almost 4× TESLA values

Challenges of CW operation

- TESLA/ILC poster child for high gradient & low duty factor.
 - Static heat load $\gg$ dynamic load
 - Cryomodule design emphasis: “keep the heat out”
 - ARIEL e-linac, and Cornell ERL Injector, are poster children for high-power CW electron linacs.
 - Dynamic heat load $\gg$ static load.
 - Cryomodule design emphasis: “get the heat out”
 - Larger diameter chimney to 2-phase pipe*
 - Slightly larger diameter LHe jacket
 - No 4K thermal shield – not cost effective
- *c.f. BESSY FEL CM: heat-flow $< 1 \text{ W/cm}^2$ at 1.8 K

High-power CW input couplers

- RF Couplers are a heat load both to the cavity and to themselves.
- This is a problem already solved by Cornell since 2007.





S. Belomestnykh:
Cryomodules for
high current CW
linacs and ERLs;
2007 July 26

Choice of cold tuner

CW low gradient operation has benefits

- No periodic beam-load transients & small Lorentz-force detuning
- No need for piezo actuators
- Small number of cavities, makes e-linac vulnerable to loss of a cold tuner.
- To mitigate risk, a warm tuner drive was chosen to operate a modified Jefferson lab screw jack tuner.



“Backlash free”
demonstration

Cavity Shape & HOM damping

- Use Cornell coupler → must increase pipe OD c.f. TTF cavity
- For the single-pass RIB beam, low bunch charge (16pC) → marginal (or no) need for HOM damping

▪ **BUT dream of adding recirculation path for RLA or ERL operation**


▪ HOM damping target set by Regenerative (2-pass) BBU instability

▪ 20-40mA BBU threshold if $(R/Q)Q < 10^7$ for all modes

▪ 9 cell cavity

▪ Inner 7 cells TTF geometry

▪ Modified end groups for larger coupler & HOM damping




Two 50 kW Cornell/ CPI coupler per cavity



Calculated HOMs spectra for variety of geometries with SLANS and CST $\mu\lambda$

“Tuner side” SS
ring damper




Coupler side C-Si
ring damper

Tuner side	Inner 7 cells	Coupler side
39	35	48
48	35	48
55	35	48
39	37	48
55	40	48


Iris radii (mm)

Cavity & HOM Damping

HOM frequency spectrum and shunt resistance for 9-cell cavity




- 39/35/48 mm iris geometry gives the lowest maximal $(R_d/Q) \times Q_L$
- Damping by SS ring on coupler end, CESIC ring on tuner end
- All modes $(R_d/Q) \times Q_L < 2 \times 10^6$ ohm




Cavity Status

2011 Dec Success:
7 out of 7 PAVAC/TRIUMF
single-cells meet Q0
requirements

- 7 cell Cu cavity delivered 2012 Feb
- Nine cell cavity design fixed & tooling optimized
- Four Nb cells formed and welded
- 9-cell delivery 2012 Dec



Injector Cryomodule




Cryomodule concept borrows significantly from ISAC-II


Top loading box concept with cavity mounted to strongback that is suspended from struts

Box gives headroom for on-board 2K/4K HX and 4K separator


- All procurements in hand
- Fabrication underway
- Cavity, 4K/2K insert (95% done)

EINJ: Injector Cryomodule Detailing






Accelerator Cryomodule



- Single-cavity EIJ prototypes most features of two-cavity EACA design.
- 2011 June: focus narrowed to completion of EIJ design, and fabrication in 2012



ARIEL Civil Construction

Site Preparation: demolition, relocation, construction



- **2011 October**
- **CONGESTED SITE**
- **Old Stores & RH Demolition**
- **Excavation and shoring**
- **Makes way for ARIEL building**



New Badge building



TRIUMF

New Stores Bldg



Ground Breaking:
2011 March

Completion:
2011 September



New Badge Building



Construction started:
2011 August

Occupancy:
2011 November



Helium Compressor Building




Foundations,
structural steel,
perimeter wall:
2012 July 30




- Envelope cladding, roof, mech & elec services 2012 Sept 03
- Expect occupancy: 2012 December

ARIEL building design



The culmination of an intensive study of what is needed to facilitate smooth and routine RIB delivery.

ARIEL layout



Excavation, Shoring, Construction

Excavation started: 2011 November




ARIEL site: 2012 May

Tunnel

ARIEL site: 2012 Aug 29

Building occupancy
expected: 2013 April



RIB Annexe




Actinide target Labs & hot cells




ARIEL Construction

Target Hall



Tunnel




Electron Hall

Electron Hall Renovation: shielding



North Wall:
shield e-hall from BL4N



- South wall B2 up to ground for ERL/RLA
- Final pour, 2012/April



Electron Hall Renovation: crane, catwalks, etc



E-hall 2012 March 13




Breakthrough from ARIEL
tunnel to E-hall, July 7th

**E-hall 2012 Sept 03, prior to
sealing roof beams**



Expect E-hall occupancy 2012 October

Siemens 12.47 kV Switchgear, factory test 2012 Aug 23




The 5MW gear will feed:

- 1.5MW to klystrons,
- 0.5 MW emergency power,
- north to the ARIEL building (2 MW)
- south to the Helium compressor building (1 MW)

**Delivery to TRIUMF
Dec 2012**


E-linac Progress Report

Electron Gun Components



SF6 vessel & Gun RF modulation


RF horns and ceramic waveguide



Eimac cathode

rf matching network

Successful dielectric waveguide R&D program with scale model & HFSS




Transmission optimized at 650 MHz

300 kV 10 mA Electron Gun Gun Status

- Most long lead items delivered
- SF6 vessel tender package released: 2012 Sept




Electrode polishing under way



Installation begins: 2012 Dec

Cryogenic System Design/Procurement



- White boxes: TRIUMF responsibility
- Pale blue boxes: cryopant ordered from Air Liquide Advanced Technology, 2011 Oct

Supplied by ALAT



Helial Cold Box



Main Compressor



Figure 6 : CSD 82 View


Recovery Compressor

Schedule

2013 March: ALAT cryoplant
at TRIUMF

2013 October: commissioned

Successful Final Design Review
concluded 2012 May15




Oil removal & Gas
Management System

Cryo-plant specs

The plant shall demonstrate 3 modes:


- Mixed Mode: $>130\text{W}$ @ $4,6\text{K}$ and 242 L/h
- Liquefaction: 288 L/h at 4.6K in the dewar
- Refrigeration: 600W at 4.6K in the dewar



**ALAT Helial-2000
cold box**

Other major components

- Dewar in hand; will widen neck
- He Purifier- procure in collaboration with FNAL
- **LHe Distribution System: tender issued 2012 Aug**
- 2K sub-atmospheric components:
 - Pumps: contract awarded 2012 Aug
 - He heaters: prototyping



Fabrication 2012 Aug 02

He buffer tanks modeled on ISAC-II

- Tanks rated 15 Bara
- Capacity $\sim 113 \text{ m}^3$ each
- Delivery 2013 Jan


Sub-atmospheric pumps



	Phase1	Phase2
ICM	1.9gm/sec	1.9gm/sec
ACM1	3.7gm/sec	3.7gm/sec
ACM2	NA	3.7gm/sec
Sub-total	5.6gm/sec	9.3gm/sec
Total	5.6gm/sec	9.3gm/sec


- BUSCH –Combi DS3010-He
- Dry technology – roots blower & screw type backing pump
- Four units ordered 2012 Aug
- Delivery 2013 February

High Power RF staging: 5mA, 25 MeV in 2014




30 kW IOT Transmitter

- IOT transmitter will be used for EIJN beam test 2013 Jan;
- RF input coupler conditioning (10kW) 2012 March onward



- 2011 June: Tube operated tube in excess of 30kW
- 2011 July: Successful acceptance tests: ran cw at 30 kW for 24 hours, at 25kW for 40 hours and at 20 kW for 7 days without trip.
- Now running routinely


Coupler Conditioning Stand in ISAC/VECC test area



1.3 GHz 290 kW klystron & HVPS procurement

Require 200kW cw for EACA (2-cavity) cryomodule

- 2011 Aug: 290kW Klystron ordered from CPI, USA
- Coordinated purchase with Helmholtz Zentrum Berlin
- 2012 Aug: Final design review
- 2013 Jan: klystron factory test




600kW 65kV Power Supply


- 2012 Feb: Tender issued
- 2012 June: Awarded Thomson Broadcast
- 2012 Aug: Preliminary design review

- **Outstanding Progress Across All Areas**
- **Buildings Construction – on schedule for 2013 April**
- **Injector Cryomodule beam test – on schedule for 2013 March**
- **Accelerator Cryomodule beam test – on schedule for 2014 June**



ELBT at ISAC/VECC test stand



VECC ELBT Test1 – 2011 Dec/2012 Feb



Allison emittance scans performed 2012 Feb 09 onward up to to 660W beam power at $\sim 20\text{W/mm}$




VECC ELBT Test2 – 2012 July

Fast Faraday Cup (8 mA peak current)
Bunch length ≈ 200 ps, consistent with estimate by conduction angle.

Deflector Commissioning

- Phase locked to Gun RF
- Scan buncher phase/amplitude and observe beam movement in spectrometer



Phase scan at 0, 90, 180,
270 deg – Open loop

