

# **Major Upgrade Activity of the PLS in PAL: PLS-II**

**S. H. Nam**  
**on behalf of the PAL staff**

**Pohang Accelerator Laboratory (PAL)**  
**POSTECH**

**May 7, 2009**

**Particle Accelerator Conference 2009**  
**Vancouver, British Columbia, Canada**

**PAL**



- Total Land Area : 651,031 m<sup>2</sup>
- Total Building Area: 41,846 m<sup>2</sup>
- Number of Building: 15





# PAL: Chronology

---

## I. PLS

▪ Project started	Apr. 1 1988
▪ Ground-breaking	Apr. 1 1991
▪ 2-GeV Linac commissioning	June 30 1994
▪ Storage ring commissioning	Dec. 24 1994
▪ <u>User's service started</u>	<u>Sept. 1 1995</u>
▪ <u>1<sup>st</sup> PLS Upgrade Complete</u>	<u>Nov. 1 2002</u>
✓ Energy ramping to 2.5 GeV	Sept. 1 2000
✓ 2.5-GeV injection	Nov. 1 2002

## II. 2<sup>nd</sup> Major Upgrade of the PLS (PLS-II)

▪ 3.0 GeV PLS-II Upgrade begin	Jan. 2009
▪ <u>3.0 GeV PLS-II Upgrade Complete</u>	<u>Dec. 2011</u>

# Major Goal of the PLS-II Upgrade

Item	PLS	PLS-II
Increase Energy	2.5 GeV	3.0 GeV
Lower Emittance	18.9 nm·rad	5.6 nm·rad
Increase Stored Beam Current	200 mA	400 mA
<b>Increase No. of IDs</b>	<b>10</b>	<b>&gt;20</b>
<b>Increase Brightness</b>	<b><math>\sim 2 \times 10^{18}</math></b>	<b><math>\sim 10^{20}</math></b>
Change Lattice Type	TBA	DBA
Change Operation Mode	Decay	Top-up

# PLS-II Project Summary

- Project Period: 3 years (2009 – 2011)
- Total Budget: US 100 M\$
- Yearly Budget: in US M\$ (1U\$ = 1000 Won)

Item	Year			Total
	2009	2010	2011	
Storage Ring	15.1	25.11	9.42	49.63
Linac	8.57	5.97	1.6	16.14
Beamline	5.46	11.82	6.62	23.9
Utility	0.87	3.5	5.96	10.33
Total	30.0	46.4	23.6	100.0

Linac & BTL





# Current Linac



**Gallery**

- Thermionic Electron Gun
- 12 Pulse Modulators (200MW)
- 12 Klystrons (80 MW, 4us)
- 11 Energy Doublers ( $g=1.6$ )
- 44 Accelerating Sections

## Injector LINAC

- Length = 160m
- 2.5GeV, full energy injection
- 2,856 MHz (S-band)
- 10Hz, 1.5 ns, 1A pulsed beam



**Tunnel**



## Performance Upgrade Goal of the PLS-II Linac

	PLS	PLS-II
<b>Energy</b>	<b>2.5 GeV</b>	<b>3 GeV</b>
<b>Repetition Rate</b>	<b>10 Hz</b>	<b>10 - 30 Hz</b>
<b>Energy Stability</b>	<b>0.5% rms</b>	<b>0.1% rms</b>
<b>Energy Spread</b>	<b>0.6% rms</b>	<b>&lt; 0.2% rms</b>
<b>Emittance (normalized, rms)</b>	<b>150 mm mrad</b>	<b>&lt; 20 mm mrad</b>
<b>Gun Pulse Length</b>	<b>1.5 ns FWHM</b>	<b>&lt; 1 ns FWHM or 0.5 us</b>
<b>Klystron Power (Operating Levels)</b>	<b>50 – 60 MW</b>	<b>70 – 80 MW</b>
<b>SLED Gain</b>	<b>1.5 – 1.6</b>	<b>1.6 – 1.7</b>
<b>Diagnostics</b>	<b>BCMs, BASs, BPRMs</b>	<b>+ BPMs, Slits, Wire Scanners</b>




# PLS-II Gun: Comparison of Various Gun Systems

	PLS	PLS-II	
Number of Guns	Single Gun	Single Gun with fast replacement	Dual Gun
Beam Energy	80 keV	80 keV	180 keV
Beam Current	1 A peak	1 A peak	1 A peak
Pulse Length	1.5 ns FWHM	< 1 ns FWHM or 0.5 – 1 us	< 1 ns FWHM or 0.5 – 1 us
HVPS Type	DC	DC	Pulse
Beam Transmission	80%	60%	70%
Pro & Cons		1. Compact & Economic 2. Good for Short Pulse Generation	1. On-line Switching between Guns is Possible 2. Large Pulse Lengthening 3. Complex & Expensive



# MW System: Current 2.5 GeV Linac

1. 12 klystron&modulator systems
2. MK01&12: two accelerating columns
3. MK2 to MK11: four accelerating columns
4. The klystron drive uses main drive line.
5. Klystron Out Power: 50-60 MW (~19 MV/m)




# Linac MW Layout (2.5GeV $\rightarrow$ 3.0GeV Energy Upgrade)


	MK1 1(set)	MK2 - MK10 9(set)	MK11 – MK14 4(set)
Klystron output power	60 MW	72 MW	70 MW
Model	SLAC5045	Toshiba E3712	
Number of A/C	2	36	8
Type of A/C	IHEP		Commercial
Av. energy gain of SLED	NA	~1.6	
Gradient of A/C		22.6 MV/m	31.6 MV/m



# Klystron-Modulator



# Waveguide Windows and SLEDs in the Gallery



# Linac/BTL Beam Instrument of the PLS


Instrument	No.		Operation	Remark
	Linac	BTL(BAS)		
BCM	7	5(1)	0	OK
BPRM	4	5(1)	0	OK
BLM	42	12	0	Need controller
BPM	13	13(1)	Linac pickup install(~2009.8)	Need DAQ
			BTL pickup ok	Operation
Beam Charge Monitor		1(1)	ICT install	Need DAQ
YAG screen monitor		1(1)	screen	Need Controller
Gallery environment	1		operation	SLED, gallery, driver line
Beam slit		1(1)	X	Need controller/monitor



# Storage Ring



# Current PLS Storage Ring






- Beam Energy 2.5GeV
- Beam Current 200mA
- Lattice TBA
- Superperiods 12
- Circumference 280 m
- Emittance 18.9 nm-rad
- Tune 14.28 / 8.18
- RF Frequency 500 MHz
- Energy spread  $8.5 \times 10^{-4}$

## PLS Orbit Requirements

<1% x-y coupling>

	Beam Size		Orbit Stability	
	Horizontal	Vertical	Horizontal	Vertical
Bending Magnet	230 $\mu\text{m}$	24 $\mu\text{m}$	23 $\mu\text{m}$	2.4 $\mu\text{m}$
Insertion Devices	455 $\mu\text{m}$	35 $\mu\text{m}$	45 $\mu\text{m}$	3.5 $\mu\text{m}$








# PLS-II Photon Source Parameters


	Long SS	Short SS	Bending Magnet
Number	9 or 10	11	24
Length or Bending R (m)	6.8	3.1	6.875
$\beta_x$ (m)	6.16	2.84	0.38
$\beta_y$ (m)	4.90	2.46	14.14
$\eta_x$ (m)	0.21	0.17	0.037
$\sigma_x \times \sigma_y$ (mm <sup>2</sup> )	234 x 17	167 x 12	47 x 28

# Issues on lattice design / Limitation overcome

## Straight section for IDs



## Usage of present wall





# PLS-II IDs and Expected Photon Beam Performance

Species of ID (Tentative, Not fixed yet)

## X-ray undulator (6EA)

Period : 2 cm Length : 2 m Field : 1.2 T  
Brightness :  $4E19$  @ 2 keV

## EPU6 (6 EA)

Period : 6cm Length : 4 m Field : 0.69 T  
Brightness :  $1E19$  @ 0.8 keV


## U7 (4EA)

Period : 7cm Length : 4m Field : 0.99T

## MPW (4EA)

Period : 14 cm Length : 2 m Field : 2 T


U7-Undulator brightness





APR15

Plan 1







## Diagnostics in PLS-II

	Monitor	Qty.	Function
<b>Electron</b>	<b>Beam Position Monitor</b>	<b>96</b>	<b>Beam Position</b>
	<b>DC Current Transformer</b>	<b>1</b>	<b>Average Beam Current</b>
	<b>Stripline Electrode</b>	<b>2</b>	<b>Tune, Beam Damping</b>
	<b>Screen Monitor</b>	<b>3</b>	<b>Beam Position (Commissioning)</b>
	<b>Scraper</b>	<b>1</b>	<b>Beam Trimming, Dynamic Aperture</b>
<b>Photon</b>	<b>Photon Beam Position Monitor</b>	<b>36</b>	<b>Frontend Beam Position</b>
	<b>Diagnostic Beamline</b>		
	<b>X-ray</b>	<b>1</b>	<b>Beam Profile, Beam Size</b>
	<b>Visible Light</b>	<b>1</b>	<b>Beam Size, Bunch Length</b>

# PLS-II Magnet System Layout



# *Magnet System for PLSII*

Type	Number	Key Parameters	Remarks
Gradient	24 (2 X12)	1.4555 T, 4.0828 T/m Gap=34 mm, $L_{\text{eff}}$ =1.800 m	All powered in series
Quadrupoles	96 (8 X12)	4 types, Max Gradient 22T/m, $R_c$ =36 mm	Powered in family series with independent aux coils.
Sextupoles	144 (12 X12)	Max $B'$ =550 T/m <sup>2</sup> $R_c$ =39 mm, 6 types	SkewQ, V-corrector, H-corrector, combined function
Kicker Magnet	4		Recycle existing one
Lambertson Septum	1	3.0 GeV, 8 or 6 vertical bending,	



## PLS-II RF system

Parameters	PLS-II RF	PLS RF
Current [mA]	<b>400</b>	<b>200</b>
RF frequency [MHz]	499.66	500.082
Total beam loss power (kW)	<b>696</b>	<b>130.2</b>
Accelerating Voltage [MV]	<b>3.3</b>	<b>1.6</b>

- To provide the required RF power and control beam instabilities at higher energy and beam currents with more high field IDs, the current PLS RF needs to be fully replaced with a new system.



## PLS-II RF system

### Possible cavity choice and its corresponding facilities

	NC	SC
Number of cavity	6	3
RF voltage per cavity [MV]	0.55	1.1
Wall loss power per cavity [kW]	44.5	0.013
Beam load power per cavity [kW]	112	223
RF Power need per cavity [kW]	163	232
Number of high power system	250 kW $\times$ 6	300 kW $\times$ 3
Number of LLRF system	6	3
Cryogenic heat load power (W)	0	650
Need for the storage ring tunnel space	1–Long SS	1.5Long-SS * 1 Long-SS+1Short-SS ** 1 Long-SS **

- \*3 CESR or KEKB SRF cavities;
- \*\* 2 CESR or KEKB SRF cavities+1 modified SRF cavity;
- \*\*\* 1 cryomodule installed with 3 single-cell cavities.






## PLS-II RF system

---


6 sets of normal conducting RF system.






# PLS-II RF system

3 sets of superconducting RF system.






# Control System Standard Open Architecture





# Control System : Overall Configuration





# Girder System

## - Design Consideration

### ➤ **Natural Frequency : >30 Hz**

- ✓ **Horizontal SR Building : 3.48 – 4.26 Hz**
- ✓ **Vertical SR Building : 5.67 – 6.93 Hz**
- ✓ **Outstanding Frequency : 19.2, 23.8, 29.8 Hz**

### ➤ **Girder System Basic Requirement**



- ✓ **Girder Adjustment Full Range : >50 mm**
- ✓ **Girder Deformation :  $\pm 30$  .**
- ✓ **Active Mover System : Cam Mover and Screw Jack**
  - **Cam Mover Full Range :  $\pm 5$  mm**
    - **Remote Automatic Control (HLS, HPS, LVDT)**
  - **Screw Jack Full Range :  $\pm 50$  mm**
    - **Localized Manual Control**





# PLSII Girders System


© Modeling of girder system






# PLS-II Girder System

## ◎ Magnet Girder of Half Cell



- The girder consist of two girders, which we denote girder long(GL) and girder short(GS)
- The half cell is composed of a dipole magnet, 4 quadrupole magnets and 6 sextupole magnets.
- Dipole magnet, equipped with three supports, will form a bridge between the two adjacent girders.



# Summary

---

- **PLS-II has completed its major design and started component purchase.**
- **Final detail design will be reviewed by the PAL international advisory committee (IAC) on June 2009.**
- **TDR will be published in June 2009.**
- **The project is expected to finish on time and budget.**

---

**Thank you for your attention!!**

**As usual, we are expecting very close  
collaboration and help from light  
source facilities all around world!**