

Canada's national laboratory for particle and nuclear physics Laboratoire national canadien pour la recherche en physique nucléaire et en physique des particules







Commissioning of the 20MV Superconducting Linac Upgrade at TRIUMF

Marco Marchetto | TRIUMF

Accelerating Science for Canada Un accélérateur de la démarche scientifique canadienne

Owned and operated as a joint venture by a consortium of Canadian universities via a contribution through the National Research Council Canada Propriété d'un consortium d'universités canadiennes, géré en co-entreprise à partir d'une contribution administrée par le Conseil national de recherches Canada



Summary

o Introduction

- ISAC facility
- o ISAC-II project
 - ISAC-II Phase II upgrade
 - Beam commissioning results
- o Operational experience
 - Beam delivery
 - Future program
- o Conclusions



o Introduction

- ISAC facility
- o ISAC-II project
 - ISAC-II Phase II upgrade
 - Beam commissioning results
- Operational experience
 - Beam delivery
 - Future program
- Conclusions



ISAC at **TRIUMF**



Most intense radioactive beam of certain species



ISAC in the world

Lab	Facility	Туре	Driver	Post- accelerator	Voltage (MV)	Energy (MeV/u)
Existing						
TRIUMF	ISAC	ISOL	500MeV, 50kW	RFQ, DTL, SCL	52.5	6.5-18
CERN	ISOLDE	ISOL	1.4GeV, 2.8 kW, p	RFQ, DTL	13	3
GANIL	Spiral-I	ISOL	3kW HI	cyclotron		~5-25
ORNL	Holifield	ISOL	50MeV, 500W p,d	tandem	25	
ANL	CARIBU	Gas- catcher	Radio-active source	ATLAS sc linac	52	~7-17
Future						
CERN	HIE-Isolde	ISOL	1.4, 2.8kW, p	SCL	40	6.5-18
MSU/ NSCL	FRIB	Gas- catcher	400kW HI	RFQ, SCL		12-20
GANIL	SPIRAL-II	ISOL	200kW d	cyclotron		5-25



ISAC driver



- \circ H⁻ cyclotron as proton driver;
- $_{\odot}$ ISAC proton accelerated to 500 MeV up to 100 $\mu\text{A};$
- \circ ARIEL : one more proton line for RIB production. Cyclotron can operate at 300 μ A.







Target stations and Mass separator





Experimental facilities



April 1, 2011



ISAC I Linac





o Two normal conducting acceleratorso RFQ

- 8m long CW machine
- 150 keV/u, 3≤A/q≤30
- high quality transverse and longitudinal emittance: 0.2 π µm and 1.5 π kev/u·ns.

o DTL

- Separated functions
- Five IH interdigital RF cavities
- Three split-ring bunchers
- Variable energy machine
- 150 keV/u ≤ E ≤ 1.8 MeV/u, 2≤A/q≤7
- ISAC II injector 1.5 MeV/u



Summary

- o Introduction
 - ISAC facility
- o ISAC-II project
 - ISAC-II Phase II upgrade
 - Beam commissioning results
- Operational experience
 - Beam delivery
 - Future program
- Conclusions



ISAC-II – The idea

- The idea (~1999) was to expand ISAC capabilities
- Need higher energies to support Nuclear Physics studies at and above the Coulomb barrier:
 - Goal energy E≥6.5MeV/u for A/q=6 with full energy variability
 - The decision was to develop a superconducting heavy ion linac of 40MV
- Need broader mass range to A~150
 - Add ECR Charge State Booster (CSB) to increase the charge state for A>30 to meet the RFQ A/q acceptance



ISAC-II SC-Linac





ISAC-II QWR Cavities



ISAC-II design values: V_{eff} =1.1MV, P_{cav} =7W, E_p =30MV/m, H_p =60mT

April 1, 2011



Phase II Upgrade

- o 7.5M\$ project
 - 2.7M\$ cryogenics refrigerator and distribution
 - 1.4M\$ cavities
 - 2.4M\$ cryomodules
 - 1M\$ infrastructure RF amplifiers, power supplies, installation
- <u>Development of PAVAC Industries</u> as a Canadian supplier of bulk niobium SRF resonators
- Initiated development in 2007, ordered production cavities March 2008
- Tight schedule mandated end date of March 31, 2010
- Coincided with the end of the TRIUMF Five year plan and also the end of project budget
- The project was completed on time and on budget



Developments/Challenges

- Production/development
- Frequency tuning after manufacture
 - New procedure for fine-tuning frequency using etching developed
- o Hardware
 - Mechanical tuner with brushless servo-motor and anti-backlash ball screw
 - Variable coupler with improved mechanical stability
 - Clean venting system through RF pick-up ports
- o A few challenges
 - Four cavities developed vacuum leaks after etching at TRIUMF
 - RF amplifier company went bankrupt after delivery of 11 units
 - Competition with planning for next five year plan initiated 1.3GHz program



Clean room cold test

- Each cryomodule undergoes a cold test prior to delivery to the vault
- Establish warm off-sets for cold alignment using WPM and optical targets
- Check cavities and RF systems
- Measured cryogenic static load – 14-18W
- o Establish vacuum integrity
- o Check solenoid operation





Cavity characterization

<u>Preparation</u>: cavities are degreased, chemically etched, rinsed with high pressure water, dried and then assembled on test frame



- Single cavity tests yield an average performance of 32MV/m at 7W (14% below Phase I)
- (Fact) Due to vacuum leaks after 100 μm the etching specification was reduced to 60 μm
- (Speculation) Marginal etch reduced performance; study in progress.



- All the hardware (optics, vacuum, diagnostic) is commissioned prior to send beam through the linac
- Coast the 1.5 MeV/u beam from ISAC-I: optics beam commissioning
- Solenoids perform as expected:
 - no significant steering (good alignment)
 - superconducting solenoid are set to theoretical values while matching the beam into the SC linac with quadrupoles





 ¹⁶O⁵⁺ accelerated to 10.8MeV/u equivalent to 6.5MeV/u for A/q=6 (meets ISAC-II original specification on first acceleration)

RIUMF

- SCB's set to average $E_p=30.3MV/m$, SCC's set to average $E_p=27MV/m$
- One cavity unavailable in SCB and Four cavities unavailable in SCC due to RF cable problems





Beam quality - transverse emittance



Commissioning of the 20MV Superconducting Linac Upgrade at TRIUMF - PAC11 conference



Beam quality – transverse emittance

- Beam from the ECR ion source (Pantechnik SUPERNANOGAN) with no stripping in the MEBT section
- Measured emittance is in line with the expected value of 0.2 π mm mrad
- In line with SCB measured emittance
- o No emittance growth
- Expected beam quality confirmed at the high energy experimental stations







Beam quality – longitudinal emittance









Summary

- o Introduction
 - ISAC facility
- o ISAC-II project
 - ISAC-II Phase II upgrade
 - Beam commissioning results
- o Operational experience
 - Beam delivery
 - Future program
- Conclusions

RETRIENT ISAC-II Phase II installation schedule

- o Vault installation began September 2009
 - Beam line removed
 - Cryogenic distribution installed (Linde TC50 600W commissioned)
- Final cryomodule installed March 24
- First beam (¹⁶O⁵⁺) was accelerated <u>April 24</u>
- First stable beam to an experiment April 25
- First RIB's accelerated May 3









Operational Experience

- Multipacting (low level)
 - Some cavities require extensive multipacting conditioning; low voltage pulse conditioning over a few weeks reduces impact
- o **RF cables**
 - Four cables have developed in vacuum shorts; suspect high forward power during conditioning; we are fixing them (present shutdown)
- o RF amplifiers
 - Solid state amplifiers of Phase II more stable than tube amplifiers of Phase I; Phase I amplifiers need retuning as tubes age
- Cavity performance (Q) in SCC3 significantly less than single cavity test
 - suspect Q-disease or trapped flux under investigation
- \circ Cryogenics
 - Impurities in Phase I cold box and motor failure in Phase I compressor cause downtime



Species delivered

- Accelerator immediately in heavy use. The following beams have been accelerated with the SC linac since April 2010 (most of them delivered to experiment).
- o Stable beams
 - 16O5+, 4He2+, 16O8+, 15N4+, 20Ne5+,
- Radioactive beams with stable pilot
 - 26Na, 26Al6+, 26Mg6+
 - 78Br14+ from Charge State Booster
 - 6He1+, 12C2+
 - 24Na5+, 24Mg5+
 - 11Li2+, 22Ne4+



Energy Booster Stripping Foil





Charge State Booster

- 14GHz Phoenix ECR source from Pantechnik
- o Breeding efficiency 2-5%
- Commissioned with stable beam ⁸⁵Rb¹⁴⁺ and radioactive ⁷⁸Br¹⁴⁺
- All RIBs come with contaminants from the background gas
- Need to purify the beam in flight . Development is in progress.





Beam purification

- o Most experiments need at least 90% pure beam
- $\circ~$ Different species with similar A/q (within 0.5%) are accelerated at the same time
- Contaminants have much higher (few order of magnitude) intensity of the desired RIB
- o In flight purification techniques being developed:
 - Mass resolution in transport lines
 - Time of flight separation after energy degradation
 - New particle identification diagnostics



Demonstration of beam line resolution technique

ISAC UC_x Target Fr Yields

 Comparison of experimental Fr yields with in-target production predictions of 3 models

FRIUMF

- The absence of ²¹⁵⁻²¹⁷Fr experimental yields is due to the msec half-lives of these nuclides which do not survive release from the target matrix
- o 214m Fr (t_{1/2} = 3.4 ms) & 218m Fr (t_{1/2} = 22 ms) were observed at ~ 5 × 10⁵/s

Courtesy of M. Dombsky





ISAC and **ARIEL**

- SC linac is the post accelerator for the future ARIEL facility
- New complementary driver (e-linac): electron driver for Photo-Fission
- New target stations and mass separators
- New front end and post accelerators
- Goal: <u>three simultaneous</u> <u>radioactive beams</u>
- o RIB multi-users facility





Summary

- o Introduction
 - ISAC facility
- o ISAC-II project
 - ISAC-II Phase II upgrade
 - Beam commissioning results
- Operational experience
 - Beam delivery
 - Future program
- o Conclusions



Conclusions

- o ISAC-II Phase II project
 - A 7.5 M\$ project with R+D stretching over five years
 - Completed on time and on budget
- o ISAC-II now at full energy
 - ISAC-II now can boost heavy ions to and above the Coulomb Barrier (unique ISOL facility)
 - ISAC-II linac meets specification
 - High beam quality available for experiments.
- ISAC is a main reference for RIB facilities world wide



Thank you Merci