

Upgrade of Accelerator Complex at Pohang Light Source Facility (PLS-II)


Kyung-Ryul Kim
PAL/POSTECH

On behalf of PAL Staffs Joined in the PLS-II Project


Contents

- **Status of PLS-II Accelerator System**
 - Upgrade of PLS-II Linac Full Energy Injector
 - Upgrade of PLS-II Beam Injection
 - Upgrade of PLS-II Storage Ring Systems
 - Magnet Lattice and Beam Dynamics
 - Beam Diagnostics and Control
 - SR Sources: Magnet and ID Systems
 - Magnet Power Supply System
 - Vacuum System
 - RF System
 - Sector Girder and Alignment System
 - Upgrade of PLS-II Utility/Infrastructures
- **PLS-II SR and Infrastructure Dismantling, Installation and Commissioning**
- **On-going Activities and Outlook**



Aerial View of PAL/POSTECH Campus




Aerial View of PAL/POSTECH Campus




Aerial View of PAL/POSTECH Campus



Aerial View of PAL/POSTECH Campus



Aerial View of PAL/POSTECH Campus



Linac



SR



Beamline

PLS Operation Issues and User's Demands

- Nation's Reliable and Mature Multi-user Large-Scale Light Source Facility

- Elaborate Cutting-Edge Scientific Needs from User Community

- **More Fine Beam Orbit Stability and Reliability**

- Need more correlated analysis between e-beam performance and photon beam stability
- Need well-established orbit control scheme to be adaptable into the proper PLS operation environment
- Fine beam control requirements, especially ID users

- **High Flux and Brilliance Beam**


- Meet advanced user's research demands
- More ID beamlines at lower operation and construction costs through PLS upgrade (PLS-II)

Overview of PLS-II Project

- PLS-II Project Schedule : FY 2009 - FY 2011 (3 years)
- Project Organization : PAL PLS-II Project Team (including domestic and abroad expertise joined) with a support of KOSUA
- Project Cost Breakdown (only machine upgrade) (US M\$)

Systems	Fiscal Year			Total Budget
	2009	2010	2011	
Storage Ring	15.1	25.11	9.42	49.63
Linac	8.57	5.97	1.6	16.14
Beamline	5.46	11.82	6.62	23.9
Utility and Infrastructures	0.87	3.5	5.96	10.33
Total Budget	30.0	46.4	23.6	100.0

Key Milestones of PLS-II Project



Status of PLS-II Accelerator System



Foundation of PLS-II Accelerator System Upgrade

Concepts of PLS Upgrade Plan for the PLS-II

- Established PLS-II design work with a great help from Prof. Helmut Wiedemann in October 2008.
 - Justification of the PLS Upgrade (lower beam emittance, higher photon energies as well as more straight sections for insertion devices in the PLS-II)
 - Outlined the scope of upgrade (storage ring lattice, hardware systems, beam monitoring/diagnostics, top-up operation and linac energy upgrade in the PLS-II)
 - ID and photon source calculation (photon beam performance in the short and long straight sections)

Classification of PLS-II System Upgrade Structures

● Scope of PLS-II Upgrade

- ✓ **Magnetic Lattice** : low emittance of 5-7 nm at 3 GeV with a number of 20 ID sections (TBA→DBA)
- ✓ **Bending Magnets** : small pole gap of 34 mm compared to 56 mm in PLS
- ✓ **Quadrupoles and Sextupoles** : new more sextupoles for much stronger focusing
- ✓ **Vacuum Chamber** : newly designed and constructed
- ✓ **Beam Position Monitors** : more stable support from the girder
- ✓ **Magnet Power Supplies** : depending on the number of magnets and adjustment of beam dynamics
- ✓ **RF System** : sustain the 400 mA at 3 GeV, HOM-damped style (NC, SC) cavity be implemented
- ✓ **Linac Upgrade for Top-up** : upgrade to 3 GeV and sustain stable beam condition
- ✓ **Photon Beamline-Relocation and Heat Load Issue** : newly designed for high heat load components such as photon mask, shutter
- ✓ **R&D on Key Components** : In-vac Undulator and DCM, Microwave Components, Others


Upgrade of PLS-II Linac Full Energy Injector

● PLS-II Linear Accelerator of 3.0 GeV



Parameters	PLS	PLS-II
Energy	2.5 GeV	3.0 GeV
Repetition Rate	10 Hz	10 - 30 Hz
Energy Stability	0.5% rms	0.1% rms
Energy Spread	0.6% rms	< 0.2% rms
Emittance (normalized, rms)	150 mm mrad	< 20 mm mrad
Gun Pulse Length	1.5 ns FWHM	< 1 ns FWHM or 0.5 us
Klystron Power (Operating Levels)	50 – 60 MW	70 – 80 MW
SLED Gain	1.5 – 1.6	1.6 – 1.7
Diagnostics	BCMs, BASs, BPRMs	+ BPMs, Slits, Wire Scanners

Upgrade of PLS-II Linac Full Energy Injector (cont.)

Preinjector Layout and Bunch Train





80 KeV @ Gun
 Peak current : 1 A
 Pulse width : 0.2 ns
 Beam size : 10 mm
 Beam transmission : 54 %



Upgrade of PLS-II Linac Full Energy Injector (cont.)

● Preinjector Layout and Bunch Train




- Parameter of bunching system has been optimally adjusted into Bunch Length of 12 psec.

Upgrade of PLS-II Linac Full Energy Injector (cont.)

Linac Layout and Energy Upgrade to 3.0 GeV





Number of klystrons	16
Klystron power (MW)	80
SLED Gain	1.5
No. of accelerating columns	46
Total length (m)	160




Upgrade of PLS-II Linac Full Energy Injector (cont.)

	MK1(1set)	MK2 – MK08(7set)	MK09-MK14(6set)	MK15-MK16(2set)
RF Power	60 MW	70MW	70 MW	70 MW
Klystron	SLAC5045	Toshiba E3712		
A/C	IHEP			Mitsubishi
SLED Gain	w/o	1.5		1.5
Gradient	18.3 MeV/m	20.9 MeV/m	29.6 MeV/m	29.6 MeV/m
Energy	105.8 MeV	251.0 MeV	177.5 MeV	177.5 MeV
Number of A/C	2	28	12	4


$E = 3.286 \text{ GeV}$



20.9 MV/m, 251.0 MeV



29.6 MV/m, 177.5 MeV






29.6 MV/m, 177.5 MeV

Upgrade of PLS-II Linac Full Energy Injector (cont.)

	MK14(6set)	MK15-MK16(2set)
RF Power	60 MW	70 MW
Klystron	SLAC E3712	
A/C		Mitsubishi
SLED Gain	w/	1.5
Gradient	18.3 MeV/m	29.6 MeV/m
Energy	105.8 MeV	177.5 MeV
Number of A/C	2	4



E = 3.28




W

K16

177.5 MeV

🍌 RF Synchronization of SR and Linac

PAL




Upgrade of PLS-II Linac Full Energy Injector (cont.)

Linac Beam Energy Stabilization

Beam
Position

#12
RF Phase




Fluctuation:
 ± 0.5 mm
Resolution:
10 MeV/mm


PLS-II Linac requirement: 0.2% energy spread:
 $3 \text{ GeV} \times \pm 0.2\% = \pm 6 \text{ MeV} \Rightarrow \pm 0.6 \text{ mm @ BPM}$

Upgrade of PLS-II Beam Injection

Horizontal Plane




Vertical Plane






VB3 : Rotation Angle : 7.17° Downward
SEP : Rotation Angle : 8.234° Downward

Typical orbit distortion after correction







	PLS	PLS - II	Change
Kicker 1- Kicker 2 distance (center-to-center)	1.24 m	1.590 m	+0.35 m
Septum length (longitudinal)	1.068 m	1.335 m	+ 25%
Expected bump height	~ 12 mm	~ 15 mm	+ 3 mm
Vacuum pumps	3 x 240 l/s	6 x 120 l/s	22/51

Upgrade of PLS-II Beam Injection





Upgrade of PLS-II Beam Injection




Upgrade of PLS-II Beam Injection





Layout of Injection Straight Section



Upgrade of PLS-II Beam Injection



	Distance D (mm)	Field (T)	Angle (rad)	Energy (GeV)	Bump H (mm)	Length (m)
PLS	1260	0.165	0.011867	2.5	15.0	0.6
PLS-II	1590	0.165	0.009889	3.0	15.7	0.6



Magnet Lattice and Beam Dynamics

Electron Beam

Energy	3 GeV
Current	400 mA
Emittance	5.8 nm
Emittance coupling	< 1%
Energy spread	0.1%

Straight Section

Long	length, #	6.86 m × 9
	$\beta_x / \beta_y / \eta_x$	6.46 m / 4.32 m / 0.25 m
	effective emittance	9.5 nm
Short	length, #	3.10 m × 11
	$\beta_x / \beta_y / \eta_x$	2.95 m / 2.86 m / 0.14 m
	effective emittance	8.5 nm

Lattice



Circumference	281.82 m
Tune (h/v)	15.24 / 9.17
Natural chromaticity (h/v)	-32.88 / -15.49
Momentum compaction factor	0.0013

Magnet

Bending	24 units, length 1.8m
Rectangular	Bending radius 6.875m
	field gradient -0.4 T/m
Quadrupole	96 units, length 0.24~0.53m
	field gradient ~22 T/m
Sextupole	144 units, length 0.1~0.2m
	2nd field derivative ~600 T/m²

Magnet Lattice and Beam Dynamics (cont.)

Magnetic Lattice Design of PLS-II Storage Ring





Electron Beam Parameters

Energy	3.0 GeV
Current	400 mA
Emittance	5.8 nm·rad
Emittance coupling	< 1%
Energy spread	0.1%



Magnet Lattice and Beam Dynamics (cont.)

Dynamic Aperture and Lattice Performance



With aperture (H: 21 mm / V: 4 mm)

The vertical BSC is limited by the vertical aperture of 13 mm in the bending magnet vacuum chamber. The horizontal limit of BSC is given by the standard chamber with an aperture of 36 mm in quadrupoles.



Magnet Lattice and Beam Dynamics (cont.)

Alignment error (rms)

Bending magnet : 150 μm



Roll for all magnets : 200 μrad

Quadrupole / Sextupole : 100 μm

Main magnet field error: $2 \cdot 10^{-4}$


Multipole contents

Dipole	Systematic errors	Random errors
3 (b3/b1)	-1.88e-4	2.0e-4
4	2.55e-4	2.0e-4
Quadrupoles	Systematic errors	Random errors
3	0	0.00013
4	0	7.20e-5
5	0	1.26e-5
6	4.57e-4	2.34e-5
7	0	2.34e-5
8	0	2.34e-5
9	0	2.34e-5
10	2.50e-5	2.34e-5
14	2.52e-4	2.34e-5
Sextupole	Systematic errors	Random errors
4	0	0.00075
5	0	0.00075
6	0	0.00075
7	0	0.00075
8	0	0.00075
9	0.003	0.00075
10	0	0.00075




Magnet Lattice and Beam Dynamics (cont.)

Corrected chromaticity: ~ 0.2



Corrected chromaticity: ~ 5




ID tracking

ELEGANT

(Ying Wu's canonical integration code)

$$B_y = -|B_0| \sum_{m,n} C_{mn} \cos(k_{xl}x) \cosh(k_{ym}y) \cos(k_{zn}z + \theta_{zn})$$

$$k_{ymn}^2 = k_{xm}^2 + k_{zn}^2; k_{zn} = 2\pi n / \lambda_w$$



Beam Diagnostics and Control

Beam Diagnostics System





■ Design Requirements of Beam Diagnostics

- Satisfy the requirements of commissioning, machine study, routine operation and the performance upgrade
- Provide beam intensity, orbit information, transverse and longitudinal profiles, energy and many beam parameters
- Distribute the diagnostics tools around the accelerator, incorporating signal-processing electronics in analogue or digital way for data acquisition and further analysis

Electron Beam Parameters	Instruments	Description	Quantity
Beam position meas. (first-turn, turn-by-turn, closed orbit feedback)	Digital BPM	- Machine tuning and beam studies - Closed orbit meas. Orbit control and feedback	12×8=96
Average beam current	DC Current Transformer	-Built-in magnetic field shielding, low temperature coefficient, 1μA resolution	2
Betatron tune and beam damping	Stripline Electrode	- Beam spectrum and observation of instability - Used as transverse kickers for a transverse bunch-by-bunch feedback	2
Beam profile for commissioning	Screen Monitor	- Destructive position measusment	1
Beam trimming, dynamic aperture	Scraper	- To define the physical dynamic aperture	1

Beam Diagnostics and Control (cont.)

Beam Position Monitor Distributions in PLS-II



Position offset: $X_0 = -0.1107$ mm, $Y_0 = 0.1599$ mm


Beam Diagnostics and Control (cont.)

Orbit Control and Monitoring System

Orbit Stability Requirements

Source	Beam Size (μm)		Orbit Stability (μm)	
	Horizontal	Vertical	Horizontal	Vertical
Bending Magnet	53	30	5.3	3
IDs at Long Straight Section	241	17	24.1	1.7
IDs at Short Straight Section	160	11	16	1.1

Orbit Feedback System







Beam Diagnostics and Control (cont.)



- Feedback Type
 - Hybrid Type (Fast + Slow Orbit Feedback)
 - Download + Interaction (Soleil Type)
- BPM, Corrector Number
 - Number of BPM: 96 (8 per cell)
 - Corrector: 48 (4 per cell, insertion device area)
- Feedback Bandwidth
 - BPM Sampling Rate > 4 kHz
 - Corrector Magnet Risettime < 1 ms
 - Feedback bandwidth > 100 Hz
- Corrector Strength
 - Corrector Magnet Strength : $\pm 20 \mu\text{rad}$

SR Sources: Magnet and ID Systems

Magnet Layout in Half Cell of PLS-II



Gradient Magnet coils and 3D Drawings Bus structure with two parallel conductors




COPPER CONDUCTOR (OFHC)
11.8W x 10.3H x 6D x 1.0R
A=92.4mm²
TURN INSULATION
GROUND INSULATION
EPOXY

(SCALE 3X)

SR Sources: Magnet and ID Systems

Central Field Distribution of Gradient BM



SR Sources: Magnet and ID Systems (cont.)

● Magnet Systems for PLS-II

Type	Number	Key Parameters	Remarks
Gradient	2×12	1.4555 T, 4.0028 T/m Gap=34 mm, L_{eff} =1.800 m	All powered in series
Quadrupoles	8×12	4 types, Max Gradient 22T/m, R_c =36 mm	Powered in family series with independent aux coils.
Sextupoles	8 ×12	Max B'' =550 T/m ² R_c =39 mm, 2 types	SkewQ, V-corrector, H-corrector, combined function
Kicker Magnet	4		Recycle existing one
Lambertson Septum	1	3.0 GeV, 8.8 degree vertical bending,	




Energy, E	3.0	GeV
Bending radius, r	6.87549	m
Full aperture in bending magnet, G	34	mm
Aperture radius in quadrupole, R_Q	36	mm
Aperture radius in sextupole, R_S	39	mm



SR Sources: Magnet and ID Systems (cont.)



ID Installation Plan of PLS-II




Vacuum pipe
cross-section:
22 x 66 (mm)

Name	#	Pole-gap (mm)	Length (m)	Radius ¹ (mm)	Total length ² (m)
EPU	1	18	4	7	6
EPU	1	18	3.6	7	5.6
NanoScopy	1	18	3.6	7	5.6
U10	1	16	1.6	6	3.6
U6	1	18	2	7	4
MPW10	1	12	2	4	4
MPW10	1	12	1.1	4	3.1
MPW14	1	14	1.2	5	3.2
IVU	2	5	1.8	3 ³	1.8 x 2
IVU	9	5	1.35	3 ³	1.35 x 9
Rev.	1	4	1.02	3 ³	3.2

1. If out-vac, (pole-gap – 4mm) / 2
2. If out-vac, +2m
3. Nominal operation @ 6mm full gap


SR Sources: Magnet and ID Systems (cont.)

ID Installation Plan of PLS-II



Vacuum pipe
cross-section:
22 x 66 (mm)

- ✚ EPU7.2 : $L=2.5\text{m}$, $\lambda=7.2\text{cm}$, $B=0.793\text{T}$
- ✚ Hybrid : $L=3.0\text{m}$, $\lambda=6.6\text{cm}$, $B=0.989\text{T}$
- ✚ NanoScopy : $L=2.5\text{m}$, $\lambda=7.2\text{cm}$, $B=0.793\text{T}$
- ★ U10 : $L=1.6\text{m}$, $\lambda=10.0\text{cm}$, $B=1.320\text{T}$
- ★ U6 : $L=2.0\text{m}$, $\lambda=6.0\text{cm}$, $B=0.910\text{T}$
- ★ Revolver : $L=1.02\text{m}$, $\lambda=2.4\text{cm}$, $B=1.10\text{T}$
- ★ MPW10(2m) : $L=2.0\text{m}$, $\lambda=10.0\text{cm}$, $B=1.80\text{T}$
- ★ MPW10(1m) : $L=1.1\text{m}$, $\lambda=10.0\text{cm}$, $B=1.80\text{T}$
- ★ MPW14 : $L=1.12\text{m}$, $\lambda=14.0\text{cm}$, $B=2.020\text{T}$
- IVU2 SSRF (● ADC) : $L=1.8\text{m}$, $\lambda=2.0\text{cm}$, $B=0.970\text{T}$
- IVU2 SFA : $L=1.35\text{m}$, $\lambda=2.0\text{cm}$, $B=0.970\text{T}$
- MPI EPU SFA : $L=2.5\text{m}$, $\lambda=6.4\text{cm}$, $B=0.734\text{T}$



10.05.25 version

1. If out-vac, (pole-gap – 4mm) / 2
2. If out-vac, +2m
3. Nominal operation @ 6mm full gap

Magnet Power Supply System

Design Parameters of Magnet Power Supply

	BD	Main-quadrupole				Sextupole				Sept.
		MQ1	MQ2	MQ3	MQ4	S1	S2	S3	S4	
INPUT(3Φ, Y/Δ, V)	470	400	400	460	400	440	440	440	440	30
OUTPUT(A)	1000	1000	1000	1000	1000	500	500	500	500	250
Power conversion	4-paralleled buck converter					2-paralleled buck converter				single buck
Stability Short: <1 hour						+/- 5 ppm				
Stability long: >8 hour						+/- 10 ppm				
Controller						Full digital controller				
Resolution						20 bit				
cooling	water									
protection	OC, OT, OV, cooling water, Ext.									

 protection

4


Magnet Power Supply System

Design Parameters of Magnet Power Supply

	Aux. Quad.	Skew	Slow corrector	Fast corrector	Trim coil (Gradient magnet)	ID corrector (ID no: 20)
No.	96	24	V: 96, H: 96	V: 48, H: 48	24	V: 40, H: 40
INPUT(3 Φ , Δ , V)	23	15	23	15	15	15
OUTPUT(A)	20	20	20	15	15	10
Power conversion						
Stability Short: <1 hour						
Stability long: >8 hour						
regulation	Line: +/-10 ppm for +/-10%, Load: +/-10 ppm for +/-10%					
Controller	Full digital controller					
Resolution	20 bit					
cooling	Water					
protection	OC, OT, OV, cooling water, Ext.					


Magnet Power Supply System

Arrangement of Magnet Power Supply in Typical Cell







Main quadrupole MPS

— Current[A]





1:21:362:21:363:21:364:34:515:34:516:34



Magnet Power Supply System

Installation Layout of Magnet Power Supply



PLS-II MPS system is nicely under progress on the scheduled time.

Sector Girder and Alignment System


Mechanical Girder System

System Design Criteria

- Hold magnet center of 1,400 mm from the SR tunnel floor
- Rigid enough to sustain higher natural frequency
- Absorb the deformation coming from the ground movement
- Allow the active adjustment in vertical direction
- Install several diagnostic instruments to measure the deformation and get more flexible alignment (HLS, HPS, LVDT)



BM Girder



- Screw Jack : 3 set
- Stepping Motor : 3 set
- Linear Absolute Encoder : 3 set
- Total weight : 2.0 ton




QM/SM Girder


- Screw Jack : 6 set
- Stepping Motor : 3 set
- Linear Absolute Encoder : 3 set
- Total weight : 3.0 ton

Vacuum System

Configuration of Magnet Vacuum Chambers



Gradient bending magnet vacuum chambers






Diff. Pressure : 0.1 MPa


Support : Fixed (2point)

Material : Al 5083-H321

Deformation (Max) : 0.107 mm



Multipole magnet vacuum chambers




Diff. Pressure : 0.1 MPa

Support : Fixed (2point)

Material : Al 5083-H321

Deformation (Max) : 0.106 mm



Diff. Pressure : 0.1 MPa


Support : Fixed (2point)

Material : Al 5083-H321








Deformation (Max) : 0.196 mm

Vacuum System

● Configuration of Magnet Vacuum Chambers



Vacuum System (cont.)




Vacuum System (cont.)

Vacuum Chamber Fabrication Process



machining




delivery/inspection



moving



measurement



TE mode test



cleaning



alignment



weld



assembly/vacuum test


RF System

🍌 Design Parameters of Superconducting RF System

Y

RF System

Design Parameters of Superconducting RF System



RF System (cont.)

Parameters	PLS	PLS-II
Energy [GeV]	2.5	3.0
Current [mA]	200	400
Emittance [nm-rad]	18.9	5.8
Circumference [m]	280.56	281.82
Revolution frequency [MHz]	1.068	1.0638
Harmonic number	468	470
No. of Insertion Devices	10	20
Electron energy loss / turn from dipoles [keV]	548.4	1042
and insertion devices [keV]	160	250
Beam loss power by synchrotron radiation [kW]	142	517.0
RF frequency [MHz]	500.082	499.973
Cavity type	NC	SC
No. of RF cavities	5	3 (2)
Accelerating Voltage [MV]	2.0	4.5 (3.3)
RF Voltage per cavity [MV]	0.4	1.5 (1.65)
Klystron amplifier	Five 75 kW amplifiers	Three 300 kW amp.
Cryogenic Cooling Capacity @4.5 K [w]		700

- Baseline design: Three Cryomodules
- Two Cryomodules will be installed in Phase II commissioning periods.

RF System (cont.)

● Digital Low Level RF System and Klystron System

- ✓ Cavity Field Control(Amplitude & Phase)
- ✓ Cavity Tuning & Beam Loading Compensation
- ✓ Beam Instability Suppression
- ✓ RF Reference Generation & Distribution
- ✓ High-power protection

- ✓ Analog + Digital Technology
- ✓ RF Signal Generation & Precision Clock Synchronization
- ✓ **RF & Digital Board Development with JLAB Collaboration**
- ✓ **PC/104 Based Single Board Computer with EPICS IOC with JLAB Collaboration**
- ✓ High Power Amplification : 2-75kW and 2-300kW Klystron

- ✓ **Prototype**
~ February 2011
- ✓ **Production Type**
~ April 2011
- ✓ **Overall Field Test & Commissioning**
~ July 2011





INSIDE KSU WITH HT DESK


RF System (cont.)

Design Parameters of PLS-II RF System


Parameters	
RF cavity	SC
Number of cryomodule	2
RF voltage per cavity	1200 kV
RF power per cavity ($P_{\text{cavity}} = P_{\text{wall}} + P_{\text{beam}}$)	232 kW
Wall loss power (P_{wall})	23 W
Beam Loading power (P_{beam})	232 kW
Number of power amplifier	300 kW $\times$ 3
SR tunnel space	1 and half -SS



# of Amplifier/HVPS	3
Waveguide	WR1800
Circulator	~350kW
Amplifier	300kW klystron
HVPS	55kV/10A



RF System (cont.)




Item	Unit	Value
Resonant frequency	MHz	499.765
RF Voltage per cavity [MV]	MV	1.65 (1.5)
Accelerating voltage [MV]	MV	3.3 (4.5)
Operating temperature	K	4.5
Operating pressure	mbar	1.3
Pressure stability of LHe tank	mbar	± 3 @2.0 MV
Cryomodule helium level stability	%	± 1
LN2 pressure stability	mbar	± 50

Magnet Girder and Alignment System

Mechanical Girder and Supporting Structures


■ System Design Criteria

- Hold magnet center of 1,400 mm from the SR tunnel floor
- Rigid enough to sustain higher natural frequency
- Absorb the deformation coming from the ground movement
- Allow the active adjustment in vertical direction
- Install several diagnostic instruments to measure the deformation and get more flexible alignment (HLS, HPS, LVDT)



DM Girder


- Screw Jack : 3 set
- Stepping Motor : 3 set
- Linear Absolute Encoder : 3 set
- Total weight : 8.0 ton (w/magnet)




MM Girder

- Screw Jack : 6 set
- Stepping Motor : 3 set
- Linear Absolute Encoder : 3 set
- Total weight : 7.5 ton (w/magnet)

Magnet Girder and Alignment System




Multipole Magnet Girder



Dipole Magnet Girder

Magnet Girders and Alignment System



[Magnet Error Tolerance with respect to Girder]

• QM, SM : 50 μm • BM : 150 μm

Storage Ring Total : 100 μm (rms)


[Alignment System]

- HLS : Monitoring the Girder Movement
- Stepping Motor : Adjusting the Vertical Position
- Absolute Linear Encoder, Digital Probe : Recording the Position

Upgrade of PLS-II Utility/Infrastructures

● Infrastructures for More Stable Beam of PLS-II

- Building and Ground Movement
 - Monitor ground displacement using the HLS in real time and countermeasure mechanically the movement with a active girder system
- Thermal Deformation
 - Prevent structural thermal deformation using isolating materials and low thermal expansion structures
 - Water temperature control, air-conditioning and dissipation of heat from electric power devices
- Mechanical Vibration
 - Increasing the resonance frequency of the mechanical structures, using damping materials and isolating vibration sources
- Electrical Power and Grounding System



PLS-II SR and Infrastructure Dismantling, Installation and Commissioning



Basic Strategy of PLS-II Installation and Commissioning

● Strategy to Achieve Technical Goals of PLS-II

- Define Key Milestones
- Analyze System Integration
- Establish Dismantling and Installation Plan
- Safety Issue and Radiation Shielding
- High Heat Load Components (Vacuum)
- Communication (Risk Management)
- Experienced Experts (Manpower)
- Planned Commissioning Scenario

Basic Strategy of PLS-II Installation and Commissioning

● Concepts of Three Phase Construction Programs

- Separation of the construction activities into **Three Phases** to meet the overall dismantling/installation schedules based on the work duties


Installation Phases	Periods (Not Fixed)	Main Activities*	
		Storage Ring	Linac/BTL
Phase I	Dec. 15, 2010 - Jan. 15, 2011	Dismantling of PLS SR Components	Re-location of Linac MK09 downstream
Phase II	Jan. 16, 2011 - Feb. 11, 2011	Preparation of tunnel floor, ground marking, cable tray	Actual installation of systems and components of Linac
Phase III	Feb. 14, 2011 - June 30, 2011	Actual installation of systems and components of SR	Start-up and commissioning of Linac (May to June, 2011)
* The beamlines with front-end components should be interfaced with SR installation activities.			

Procedures of Dismantling Program

Dismantling Procedures to Meet PLS-II Needs

1. Preparation of tug transport system for moving heavy-weight structures, chain blocks and jigs, etc
2. Three gates (doors) open to transfer from SR tunnel to outside (#5, 11 cell - shielding wall blocked)
3. Dismantling the HLS, power/signal cables, cooling pipes/tubes, cable trays, air/gas lines, vacuum vent/valve closing, sector by sector
4. Disassemble the re-cycled components in the SR tunnel and move out the components to outside building (reserved for final removal after radiation safety check)
5. Anchor removal, ground grouting/painting, ground floor survey/monument and marking, cable tray re-arrangement
6. Review and check the dismantling of the SR tunnel for PLS-II needs

Storage Ring Layout of PLS SR Tunnel



Demolition Status of PLS Storage Ring/Beamlines



Demolition Status of PLS Storage Ring/Beamlines



Demolition Status of PLS Storage Ring/Beamlines



Procedures of Installation Program

Installation Strategy of SR Components

- Detailed analysis and planning of manpower and resource distribution for intensive system integration on the scheduled time
 - ✓ Identification of equipment and systems - hardware readiness
 - ✓ Identification of assembly sequence between the main components and ancillary systems - interface procedure readiness
- Safety process depending on the rules and regulations for no accidents
- Installation crew training and coordination
- Review of the readiness to verify the PLS-II start-up

Procedures of Installation Program

- Demonstration of Typical Cell of PLS-II for Identifying Installation Activities and Component Interfaces



Procedures of Installation Program

Installation Procedures of both Magnets and Girder Assembly

In the Workshop (Assembly Room)

- Set and lay out the girders to the imaginary orbit center line on the ground.
- Install the magnets and adjust the position locally.
- The magnet-girder assemblies will be transported independently in the tunnel by a tug transporter.

In Storage Ring Tunnel

- Check the ground level and grout the floor.
- Drill and insert the anchor nut into the ground with a precision less than 1 mm.
- Move and pre-install the magnet -girder assembly.
- Install the base plate and screw jack.
- Install the magnet-girder assembly on the screw jacks.
- Remove the upper part of the Quadrupole and Sextupole Magnets.
- Install the vacuum chamber.
- Set up the upper part of the Quadrupole and Sextupole Magnets.
- Install the dipole magnet.
- Survey and align the magnet and vacuum chamber cell by cell
- Whole ring survey and adjust the positions of the magnets.



Installation Status of PLS-II Storage Ring/Beamlines



🍌 Tentative Machine Start-up and Commissioning Plan



On-going Activities and Outlook

- Be done an actual installation program of PLS-II accelerator systems including the dismantlement of current PLS SR and beamline components, including the modification of ancillary infrastructures to meet PLS-II requirements.
- Be defined key milestones depending on the system levels more clearly from construction to start-up or commissioning to achieve the technical goals of a complex projects
- Be confirmed on-time delivery of components with an accepted performance to prevent an interruption of the installation program of PLS-II within 6 months

On-going Activities and Outlook


● Readiness of PLS-II Main Accelerator Components

- ✓ **Magnetic Lattice** : Completion of Linear/Nonlinear Beam Dynamics including error budget analysis and optimization (tune, DA, etc.)
- ✓ **Bending Magnets** : IHEP manufacturing (BM) prototype finished and under field measurement delivered on Jan., 2011
- ✓ **Quadrupoles and Sextupoles** : For aux coil, IHEP manufacturing (QM) and refurbished with PLS QM, domestic company manufacturing (SM) - on schedule (delivered on Dec. 2010)
- ✓ **Vacuum Chamber** : Domestic company manufacturing (Sector Chamber) - on schedule (delivered on Dec. 2010)
- ✓ **Beam Position Monitors** : IT (Libera) manufacturing (2nd procurement) and pick-up button (domestic) - on schedule (delivered on Jan. 2011)
- ✓ **Magnet Power Supplies** : domestic company manufacturing - on schedule (delivered on Dec. 2011)
- ✓ **RF System** : Cryomodule system (RI-contracted), Cryogenics (AL-contracted), Klystron amplifier (Thales), Waveguide and others - on schedule
- ✓ **Linac Upgrade** : Klystron (Toshiba-contracted), Acc. Section (Mitsubish-contracted, Modulator (domestic) and others - on and advanced schedule
- ✓ **R&D on Key Components** : In-vac Undulator (domestic)
- ✓ **Utilities and Safety** : Water, Electricity, Radiation Safety (domestic) -on schedule
- ✓ **SR Dismantling and Installation** : Under preparation of detailed work duties (domestic) -on schedule

On-going Activities and Outlook

● Outlook of PLS-II Light Source Facility

The upgrade program (PLS-II) has been officially launched with a project period of three years from 2009 to 2011. The main goals of PLS-II are the increase of straight sections for more insertion devices, the energy increase from 2.5 GeV to 3.0 GeV, a stored beam current from 200 mA to 400 mA, a relatively low emittance of 5.9 nm·rad, and more stable beam conditions. During last year (2011) of project periods, the current PLS facility will be shutdown and components be built, and then the first stage commissioning of 100 mA with 3.0 GeV be finalized. New beamlines and experimental stations will be also relocated with newly established insertion devices (undulators and wigglers), while the existing insertion device beamlines may be preserved. The PLS-II is to open for user experiments in 2012 after the international review for assessment of the PLS-II performance and readiness.



Cited from TPS CDR, 2008

Acknowledgements

PAL IAC Members

Gerhard Materlik, DLS, UK (Chair)
Kwang-Je Kim, ANL, USA (Co-Chair)
Efim Gluskin, ANL, USA
Jerry B. Hastings, SLAC, USA
Tetsuya Ishikawa, Spring-8, Japan
Osamu Shimomura, KEK, Japan
Katsunobu Oide, KEK, Japan
Keng S. Liang, NSRRC, Taiwan
Wolfgang Eberhardt, BESSY, Germany
Helmut Wiedemann, SLAC, USA
Zhentang Zhao, SSRF, China
Winfried Decking, DESY, Germany
Robert Hettel, SLAC, USA
Hesheng Chen, IHEP, China

The PLS-II Program has been launched
with the full financial support from MEST
and POSCO, Korea.

The author is also thankful for
Domestic and International
Reviewers who have joined in
the PLS-II Technical Review
Meetings.

PAL IAC Guest Members

Tsumoru Shintake, Spring-8, Japan
John N. Galayda, SLAC, USA
Jochen R. Schneider, DESY, Germany
Hans-Heinrich Braun, PSI, Switzerland
Alexander Zholents, LBNL, USA
Paul J. Emma, SLAC, USA
Zhirong Huang, SLAC, USA
Paul Bellomo, SLAC, USA
Josef C. Frisch, SLAC, USA

*Thank you very much for
your kind attention*

