

# Upgrade of CEBAF to 12 GeV

Leigh Harwood  
(for 12 GeV Accelerator team)



# Outline

- **Background**
- **High-level description**
- **Schedule**
- **Sub-system descriptions and status**
- **Summary**

# CEBAF Science Mission

CEBAF was originally built to establish a deep understanding of the quark/gluon structure of nuclei.  
(non-perturbative QCD)

The program to date has been highly successful.

Theoretical initiatives identified critical areas with new opportunities for understanding.

- Explanation for quark confinement (exotic meson spectroscopy)
- Tomography of the nucleus with Generalized Parton Distributions
- Valence quark behavior

Investigating these open questions required doubling the CEBAF beam energy

# 12 GeV Upgrade Project

Scope of the project includes:


- Doubling the accelerator beam energy
- New experimental Hall and beamline
- Upgrades to existing Experimental Halls

The completion of the 12 GeV Upgrade of CEBAF was ranked the highest priority in the 2007 NSAC Long Range Plan.


This priority was re-iterated in an 2013 NSAC report to DOE/NP

The Upgrade is built on an existing facility:


The vast majority of accelerator and experimental equipment have continued use




# 6 GeV CEBAF



# 12 GeV CEBAF



# Schedule: Long View



# Sub-system Descriptions and Status



# Cryomodules: Scope & Key Technical Parameters

- Scope: Develop, Design, Fabricate, Install and Check-out  
**10 Cryomodules** (5 new cryomodules per linac)

(The following parameters are for each Cryomodule)

<b>Voltage</b> (Includes 10% reserve):	<b><math>\geq 98\text{MV}</math> (108 MV)</b> (ensemble average in each linac)
<b>Heat budget: (Interface with Cryogenics)</b>	
– 2 K	<b><math>\leq 300\text{ W}</math></b>
– 50 K	<b><math>\leq 300\text{ W}</math></b>
<b>Slot Length:</b>	<b>9.8 m</b>
<b>Tuner resolution:</b>	<b><math>\leq 2\text{ Hz}</math> (stepper + PZT)</b>
<b>Fundamental Power Coupler:</b>	<b>7.5/13 kW (Avg/Pk)</b>
<b>Higher Order Mode (HOM) damping:</b>	
– Transverse (R/Q)Qk	<b><math>&lt; 2.4 \times 10^{10}\ \Omega/\text{m}</math></b>
– Longitudinal (R/Q)Q	<b><math>&lt; 6.5 \times 10^{11}\ \Omega</math></b>
<b>Cryomodule Length (Physical)</b>	<b><math>\sim 8.5\text{m}</math></b>

# Cryomodules: Status

	Checked out in tunnel
#1	104 MV
#2	110 MV
#3	118 MV
#4	106 MV
#5	110 MV
#6	108 MV
#7	108 MV
#8	
#9	114 MV
#10	110 MV

**Avg 109 MV**

**Avg  $Q_0$  @ 19.2MV =  $8.1 \times 10^9$**





**Final C100 installed in linac**

**Hogan: WEZAA2**

# RF: Key Technical Parameters

- Ten new zones of RF power for new accelerating structures:
- Operating Freq: 1497 MHz
- Eight cavities per zone
  - Individual low-level controls
  - Cavity  $Q_L$ :  $\geq 2 \times 10^7$
  - Operating Gradients:  $>17.5$  MV/m
  - One cavity per klystron

	<i>Fast</i> ( <1sec)	<i>Slow</i> ( >1sec)
Phase Stability (rms)	0.5°	3.0°
Amplitude (rms)	$4.5 \times 10^{-4}$	NA



# RF details

- **Low Level RF**
  - **Ground-breaking digital solution for cw controls**
  - **Double-moded**
    - **Self-Excited Loop (SEL):**  
If phase/amplitude control is not needed
      - Permits cavities to be energized and quickly brought onto resonance.  
⇒ Mitigates the double-valued detuning curve.
    - **Generator-Driven Resonator:**  
When phase/amplitude control is needed for beam
      - Hovater: TUZBA1**
      - Hoffler: THTB1**

- **High power RF**
  - **New 13kW klystron**




- **Only 2 cavities/klystrons per high-power amplifier**  
⇒ Improved up time

## Installation is complete




# RF: Layout



# RF: LLRF/HPA Control Systems

**Field Control Chassis**




**Cryomodule Interlocks Chassis**

**High Power Amplifier Control Chassis**

**Stepper Tuner Control Chassis**

**Piezo Tuner Amplifier Chassis**

**Klystron Solenoid Power Supplies**



# Cryogenics

- **Double the capacity of 2K plant: 4.6kW → 9kW**
  - New 4.5K helium refrigerator: 4.6kW @ 2.1K, 12kW@35K plus 15 g/s of 4.5K liquefaction
  - Modified the cryogenic distribution system for the interconnection of 10 new C100 cryomodules
  - Note: Leveraged an existing 2K coldbox
- **Status**
  - 4.5K coldbox has been accepted
  - Distribution system is complete
  - Commissioning on integrated system is underway

# Cryogenics (cont'd)



Lower coldbox



Upper coldbox



# Beamlines

- Overall length (excluding linacs)
  - Original: 4.3 km
  - Upgrade: 4.9 km
    - New 10<sup>th</sup> recirculation arc and beamline to new Hall D
- Original layout retained (including dipole & quad locations)
- Almost all magnets were reused
  - Dipoles
    - Beam energy at any location has increased by ~2x, so  $\int B dL$  of dipoles much increase by same ratio
    - Solution: Increase the current in the dipoles by 2x
      - Saturation was beaten by adding more return iron
        - » Changed “C” dipoles to “H”
  - Quads
    - Most reused w/o change
    - ~100 were shifted to higher-current power supplies

# Beamlines (cont'd)

Magnets		Major ( $\geq 1\text{m}$ ) dipoles	Quads	Steering dipoles
Original		452	705	750
Upgrade	Unchanged	27	635	750
	Reworked*	425	0	0
	New	43	114	64

\*Reworked: disassembled, insulation replaced, iron modified and/or added, coils reconfigured on some magnets, reassembled, QA'ed and field mapped

Power supplies		35-260kW	40-1080kW	10A/20V	20A/70V
Original		22		1455	
Upgrade	Reused	9		1322	
	New		15		240

# Beamlines (cont'd)


Original

Removed original


East Recombiner

East Arcs

12GeV




# Extraction: Beam to 3 Halls at Once



# I&C/Safety

- **Added diagnostics and machine protection systems for new beamlines**
  - New design for beam position monitor electronics was needed because of obsolescence of components for original
- **Expanded network and modify control software for new cryomodule/rf zones, magnet power supplies, and CHL expansion**
- **Modified control software to incorporate new magnet power supplies and new cryomodule/rf zones**
- **Expanded personnel safety system to cover new Hall D**
- **Status**
  - Ready for beam commissioning
  - Additions for Hall D will complete in FY14

# Schedule: 2009-now




- **FY11 shutdown: Reworked 7 arcs and installed 2 zones of cryomodules & RF**
- **FY12-13 shutdown: Completed accelerator installation for commissioning**

# 2012: Full Performance of C100 + RF was Demonstrated


Cryomodule voltage

Total current in linacs:  
465  $\mu\text{A}$



**This is with beam going to the NP experiments**

# Costs





# Future

- What's after 12 GeV?
- The NP community is looking towards an **Electron-Ion Collider.** Zhang: TUZAA1

# Summary

- An exciting research program in the study of the quark structure of nuclei as well as the fundamental question of quark confinement is possible with a 12GeV cw electron beam.
- The CEBAF accelerator has been upgraded to deliver 12 GeV beam.
  - The core of that upgrade was increasing the total linac voltage by 1.0 GV to a total of 2.2 GV.
- All systems have met their defined goals

**Beam commissioning is about to start!**