

Overview and Lessons Learned of the Jefferson Lab Cryomodule Production for the CEBAF 12 GeV Upgrade



Outline


- **Introduction / Scope**
- **Design**
 - Overview & Parameters
- **Procurement**
 - Planning
 - Execution
 - Lessons Learned
- **Production**
 - Facilities & Planning
 - Execution
 - Acceptance Testing
 - Lessons Learned
- **Installation / Check out & Commissioning**
 - Planning
 - Execution
 - Performance
 - Lessons Learned
- **Cost & Schedule**
 - Lessons Learned
- **Summary & Acknowledgements**



Introduction to Jefferson Lab

>1200 active member international user community engaged in exploring quark-gluon structure of matter

Superconducting electron accelerator provides 100% duty factor beams of unprecedented quality, with high polarization at energies up to 6 GeV




Newport News, VA



Test Lab (SRF) Renovation and Technology & Engineering Development Facility Complete






SCOPE OF 12 GeV UPGRADE


Parameter	Present JLab	Upgraded JLab
Number of Halls	3	4
Number of passes Halls A/B/C	5 (for max energy)	5 (for max energy)
Max Energy to Halls A/B/C	up to ~6 GeV	up to ~11 GeV
Number of passes to Hall D	New Hall	5.5
Energy to Hall D	New Hall	12 GeV
Current – Hall A & C	max ~180 μ A combined	max ~85 μ A combined (higher at lower energy)
Current – Hall B & D	(B) Up to 5 μ A max	(B, D) Up to ~5 μ A max each
Central Helium Liquefier (CHL)	4.5 kW	9 kW
# of cryomodules in LINACS	40	50
Accelerator energy per pass	1.2 GeV	2.2 GeV

Routinely provide beam polarization of ~85% now, same in 12 GeV era

C100 Cryomodule Design



- Eight-seven cell SRF cavities (2K - nominal operating temp)
- Eight individual helium vessels (stainless steel)
- Waveguide power couplers (double warm rf-windows)
- Cavity tuners
 - Cold scissor jack
 - Warm drive components
- Supply/Return cryogenic end-caps (two cooling circuits)
 - 2K primary & 50K shield



Cryomodule Scope & Key Technical Parameters

- **Scope: Develop, Design, Fabricate, Install and Check-out 10 Cryomodules (5 new cryomodules per linac)**

(Note: The following parameters are for each Cryomodule)

Voltage (Includes 10% reserve): ≥ 108 MV

– **Corresponds to average cavity gradient of 19.2 MV/m**

(ensemble average in each linac)

Heat budget: (Interface with Cryogenics)

– **2 K ≤ 300 W**

• **Corresponds to cavity Q_0 7.2 E9 @ 19.2MV/m**

– **50 K ≤ 300 W**

Slot Length: 9.8 m

Tuner resolution: ≤ 2 Hz

Fundamental Power Coupler (FPC): 7.5/13 kW (Avg/Pk)


Cryomodule Length (Physical) ~ 8.5 m

Procurement - Planning

- **Industry to produce components (build to print)**
 - Develop advanced procurement plan
 - Specifications, drawings, acceptance criteria, schedule
 - Bid/Award process
 - Stock components
 - Low price technically acceptable
 - Best Value (consideration for experience)
 - Acceptance criterion
 - Delivery schedule
 - Production Schedule

Procurement - Execution

- **Manufacturing and Acceptance**
 - Criterion developed & defined prior to award
 - Vendor visits during production improves communication
 - First Article delivery schedule is critical
 - **Validate production process before all components made**
- **QA/QC all components prior to release for use in cryomodule production**




Procurement – Lessons Learned

- **Strong Quality Assurance Pays off**
 - **Get early start on ‘non-standard’ components**
 - **Specifications & acceptance criteria must be well documented**
 - **Acceptance travelers, staff training, feedback to vendor**
 - **Issues with vendor performance must be communicated promptly**
 - **Manage resources**
 - **Resources must be in place prior to delivery of first article**
 - **Staffing: Availability, allocation, training, skill sets, etc.**
 - **Facilities: Process control, priority access, maintenance**
 - **Maintain Detailed Documentation**
 - **All procedures must be vetted prior to release**
 - **Establish robust QC; traveler system - (receiving inspections, process control, testing results, database management)**

Production – Facilities & Planning

- **Pre-production**
 - **Inventory management**
 - **Logistics:**
 - **Space, access, equipment, staffing**
 - **Scheduled mockup activities**
 - **Exercise tooling (ensure fit & function)**
 - **Work through assembly procedures**
 - **Identify/resolve any interference issues**
 - **Opportunity to vet assembly travelers**




Production – Execution

- **Production**

- **Cavity qualification**
 - Qualified in He vessel in VTA
 - 65% qualified on first test
- **Cavity string assembly**
 - Assembly in cleanroom



C100 VTA tests for 12 GeV upgrade



C100 CavID

Production – Execution

- **Production (in-process quality checks)**
 - **Cold mass assembly**
 - **Mag shielding, Headers, tuners, instrumentation, MLI**
 - **Space frame assembly**
 - **Alignment, Thermal & Mag shielding, MLI**



Production – Acceptance Testing


- **Production**

- **Final assembly**

- **Complete warm checkout of all subsystems.**

- **Acceptance testing**

- **Cryomodule is slow cooled down to 4K (pumped down 2K)**
 - Instrumentation checkout
 - **Low power measurements**
 - Tuner operation, cavity frequencies, HOM damping, heater control
 - **High power measurements**
 - Emax, Qo, Heat loads, Lorentz



Production – Lessons Learned

- **Have Focused Response to ‘unplanned’ Issues**
 - **High permeability in He vessel heads**
 - **Spuncast head manufacturer added carbon steel to process**
 - **Manufacturer contacted; new (C-free) process implemented**
 - **Replacement heads manufactured from 316 SS**
 - **Cryogenic electrical feed-through(F-T) leaks**
 - **Failed after QA acceptance testing**
 - **Replaced: Based on previous experience, F-T’s located behind access panels.**
 - **Microphonic response higher than planned**
 - **Cold tuner modified to add stiffness to system.**
 - **Individual cavity heater control needed for operations**
 - **LLRF controls modified to accommodate**
 - **Based on previous experience, individual heaters installed**

Installation / Checkout & Commissioning - Planning

- **Coordination (with other 12 GeV upgrade activities)**
 - Civil, beam transport, cryogenics, high power-rf, instrumentation, controls & safety
 - Integrate detailed schedule of activities including resources and interdependencies
- **Goal – Install two cryomodules into CEBAF ahead of baseline schedule**
 - Opportunity to operate cryomodules with beam and demonstrate performance goals.
 - Close coordination with physics program to integrate new digital LLRF control system designed for C100 cryomodules.


Installation / Checkout & Commissioning - Execution



- **Following acceptance testing**
 - Cryomodule transported from Test Lab to CEBAF tunnel
 - Installation into designated zone
 - Complete integration with all other accelerator systems
 - Beamline, cryogenics, high-power-rf & rf control & safety systems

Full Performance of C100 & RF Demonstrated

Cryomodule
voltage



Beam Current
465 μA

Installation / Checkout & Commissioning - Performance

- **Design goals**

- **98 MV/CM**

- **Required for 12 GeV operations**

- **108 MV/CM design goal**

- **Provide operational margin**

- **19.2 MV/m/cavity**

- **Avg Emax = 22.2 MV/m**

- **Qo ≥ 7.2 E9 @ 19.2MV/m**

- **Avg Qo = 8.1E9**


Tunnel Performance (MV)

C100-01	104
C100-02	110
C100-03	118
C100-04	106
C100-05	110
C100-06	108
C100-07	108
C100-08	In progress
C100-09	114
C100-10	110

- **Good communication & cross functional coordination is critical to success**
 - **Baseline design performance goal achieved**
 - **Design goal of 10% margin not achieved on all cryomodules**
 - **These activities are still in progress**
 - **Preliminary lessons learned**
 - » **Improvements made to process/configuration control**
 - » **Upgrades to testing hardware & software beneficial**

Cost & Schedule – Planning


- C100 CM's ~10% of total project cost




- **Earned Value Management System (EVMS)**
 - Formal EVMS implemented for 12 GeV project in accordance with DOE Order 413.3B

Cost & Schedule – Monitoring & Control

Total C100 Cost Breakdown



Labor Breakdown by Process



- **EVMS data**

- Procurements were the dominate cost for the C100 CM's
- Labor costs dominated by QA, cavity processing & cryomodule assembly

Cost & Schedule – Monitoring & Control

- **EVMS – ‘Touch labor’**
 - **Quality Control**
 - **Component receiving inspections**
 - **Several hundred individual component inspections**
 - **Documentation (travelers, database management, etc.)**
 - **Inventory control**
 - **1000’s of parts inventoried, tracked & released for production**
 - **Cavity QA & qualification**
 - **Cavity receiving inspection, chemical cleaning, testing and assembly**
 - **Cryomodule assembly**
 - **Cold mass, space frame & final assembly**

Cost & Schedule – Lessons Learned

• Cost

– Procurement

- Work with vendors to identify cost drivers and minimize NRE & schedule delays
- Take advantage of quantity discounts where possible
- Minimize custom components/maximize common parts

– Labor

- QA: Develop capable vendors prior to request for quotes
- Processing & Assembly:
 - Automate processes and redundancy
 - Minimize touch labor

• Schedule

– Good communication critical

- With vendors, safety, facility and technical and PM staff

Summary

- **Planning**
 - **Prototyping**
 - Develop/finalize component specifications & acceptance criteria
 - Identify/resolve any potential performance issues
 - Thoroughly vet processes, procedures, tooling and staffing needs
 - Develop sound basis for full production planning
- **Execution, Monitoring and Controlling**
 - **Utilize formal database management**
 - Receiving inspections, assembly travelers, cost & schedule
 - Establish baseline, monitor progress & promptly identify cost issues
 - **Work the plan**
 - Communicate progress to all stakeholders on a regular basis

Acknowledgements

- Andrew Burrill et al., “Production and Testing Experience with the SRF Cavities for the CEBAF 12 GeV Upgrade,” IPAC2011, San Sebastian, Spain, September 2011, MOOCA01
- Leigh Harwood, “The JLab 12 GeV energy Upgrade of CEBAF”, NA-PAC13, Pasadena, CA MOZAA1
- V. Ganni et al, “Commissioning of Helium Refrigeration System at JLab for 12 GeV Upgrade”, CEC-ICMC 2013, Anchorage, AK
- Curt Hovater et al., “Commissioning and Operation of the CEBAF 100 MeV Cryomodules,” IPAC 2012, New Orleans, LA., WEPPC093.
- Frank Marhauser et al., “HOM Damping Sensitivity in SRF cavities,” International Workshop on HOM Damping in SRF Cavities, Cornell University, Ithaca, NY, 11-13 October 2010.
- K. Davis et al, “Vibration Response Testing of the CEBAF 12 GeV Upgrade Cryomodules”, LINAC 2012, Tel Aviv, Israel.
- Andrew Burrill et al., “SRF Cavity Performance Overview for the 12 GeV Upgrade,” IPAC 2012, New Orleans, LA., WEPPC089
- Michael Drury et al., “CEBAF Upgrade: Cryomodule Performance and Lessons Learned,” SRF 2013, Paris, France, THIOB01



Jefferson Lab - SRF
Cryomodule Production
Group