

11th WORKSHOP ON RF-SUPERCONDUCTIVITY
SRF 2003

8. – 12. September 2003

LÜBECK/TRAVEMÜNDE MARITIM - STRANDHOTEL



The X-Ray FEL at DESY

Hans Weise / DESY



The four-masted barque PASSAT was one of the famous Flying P-liner and sailed Cape Horn not less than 39 times. Today the PASSAT is anchored as museum ship in Travemünde opposite of The MARITIM-Hotel.







TESLA

The Superconducting Electron-Positron Linear Collider with an Integrated X-Ray Laser Laboratory

Technical Design Report



March
2001



integrated into TESLA LC:

using part of e- linac, two extraction points, long beam transfer → **cost effective** but **less flexible** solution





TESLA XFEL

First Stage of the X-Ray Laser Laboratory

Technical Design Report

Supplement



October
2002

TDR update 2002:

XFEL driver linac separate
from LC


→ de-coupling of LC-XFEL
regarding construction &
operation (and: *approval*)

- maintaining common site
- identical linac technology
- detailed analysis of potential gain in flexibility was not included in the update

Remark:

cost increase w.r.t. TDR2001
limited by reduction of energy
to 20 GeV (*First Stage of ...*)
and by a reduced number of
photon beamlines 10 → 5

TDR Update 2002: XFEL Layout



XFEL Key Parameters

Lower beam energy can be compensated easily:

Slightly **lower emittance** and slightly **modified undulator**.

	E_b [GeV]	ε [10^{-6}m]	σ_E [MeV]	I_{pk} [kA]	λ_U [mm]	K_U	gap [mm]	L_{sat} [m]	L_{tot} [m]
TDR2001	25	1.6	2.5	5	45	4	12	210	311
Update02	20	1.4	2.5	5	38	3.8	10	145	213

Present work: starting from TDR-update, develop a guideline for detailed project definition to start construction in ~2 years.

Basic Assumptions for the Linac Specification

- Linac has to deliver a beam energy of 20 GeV at a **gradient close to 23 M/m**; the corresponding linac length represents the final stage, **i.e. higher energy reach comes from better cavity performance**

The “trend”: arguments towards higher beam energy become weaker

- more aggressive undulators
- better beam quality (careful: we haven't seen the 1.4 mm mrad ...)
- higher harmonics generation

This together with recent achievements in cavity performance makes the **linac length extendibility hard to justify (cost!)**.



- **Linac to be constructed in TTF-like technology:**

12m modules with 8 cavities + quad package (exact length, cavity spacing, magnet specifications to be reviewed)

- Limit average beam power to ~600 kW


(two solid state beam dumps in the 1st stage, 300 kW each)

TTF Linac Accelerator Modules




TTF Linac Accelerator Modules


New Type as **XFEL Prototype** (modules #4 and #5)




- Reduced diameter
- New concepts accommodate for long shrinkage during cooldown



Gradient of Accelerator Modules





Reference Parameter Set

Main linac Section 2	
Energy gain	2.5 → 20 GeV
# installed modules	100
# active modules	92
acc gradient	22.9 MV/m
# installed klystrons	25
# active klystrons	23
beam current	5 mA
power→beam p. klystron	3.8 MW
incl. 10% + 15% overhead	4.8 MW
matched Q_{ext}	$4.6 \cdot 10^6$
RF pulse	1.37 ms
Beam pulse	0.65 ms
Rep. rate	10 Hz
Av. Beam power	650 kW

4 modules
(32 cavities)
per klystron.

two spare rf
stations.

10% for phase
/ amplitude ctrl.

pulse structure
to be defined.

Reference Parameter Set

Main linac Section 1	
Energy gain	0.5 → 2.5 GeV
# installed modules	16
# active modules	12
acc gradient	20.1 MV/m
# installed klystrons	4
# active klystrons	3

4 modules
(32 cavities)
per klystron.


one spare rf
station.

Comment 1: energy management in case of failure requires reserve RF unit in both section 1 and 2 of the main linac. The 2.5 GeV energy at BC-III is important for the bunch compression.


Comment 2: lower gradient in section 1 can be advantageous in view of desirable flexibility (see below) with respect to rep.rate.

XFEL RF Unit

1 klystron for 4 accelerating modules, 8 nine-cell cavities each



TTF High Power RF




**Pulse
Transformer**



**IGCT
Stack**



**TH1801
Multi-Beam
Klystron**






HV Power

Capacitor Bank

Bouncer

TESLA Test Facility Linac as Prototype for the XFEL Injector



Party Line Towards Full Project Specification: what we will *not* do

- **Go from pulsed linac to *CW operation* as baseline design**
 - 20 GeV linac would require cryogenic plant ~3 times the capacity of entire 500 GeV LC
 - He distribution would have to be drastically modified
 - Concepts exist, but to date CW beam source is not available
- **Develop 17m module with *superstructures***
 - Relation between R&D effort and gain in fill factor is not reasonable for a ~1.5 km long linac
 - Cost saving on RF couplers must be balanced against investment in cavity treatment infrastructure and time delay for acc. module specification
- **Maintain the common *LC and FEL site***
 - No green light from government for an LC site near Hamburg at this point in time; process in international community towards LC technology decision, international funding and site decision likely to take several years
 - Synergy / cost saving arguments for Ellerhoop site can't be used anymore to push the plan approval procedure through

Party Line Towards Full Project Specification:

what we *should* do: cost analysis


Example: Klystrons / RF stations

- To meet reference parameters, in principle **5MW klystrons** are sufficient → potential cost saving on R&D and final investment
- Alternative: Keep the **10MW MBK**, but reduce # of RF stations
 - Model for (crude) estimate scaled from TDR-update cost figures:
 - **0.9 M€** per 12m accelerator module
 - **1.8 M€** per 10MW RF station driving 36 cavities
 - Assume **75%** of RF cost \propto **# of klystrons**, **25%** \propto **# of cavities**

Compare two options: (1) 6 modules/klystron and

(2) 8 modules per klystron

(3) with reference 4 modules per klystron




somewhat surprising result, reason being inevitable **need for reserve stations**... (1) and (2) are cheaper than (3)

but also (1) is cheaper than (2)


Parameter Flexibility

User requirements still need to be reviewed / discussed,
but one trend seems to go towards flexibility in beam timing Structure.


a. equal filling




b. equal filling with variable number of bunches




g. pump & probe




c. equal filling with variable bunch distance




d. equal filling with variable distance and bunch number




h. bunches with $\Delta t < 200$ ns :
e.g. $\Delta t = 800$ ps, 4 ns, 20 ns




e. sub-trains with variable distance and bunch number



f. timing (pilot) bunch ahead



i. wavelength variation
<12% inside train



Single bunches.
Few bunches.
Long trains.

Sub-trains with
variable distance /
bunch number.

The s.c. linac will
take care of it.

But: **Duty cycle, i.e.**
Repetition Rate ???

Impact on **RF Gun**
laser
RF & LLRF
cryogenics

Duty cycle limitations: Cryogenics

- LC TDR layout for module / He distribution allows for an upgrade to 800 GeV (Ø He Gas Return Pipe, pressure drop)
 - ↪ At ~23 MV/m, the 1.5km linac (2.5 GeV → 20 GeV) could be operated up to about **20 Hz rep rate (~2% duty cycle)**
- Required cryogenic plant would have approximately the size of **one of the six TESLA-500 LC plants**
- From cryogenics point of view, one could use the scaling law

$$\text{duty cycle} \propto 1/\text{energy}^2$$

Duty cycle limitations: RF system

- present design of modulator / klystron station can operate at max. 10 Hz, 10MW, 1.4ms pulse length, 65% max. efficiency (average power **into** klystron ~220kW)
- Higher duty cycle at lower peak power possible
average power into klystron gun is kept ≤ 220 kW
(careful: DC \rightarrow RF efficiency drops at lower power!)
concerns: IGBTs at high rep rate, RF drive power
- Scale


beam pulse current with acc. gradient (i.e. energy)
the loaded Q_{ext} remains constant
- or optimize

for constant beam current which requires
a variable Q_{ext}


Max rep. rate and beam power, 4 vs. 6 modules / klystron

Calculation includes **klystron efficiency**, **scale beam current** during macro pulse with gradient, and aims for **maximum possible beam power**.

rep rate vs. acc gradient, 4 modules/klystron



rep rate vs. acc gradient, 6 modules/klystron




because of beam dump (solid absorber) we wanted to limit $P_{av} \leq 600 kW$

Variable Q_{ext} ($I_{\text{beam}} = \text{const.}$)

6 modules / klystron


Keep $I_{\text{beam}} = 5 \text{ mA}$ constant, scale $Q_{\text{ext}} \propto E_{\text{acc}}$

Attractive option: shorter pulses / higher f_{rep} (RF gun!)



$$Q_{\text{ext}} = 1 \times 10^6$$

$$Q_{\text{ext}} = 4.6 \times 10^6$$



Too high rep.frequencies might cause problems with the RF gun!

Injector and low-energy linac section

- Possibility of RF gun operation at 50Hz or more has to be studied. Pulse shortening likely to help!
- 500 MeV injector can't be scaled in E_{acc} for higher f_{rep} (bunch compression, beam dynamics)



special solution for RF system desirable
(lower power/higher duty cycle klystrons?)

- 0.5 → 2.5 GeV linac section (before BC-III):

To which extend can we change the energy in BC-III?

If constant energy at BC-III is necessary then the 2 GeV pre-linac needs a modified layout (rf system, reduced gradient?).

Prepare for Start of Project Construction

The XFEL Project Group structures the **work necessary to prepare for start of project construction** in ~ two years. A total of **38 work packages** was created. WPs cover different categories for complete project definition:

Overall design & parameters, beam physics

Major technical components

Sub-systems

Other issues

WPs are not orthogonal – good communication / interaction necessary. All WPs have one **DESY representative**.

This does not mean to imply that DESY wants to take over all tasks! Leadership and / or participation from other labs is already present, especially for s.c.linac technology, e.g.

C. Pagani / INFN & TESLA Coll.Leader (acc. module development)

T. Garvey / Orsay et al. (RF couplers)

C. Magne / Saclay et al. (linac BPMs)

Participation from outside will grow in the future.

Partners will be integrated in the XFEL Project Group as early as possible.














XFEL Project Group: 38 work packages

1. RF System
2. Low Level RF (LLRF)
3. Accelerator Modules
4. S.C. Cavities
5. Power Coupler
6. HOM Coupler / Pick-Up
7. Frequency Tuner
8. Cavity Flanges / Cold Vacuum (incl.warm injector section)
9. Cavity String Assembly / Clean Room Quality Assurance
10. Module Test Facility
11. Cold Magnets
12. Warm Magnets
13. Cryogenics
14. Injector
15. Bunch Compression and Start-to-End Simulation
16. Lattice Design and Beam Optics/Dynamics
17. Standard Beam Diagnostics
18. Special Beam Diagnostics
19. Vacuum system (warm)
20. Beam Dumps
21. Undulators

accelerator modules
module test / magnets / cryogenics
linac components (injector, bunch compressors, diagnostics, dumps)
Photons
FEL concepts
Controls / Operability
Infrastructure (site, civil construction, survey, tunnel layout, utilities)
Safety
Organisation














22. Generic Hard Photon Beam Line
23. Generic Medium Energy Photon
24. Photon Diagnostics
25. Experimental Areas
26. Detector Development
27. FEL Concepts
28. Control Systems
29. Operability/Failure Handling
30. Ground Motion and Mechanical Stability
31. Site and Civil Construction
32. Survey and Alignment
33. Tunnel installation
34. Utilities
35. Radiation Safety
36. General Safety
37. Construction Plan Approval Procedure
38. Overall Project Progress Tracking

XFEL Project Group: 38 work packages

	1. RF System
	2. Low Level RF (LLRF)
	3. Accelerator Modules
	4. S.C. Cavities
	5. Power Coupler
	6. HOM Coupler / Pick-Up
	7. Frequency Tuner
	8. Cavity Flanges / Cold Vacuum (incl.warm injector section)
	9. Cavity String Assembly / Clean Room Quality Assurance
	10. Module Test Facility
	11. Cold Magnets
	12. Warm Magnets
	13. Cryogenics













accelerator modules
module test / magnets / cryogenics
linac components (injector, bunch compressors, diagnostics, dumps)
Photons
FEL concepts
Controls / Operability
Infrastructure (site, civil construction, survey, tunnel layout, utilities)
Safety
Organisation

XFEL Project Group: 38 work packages

	14. Injector
	15. Bunch Compression and Start-to-End Simulation
	16. Lattice Design and Beam Optics/Dynamics
	17. Standard Beam Diagnostics
	18. Special Beam Diagnostics
	19. Vacuum system (warm)
	20. Beam Dumps
	21. Undulators
	22. Generic Hard Photon Beam Line
	23. Generic Medium Energy Photon
	24. Photon Diagnostics
	25. Experimental Areas
	26. Detector Development


accelerator modules
module test / magnets / cryogenics
linac components (injector, bunch compressors, diagnostics, dumps)
Photons
FEL concepts
Controls / Operability
Infrastructure (site, civil construction, survey, tunnel layout, utilities)
Safety
Organisation

XFEL Project Group: 38 work packages

	27. FEL Concepts	accelerator modules
	28. Control Systems	module test / magnets / cryogenics
	29. Operability/Failure Handling	linac components (injector, bunch compressors, diagnostics, dumps)
	30. Ground Motion and Mechanical Stability	Photons
	31. Site and Civil Construction	FEL concepts
	32. Survey and Alignment	Controls / Operability
	33. Tunnel installation	Infrastructure (site, civil construction, survey, tunnel layout, utilities)
	34. Utilities	Safety
	35. Radiation Safety	Organisation
	36. General Safety	
	37. Construction Plan Approval Procedure	
	38. Overall Project Progress Tracking	

If you are curious please check <http://xfel.desy.de>

want to participate




end of slide view

XFEL Project Group

1. RF System


- Cost-optimized and still flexible (rep. rate) system: 10MW MBK final decision or alternatives?
- Design + tests necessary for modulator at high repetition frequency?
- Concept for fast Klystron Exchange?



XFEL Project Group

2. Low Level RF (LLRF)

- # cavities per Klystron?
- Electronics in tunnel (radiation)?
- Handling of non-uniform bunch trains?
- Intra-train energy scan?
- 'Conventional' timing issues




XFEL Project Group

Improvements/changings for X-FEL module (necessary?) View of WP 3

-Tuners (standard/blad) saclay standard modified with piezo	WP 7
- New quad/dip doublet (pos. Field, 2K-cooling, HTc curr lead)	WP11
- Alignment/survey (more comfortable)	WP32
- HOM-Absorber, BPMs (position, cooling)	WP 6
- Module/module connections (300mm, 70mm, kind of weldings...)	WP 3
- Magn. Shielding	WP 3
- More safety for transportation/shipping	WP 3
- TÜV/AfA	WP 3
- Main Couplers (New design, heating in modules?)	WP 5
- Material specifications	WP 3
- ...	
- Module Test Facility	WP10


R. Lange



XFEL Project Group

4. S.C. Cavities


- Cavity baking in-situ
- EP on cavities with tank
- Determination of electrical axis of cavity
- Check mechanical properties of niobium after 800C
- Define processes of cavity preparation and assembly
- Optimum EP parameters
- First 10 nine cell-preparations after EP + 800C + bake
- Material
- EP on half cells, dumb-bells
- Inter-cavity spacing
- Optimum stress annealing + hydrogen degassing temperature (600 – 1000C)
- Other cleaning techniques: Oxipolishing, BCP 1:1:10, etc.
- Development of CO2 cleaning
- Cavity Production



XFEL Project Group

5. Power Coupler


- Alignment of coupler bellows
- Define processes for integration/assembly
- Define detailed specification for coupler
- Processing procedure
- Fixed or tuning of the coupler
- Define sensors needed
- Interlock electronics



XFEL Project Group

6. HOM Coupler / Pick-Up


- TW absorber
- Define detailed specification for HOMs
- Define processes for assembly
- Improved existing HOM coupler
- Define detailed specification for pick-ups
- Define processes for integration/assembly
- Cavity HOM loads at 70K?
- Integrate antenna in feedthrough



XFEL Project Group

7. Frequency Tuner


- Define detailed specification for tuner
- Define processes for integration/assembly
- Piezo mechanical design





XFEL Project Group

8. Cavity Flanges / Cold Vacuum (incl.warm injector section)

- Define detailed specification for flanges
- Define processes for integration/assembly
- Investigate/ Improve existing design for TTF2
- Type of bellows
- Number of bellows
- Number and design of gate valves
- development of new flange design
- Welded or flanged design? Where?






XFEL Project Group

10. Module Test Facility


- Module test stand



XFEL Project Group

11. Cold Magnets


- 2K Quadrupole
- Measurement of mechanical vibrations



XFEL Project Group

12. Warm Magnets


- Design of all warm magnets for the entire machine
- Production or contact to production sites



XFEL Project Group

13. Cryogenics


- Use of HERA plant?
- Separate injector/main linac systems?
- Cost aspect: start small, upgrade later?



XFEL Project Group

14. Injector


- Long. internal bunch structure?
- Cavity tilts/coupler kicks?
- Bunch parameter space: low eps w. low charge/higher compression (or vice versa)?
- Rep. rate and duty cycle?



XFEL Project Group

15. Bunch Compression and Start-to-End Simulation


- Compressors: parameter space: lower charge/higher compression (or vice versa)?
- Sensitivity of bunch shape/structure vs. charge, phase, etc. fluctuations?
- Energy at BC-III variable (at BC-II??) Å impact on energy vs. rep rate issue?
- FODO-type stage desirable (possible)?
- Switch yard
- Collimators
- Incorporation of FEL/SASE processes (undulators)



XFEL Project Group

16. Lattice Design and Beam Optics/Dynamics


- Main linac and BC matching
- Orbit correction & beam-based methods
- Collimation and diagnostic section
- Beam transport and distribution to user beam lines
- Orbit stability/stabilisation (slow and fast feedback)
- Lattice in undulator systems, phase shifters, correctors, matching sections
- Transfer to dump



XFEL Project Group

17. Standard Beam Diagnostics


- BPMs
- Screen monitors
- Beam intensity and loss monitors



XFEL Project Group

18. Special Beam Diagnostics


- Slice Parameters and longitudinal phase space diagnostics
- Sub-picosecond timing and synchronization
- Other specialized devices



XFEL Project Group

19. Vacuum system (warm)


- Warm beam pipe distribution starting from switch yard
- Bunch compressors
- Undulator vacuum
- Exit chambers to beam dumps
- Exit windows



XFEL Project Group

20. Beam Dumps


- Modifications to adapt to new site?
- Else?



XFEL Project Group

21. Undulators


- SASE, spontaneous, helical
- Design
- Mass production preparation



XFEL Project Group

22. Generic Hard Photon Beam Line


- High resolution monochromators
- Mirrors and gratings
- Slits and absorbers
- Photon diagnostics
- Beam splitters
- Extreme focussing devices
- Vacuum system
- Control systems



XFEL Project Group

23. Generic Medium Energy Photon Beam Line


- High resolution monochromators
- Mirrors and gratings
- Slits and absorbers
- Photon diagnostics
- Beam splitters
- Extreme focussing devices
- Vacuum system
- Control systems



XFEL Project Group

24. Photon Diagnostics


- Diagnostics for the photon beam quality
- Feedback to electron beam preparation and steering
- Undulator tuning



XFEL Project Group

25. Experimental Areas


- Details according to 'coherence', 'ultra short', 'diffraction' etc.
- Lasers
- DAQ other than Control; Systems?
- Control systems



XFEL Project Group

26. Detector Development


- Development of instrumentation and analysis tools for the XFEL physics
- experiments



XFEL Project Group

27. FEL Concepts


- Transportation of general theoretical developments in the area of FEL physics into the XFEL project
- Coordination of review of present FEL concepts
- Seeding options (coherent seeding, time slicing,?)



XFEL Project Group

28. Control Systems


- Conventional timing issues
- Overall 'slow control' for the entire machine
- Automatic procedures (e.g. beam based corrections, failure recovery)
- Data analysis software
- Files systems and databases
- User interfaces



XFEL Project Group

29. Operability/Failure Handling


- Assess technical risks from component failures
- Mean time to restart of user operation after failure of various components
- Single/two tunnel argumentation
- Maximize reliability aspects



XFEL Project Group

30. Ground Motion and Mechanical Stability


- Monitoring of ground motion and vibrations
- Damping measures



XFEL Project Group

31. Site and Civil Construction


- Evaluation of the two (?) DESY-near sites
- Civil construction
- Tunnels
- Switch yard
- Experimental hall and other buildings
- Access shafts



XFEL Project Group

32. Survey and Alignment


- Survey and alignment issues, implementations, implications



XFEL Project Group

33. Tunnel installation


- Layout
- Placement of components
- Support structures
- Transport system



XFEL Project Group

34. Utilities


- Power distribution
- power supplies
- Water cooling, compressed air
- Integration of existing utilities
- Ventilation and air conditioning
- Temperature stabilisation
- Industry-type controls for utilities



XFEL Project Group

35. Radiation Safety


- Analysis of radiation safety issues
- Implementation of radiation safety procedures and techniques
- Interlocks
- Construction plan approval issues



XFEL Project Group

36. General Safety


- Analysis of general safety issues
- Implementation of general safety procedures and techniques
- Electrical safety
- Procedures



XFEL Project Group

37. Construction Plan Approval Procedure

- Preparation of all material for construction Plan approval procedure
- Organization of plan approval issues
- Discussion with the public
- Legal procedures
- Etc.



XFEL Project Group

38. Overall Project Progress Tracking

- Organization and implementation of common tools for progress tracking
- Time schedule follow-up
- Cost to completion follow-up
- Configuration control
- Documentation
- Expenditure planning
- Work breakdown structure at higher levels

