



11th Workshop on RF Superconductivity
September 8-12, 2003

Travemünde/Lübeck, Germany

Status of the TTF FEL

Siegfried Schreiber, DESY

- 😊 Highlights from the TESLA Test Facility (TTF 1) Linac runs
- 😊 Upgrade to a user facility VUV FEL (TTF 2)
- 😊 Status and Milestones
- 😊 Summary

email: siegfried.schreiber@desy.de





The TESLA Collaboration

... has at present 3 projects:

TESLA LC, TESLA X-FEL and VUV FEL (TTF2)

■ **TESLA LC** is one of the competitors for the next HEP large accelerator facility.






■ **TESLA X-FEL** is the core of a proposal for an European Laboratory of Excellence for fundamental and applied research with ultra-bright and coherent X-ray photons.

■ **VUV FEL (TTF2)** will be the first user facility for VUV and soft X-ray coherent light experiments with impressive peak and average brilliance.

It is also a test facility for further TESLA LC related R&D.



TESLA Test Facility Linac (TTF 1)




TTF/TESLA Accelerating Modules

C. Pagani et al,
INFN LASA

- ☺ Three “generations” of cryomodule design, with increasing simplicity and decreasing costs
- ☺ Three 3rd generation modules assembled, 2 installed in TTF


Length	12 m	
# cavities	8	
# quad doublets	1	
Static losses	@ 2K	1.5 W
	@ 5K	8 W
	@ 50 K	70 W

- ☺ Eight 9-cell TESLA accelerating structures and a quadrupole/steerer package



☺ Example of improvements


Simplified alignment Strategy



“Finger Welded” Shields



Sliding Fixtures @ 2 K




Qualification tests in LASA





Experience from TTF 1 Operation

- 😊 Maximum obtainable gradient in a cavity
 - 😊 is given by low Q, high field emission or quench – but not by structural damage
 - 😊 is not a hard limit, it results in higher cryogenic load, radiation, and darkcurrent
- 😊 The vector sum low level RF regulation has a “quench detection” to avoid chain quenches

Example of quenches in a module



Cavity performance progress




😊 Progress mainly due to: improved welding and stricter Niobium quality control


Electro-polished 9-cell cavity Tests

L. Lilje et al.


Example:



Beam Experiments with Superstructures




Energy refilling with beam loading (4mA)



😊 Weakly coupled cavities do accelerate TESLA bunch trains



😊 Dipole modes (<2.6 GHz) are suppressed better than specs

Search for HOM's with modulated bunch trains



Principle of a SASE FEL

SASE Self Amplification of Spontaneous Emission





- »» bunch interacts with undulator field
- »» micro bunches develop
- »» which emit coherently
- $\sim N^2$ with $N \sim 10^6$

TTF 1: gain length
 $L_{\text{gain}} = 67 \pm 5 \text{ cm}$

TTF 1 FEL has achieved Saturation

First Lasing: Phys. Rev. Lett. 85(2000)3825


Saturation: Phys. Rev. Lett. 88(2002)10482, The European Physical Journal D 20(2002)149




😊 Saturation achieved Sep 10, 2001
 with a wavelength of $\lambda = 98.1 \text{ nm}$

FEL pulse length
 $dE^2 = 1 / (\text{nb. of modes } M)$
 $= 1 / 2.6$
 $M \cdot \text{coop. length } (5 \mu\text{m}) \approx$
 $L_{\text{pulse}} = 50 \text{ fs}$

Beam Energy and FEL Wavelength



Courtesy R. Ischebeck




FEL radiation:
measured diffraction pattern
of a double slit


First TTF FEL Experiment: Ablation

☺ Investigation of FEL beam induced damage of optical elements (optical coatings Al or Au, on Si wafers).

$\lambda = 98 \text{ nm}$, $W=100 \text{ TW/cm}^2$




Surface of photoresist PMMA (polymethyl methacrylate) after multiple irradiation by SASE FEL pulses $\lambda = 85 \text{ nm}$




Institute of Physics of the Polish Academy of Sciences (IFPAS), Warszawa
Courtesy J. Krzywinski

The Cluster Experiment




The clusters absorb many photons from the FEL pulse simultaneously and burst by **Coulomb explosion**

Time of flight mass spectrum of Xe clusters (~300 Xe atoms) produced by multiphoton ionization recorded in a **single shot** with FEL radiation at 98 nm



H. Wabnitz et al., Nature 420, 482 (2002)

Tuning the FEL Radiation Pulse Duration




probability density distribution of the measured energy in the FEL radiation pulse

single shot spectra profiles


spectrometer image of the FEL radiation pulse

measured longitudinal electron bunch shape

Peak brilliance of the TTF 1 FEL





GAN: TTF Practiced Remote Operation




TTF 1 Operational Statistics

- ☺ Operated 7 days per week, 24 hours per day
- ☺ 15,000 hours of beam time since 1997
- ☺ About 50 % of the time was allocated to FEL operation including a large percentage of user time.



Week 3/2002

**FEL
Operation**



Week 7/2002

**Accelerator
Studies**




TESLA Test Facility Linac (TTF 2)



Goal: FEL user facility from the VUV to the soft X-ray (6 nm) wavelength range






up to 7 accelerator modules with eight 9-cell superconducting TESLA cavities each



Photoinjector Test Stand at DESY Zeuthen

- ☺ RF gun is commissioned
- ☺ flat hat laser system installed
- ☺ measurement of beam properties under way




TTF Hardware picture Gallery




Installation of modules into the TTF linac


TTF 2 Hardware Picture Gallery



collimator




button BPM




quadrupole, sextupole




dipole, steerer




stripline BPM



kicker




dipole, steerer




TTF 2 Hardware Picture Gallery



wire scanner



toroid



optical transition radiation (OTR) vacuum chamber with screen mover

OTR optical system




TTF2 Hardware Picture Gallery

$L_{\text{und}} = 27.3 \text{ m}$

$B_{\text{peak}} = 0.47 \text{ T}$

Gap = 12 mm

6 undulator modules
à 4.5 m length




$E = 1 \text{ GeV}$


$K = 1.17$

$\lambda_{\text{rad}} = 100 \dots 6 \text{ nm}$

J. Pflüger et al.




Drawing of the Undulator Section



Bunch Length Measurement Example


😊 transverse deflecting cavity: Cooperation SLAC/DESY




Is being installed
at DESY now

Expected
resolution $<10 \mu\text{m}$

Layout of the Experimental Hall



TTF 2 Milestones for this and next Year



Summary

😊 TTF 1 run successfully ended Nov 18, 2002 after 15,000 h of beam time


- several TESLA superconducting accelerating structures tested, with and without full beam loading, incl. higher order modes experiments
- SASE FEL runs: lasing and saturation in the VUV achieved
- two successful FEL experiments

😊 TTF 1 is being extended to 1 GeV with the goal of a user facility from the VUV to the soft X-ray wavelengths



- RF test of three installed modules ongoing
- installation of the injector this year
- remaining installation in parallel to injector runs
- first beam into the dump expected mid 2004



TTF 2 Laser Upgrade



- 😊 Together with Max-Born-Institute, Berlin (I. Will et al.)
- 😊 Upgrade is being tested at PITZ (DESY Zeuthen)



NEW:
Longitudinal flat profile

Parameters of the TTF 1 FEL

FEL	Wavelength	80 – 120 nm
	2 nd harmonic	48.5 nm at 0.1...1 % intensity of fundamental
	Pulse energy at saturation	30 – 100 μ J
	Pulse duration	30 – 100 fs (fwhh)
	Peak power	1 GW
	Average power	Up to 5 mW
	Spectrum width	1 %
	Spot size	250 μ m
	Angular divergence	260 μ rad
	Peak brilliance	Up to 10^{29} ph/(s mrad ² mm ² 0.1% bw)
	Average brilliance	Up to 10^{18} ph/(s mrad ² mm ² 0.1% bw)
Beam	Bunch charge	2.7 – 3.3 nC
	Peak beam current	1 – 1.5 kA
	Charge in radiative part of the beam	0.1 – 0.2 nC
	Duration of the radiative part of the beam	50 – 150 fs
	Normalized emittance	4 – 7 mm mrad (rms)