
Recent Results from Second Sound, T-Mapping and Optical Inspection of 1.3 GHz Cavities at DESY

Felix Schlander, Sebastian Aderhold, Detlef Reschke, Krzysztof Twarowski **Deutsches Elektronen-Synchrotron DESY, Hamburg, Germany**




Abstract


Fundamental field modes in a 9-cell cavity



Cavity tests

Test results






Mode	Quench location (dz = ±10mm, dφ = ±5°)	Cells (#) with highest field [MV/m	
π-mode	Iris area between #2/#3 @ 200°	#1 - #9:	44.5
8/9 π- mode	21 mm below equator #1 @ 133°	#1 , # 9:	45
7/9 π-	Iris area between	#5:	49
mode	#1/#2 @ 230°	#1 , #9:	46
6/9 π-	Iris area between	#1 , #3, #4,	43
mode	#1/#2 @ 230°	#6, #7, #9:	
5/9 π-	10 mm above	#5 :	47
mode	equator #5 @ 186°	#3, #7:	44
4/9 π-	7 mm above	#4 , #6:	50
mode	equator #4 @ 274°	#2, #8:	44

Very good agreement between all diagnostic tools

Comparison of mode measurements with second sound data



Results:

When measuring successfully there is good agreement between the location derived from second sound and the peak field excited in mode measurements in a given cell

- Few datasets show quenches in cells with higher fields than in π -mode, but not in cells with highest field gradient
- For very few datasets there is no obvious correlation between field and quench location
- > Almost half of "bad" second sound measurements are due to noise and low signals

Gradient performance of cavities tested by material and surface treatment – the colors indicate the surface treatment

Summary

From November 2009 to June 2011 there were 66 tests in total of 9-cell cavities in the vertical test stands at DESY.

The cavities experiencing BCP treatment do not exceed an accelerating field of 30 MV/m thus confirming earlier observations

EP cavities reach higher accelerating gradients. However, some cavities fail at small gradients due to strong field emission.

Second sound and temperature mapping were used on some 10 cavities and the results show good agreement between the mode measurements and quench locations

than pi-mode	21% defect on the f-part of AC151	AC151 had a damaged HOM coupler antenna (f-part) leading to Q-switches (local	
Observation from 118 mode measurements and simultaneously running second sound	Categories for failing second sound location.	heating at the latter HOM coupler) and no proper measurements	Special thanks to the staff working in the cavity test area (hall 3)
measurement (13 cavities + 1 cavity with HOM feedthroughs).		Some second sound measurement fail when the stored energy in the cavity is too low	

