


Infrastructure, Methods and Test Results for the Testing of 800 Series Cavities for the European XFEL


Detlef Reschke / DESY

for all colleagues working on European XFEL series cavities





- Introduction
- Infrastructure for Vertical Acceptance Tests
- Cavities
- Procedures
- Vertical Test Results
 - “As received”
 - After re-treatment
 - Q-Values
- Summary + Outlook



- Vertical acceptance tests of European XFEL
 - Pre-Series + Series Cavities
 - “HiGrade”-Cavities



- 800 pre-series + series cavities
- ≥ 8 cavities per week (\Rightarrow 1 module per week)


- Cavities are produced and surface treated at industry
 \Rightarrow ***Talk by W. Singer MOIOA03***

- Status of vertical tests: **September 10 !**


Infrastructure: AMTF

- Accelerator Module Test Facility
- New Infrastructure for vertical acceptance test (+ module tests)
 - **Two** independent vertical cryostats
 - **Six** inserts for **four** cavities each
 - **Two** independent rf test stands






- Vertical tests started in Feb 2013 (IFJ-Pan & DESY)
- Parallel commissioning of inserts + vertical tests on series cavities (last insert to be qualified end of Sep)
- New software for vertical tests
- no Second Sound; no T-Mapping
=> if necessary at hall3



Cavities



- Cavities arrive at DESY in a transport box
 - Fully equipped with HOM-antennas, Pick-up antenna + fix High Q antenna
 - Under vacuum
 - **Ready for testing**

- A) Pre-Series + Series Cavities **with He-tank**


- B) “HiGrade” Cavities **without He-tank**
 - 12 cavities by each vendor
 - Use as quality control with the option of Second Sound and/or T-Mapping
 - (later: use for high gradient ILC research)



Poster MOP043

Poster MOP053

Procedures: Incoming Inspection



■ Incoming inspection checks

Poster MOP037

- Mechanical: damages during transport, obvious assembly errors
=> feedback to companies!
- Electrical: pi-mode frequency + fundamental mode spectrum, shorts at antennas
- Vacuum: next slide

Poster MOP052

Poster THP093



Procedures: Preparation for Vertical Test

8

- RF preparation:
 - Time-Domain reflectometer measurement
 - Tuning of Fundamental Mode Rejection Filters of both HOM couplers
- Vacuum:
 - Leak check ($< 1 \times 10^{-10}$ mbar·l/s)
 - Residual Gas Analysis => check for hydro carbon contamination




Procedures III: Vertical Acceptance Test at 2K

9


- “Standard” cavity test at 2K
 - Measurement of $Q_0(E_{\text{acc}})$ in π -mode
 - Measurement of fundamental mode frequencies
 - X-ray measurement on top and below each cryostat
 - Remark: no $Q_0(T)$,
no $Q_0(E_{\text{acc}})$ in fundamental modes,
no $Q_0(E_{\text{acc}})$ at various bath temperatures
 - Remark II: RF measurement one by one




Procedures: Outgoing inspection + transport



- Outgoing inspection: backwards incoming inspection
- Transport to CEA Saclay for string + module assembly



Procedures: Result + Decision



- Vertical test results stored as **raw data** and in **XFEL Cavity data base**

Poster MOP041

- Acceptance Criteria:**

“...maximum gradient > 26 MV/m with an unloaded Q_0 of $\geq 1 \times 10^{10}$ and a X-ray level lower than 1×10^{-2} mGy/min.”

(with 26 MV/m to give 10% margin compared to 23.6 MV/m design gradient)

- If acceptance criteria **passed**

=> preparation for transport + string assembly


- If acceptance criteria is **not passed**

=> **re-treatment at DESY**

(Reminder: **No performance guarantee by the vendors**, i.e. the risk of unexpected low gradient or field emission is with DESY)

- “Usable Gradient”:** i) Quench
ii) $Q_0 < 1 \times 10^{10}$
iii) radiation $> 1 \times 10^{-2}$ mGy/min

Vertical test results: As received / 1. Pass



- 79 cavities tested **as received** (1. pass) with
 - 23 from Research Instruments (RI)
 - 56 from E. Zanon (EZ)

- As received: **50 cavities passed**
 - 15 from RI
 - 35 from EZ

- Strict application of acceptance criteria
(Comment: Some cavities retreated though acceptance criteria formally met)


- No selection, no cut

- 29 cavities in re-treatment loop => later

Yield of gradients: As received / 1. Pass

13

Yield of usable and maximum gradient of 79 cavities as received




Average **maximum** gradient:

(28.1 ± 7.8) MV/m

EZ: (27.6 ± 7.7) MV/m

RI: (29.2 ± 8.2) MV/m



Average **usable** gradient:


(25.0 ± 7.7) MV/m

EZ: (24.5 ± 7.6) MV/m

RI: (26.1 ± 7.8) MV/m

given errors are standard deviation


Vertical test results: Re-treatment / 2. Pass



- Re-treatment decided mainly because of field emission and/or low Q-value
- Two re-treatment options at DESY applied:
 - **High Pressure Rinsing (HPR)**
 - **10μm BCP + HPR + 120C bake**
- after HPR: 13 cavities with 11 passed
- after BCP: 1 cavities with 0 passed
- 15 cavities missing???
- => still in re-treatment loop !!!

Yield of gradients: After re-treatment (2. pass)

- Yield of usable and maximum gradient of 64 cavities (2.pass):
50 cavities passed in 1.pass + 14 cavities after re-treatment
- Average gradients increased + spread reduced** (standard deviation)




Average maximum gradient:

(30.9 ± 4.4) MV/m

EZ: (30.4 ± 4.5) MV/m

RI: (32.3 ± 4.1) MV/m



Average usable gradient:

(29.0 ± 3.9) MV/m

EZ: (28.4 ± 4.0) MV/m

RI: (30.6 ± 3.1) MV/m

Vertical test results: Q-Values

16


- Measurement with fix coupling
=> overcoupled at low and medium gradients
=> larger error than $\beta \approx 1$

- Low field Q_0 -value:
- As received / 1.pass: $Q_{0,\max} = (2.2 \pm 0.4) \cdot 10^{10}$ (standard deviation)
(as before 79 cavities)
- After re-treatment / 2.pass: $Q_{0,\max} = (2.4 \pm 0.4) \cdot 10^{10}$
(as before 64 cavities)

- Few cavities show Q-value $< 2 \cdot 10^{10}$ at low gradient
=> feedback and quality control to companies

Poster MOP042


Summary + Outlook



- Vertical test operation in AMTF started successfully
- Handling + inspection procedures for series cavity delivery developed and in application
- **Vertical acceptance test results are satisfactory for both vendors**
- Re-treatment by HPR at DESY very successful
- 44 cavities shipped to Saclay

- Ramp-up to > 8 cavities tested per week
- Follow-up of gradient and Q-value for quality control
- Goal: Improvement of “as received”-yield

Acknowledgement




- Thanks to all colleagues of the different institutes and companies involved in cavity production, surface preparation and cavity testing
- Special thanks to Krzysztof Krzysik, Laura Monaco, Vladimir Gubarev and Nick Walker for their material for this talk

Additional Slides

19

■ **text**

Infrastructure: Hall 3



- “Old” Infrastructure for vertical acceptance test
 - Two vertical cryostats
 - Four inserts for **one** cavity each
 - Two independent rf test stands
 - Analysis with Second Sound + Temperature Mapping available (only for cavities w/o He-tank!)

