




Outlines



- **Introduction of ADS Project of China**
- Progress of 325 MHz SRF Linac
- Progress of 162.5 MHz SRF Linac
- Progress of 25-MeV Demo Facility
- Summary





Motivation (NPP in China)




● To July 2013 (<http://www.iaea.org/NuclearPower/Systems-and-Databases/index.html>)

- 18 reactors in operation, 13.860GW_e ; (6th in the world)
- 28 reactors under construction, 27.790GW_e ; (1st in the world)

● Estimation for the future (slow down after 2011.3)

- **2020**: $\sim 58\text{ GW}_e$ NPP in operation
- **2030**: $\sim 10\%$ of NP to total power capacity
- **2050**: $350\text{--}400\text{ GW}_e$, $\sim 20\%$ of NP to total power capacity
→ almost same as the scale of the total in the world today!

Nuclear Waste Management is a serious Issues for Sustainable NP Development





Roadmap of ADS project in China



- IMP is the leading institute to carry out the research in cooperation with a number of participants.



IHEP

The CAS ADS Program

CASHIPS



中国科学院高能物理研究所
Institute of High Energy Physics Chinese Academy of Sciences





Hefei Institutes of Physical Science
Chinese Academy of Sciences



Injector II, 162.5 MHz



Injector I, 325 MHz



Stage 1: Research facility (CIADS)
(250 MeV, 10 mA, 10 MWt)
Y2017-2022, 1.867 B CNY


Y2011-2016, 1.78 B CNY

“Strategic Technology Pilot Project” of CAS
Key technology R&D


Stage 2: Demo facility (CDADS)
(1.0~1.5GeV, 10~25 mA, 500 MWt)
Y2030

China Initiative Accelerator Driven System

- Budget: ~1.867 B CNY
- Location: Huizhou, Guangdong Prov.





25 MeV/10 mA/CW Proton sc-Linac





Location of CIADS



- A new site, which locates in Huizhou, Guangdong, was selected
- This new site is nearby the planed Huizhou nuclear power plant


场区鸟瞰图




Outlines



- Introduction of ADS Project of China
- Progress of 325 MHz SRF Linac
- Progress of 162.5 MHz SRF Linac
- Progress of 25-MeV Demo Facility
- Summary







- Ion sources, 35 keV
- RFQ
 - frequency 325 MHz, 3.2 MeV,
 - RF power 280 kW, four couplers
- SRF cryomodules
 - Frequency 325 MHz, 2 K operation
 - Spoke beta=0.12, Ep=32 MV/m, Vacc =0.78 MV
 - 7 Spokes and 7 solenoids per module

Injector I at IHEP

Commissioning of spoke test module




- Pules: 11 mA, 50 Hz, duty factor >90%
- Efficiency > 97% (duty factor 70%)
- Energy 3.2 MeV, average power > 31 kW





2K and spoke technique


- Two spokes
- Pules: 10 mA, 30~130 us, 1 Hz
- Efficiency > 99.7%
- Energy 3.61MeV



Vertical test results of Spoke012



No.	Eacc [MV/m]	Q_0 @7MV/m
4#	14.6	1.2e9
6#	14.7	1.3e9
7#	13.4	6.5e8
8#	15.4	5.5e8
9#	15.9	5.9e8
11#	15.3	6.5e8
12#	13.4	1.0e9
13#	14.1	9.0e8




Assembly of Spoke Module of 5 MeV



The first cryomodule of spoke has been installed in tunnel last month. New clean room was employed to install coupler.

RF conditioning is ongoing and the beam commissioning will be in September.



2 K Cryogenic Plant




- Air Liquid, 1000W/4.5K
- FSD571 main compressor
- Recycle compressor
- Purifier + Analyzer
- LN₂ tank
- Gas Helium buffers




Outlines




- Introduction of ADS Project of China
- Progress of 325 MHz SRF Linac
- **Progress of 162.5 MHz SRF Linac**
- Progress of 25-MeV Demo Facility
- Summary






Injector II at IMP



- **RFQ**
 - frequency 162.5 MHz, 2.1 MeV,
 - RF power 100 kW, 2 couplers
- **SRF cryomodules**
 - Frequency 162.5 MHz, 4.5 K
 - HWR beta=0.1, Ep=25 MV/m, Vacc =0.78 MV
 - 6 HWRs and 6 solenoids per module





Commissioning of HWR test module




- June 6th, 2014, the first beam, 2.16 MeV
- June 30th, 10 mA, CW, 21 kW, 4.5 hrs
- Operation > ~1000 hours by now
- Non-trip operation ~220 hrs

- Oct. 1st, 2014, first beam, 2.6 MeV, 2.3 mA
- Nov. 25th, first CW, 3.4 mA around 6 hours.
- Feb. 23rd, 2015, 2.55MeV/~11mA/28kW, 1 hour
- Total operation time was ~ 200 hours.

Vertical test results of HWR010



V _{acc} (MV)	0.78
B _{peak} (mT)	50
E _{peak} (MV/m)	25
E _{acc} (MV/m)	4.7
β_{opt}	0.10
Q ₀	4.0E08




Assembly of HWR module of 5 MeV





Facilities of SRF




Cryogenic plant of 850 W at 4.2 K



- Linde L280, 850W/4.2K
- FSD571 main compressor
- DS85 recovery compressor



- Recovery compressor, 15MPa/40m³*4
- HP He purifier, 15MPa/100m³
- HP He tank, 15MPa, 8000m³
- Gas bags, 25m³*2
- Purity analyzor on line



Commissioning of 5 MeV Linac



- June 6th, 2015, 5.2 MeV, 10.2 mA, short pulse, 100us@1Hz; MPS upgrade
- June 12th, 2015, 5.1 MeV, 2.7 mA, 100ms@1Hz ; radiation protection upgrade
- June 24th, 5.3 MeV, 2.7 mA, CW, 5 min, MPS upgrade
- Beam trips due to loss of phase lock
- The next turn of commissioning starts soon






Outlines



- Introduction of ADS Project of China
- Progress of 325 MHz SRF Linac
- Progress of 162.5 MHz SRF Linac
- **Progress of 25-MeV Demo Facility**
- Summary






The Demo SRF Linac of 25 MeV




162.5 MHz Half-wave Cavity




Beta=0.1

IMP & IHEP
By 2016




162.5 MHz Taper HWR

Beta=0.15



325 MHz Spoke cavity





Beta=0.21



Exploded View



Status of Resonators for 10~25 MeV



- ✓ 8 Spokes were tested
- ✓ $H_p = 98$ mT @ $Q_0 = 5e8$
- ✓ 4 T-HWR were tested
- ✓ $H_p = 85$ mT @ $Q_0 = 5e8$



Design of Taper HWR015 CM




Commissioning Hall



Vertical testing



Liquid Helium distribution



Power supply



Beam diagnostic



LLRF



Solid state AMP




Amplifier of RFQ



Outlines



- Introduction of ADS Project of China
- Progress of 325 MHz SRF Linac
- Progress of 162.5 MHz SRF Linac
- Progress of 25-MeV Demo Facility
- Summary






Summary



- ▶ The prototypes of Spoke and HWR are commissioned. One has achieved 11 mA, CW proton beam.
- ▶ 5 MeV of HWR Linac has been commissioned and got 10 mA pulse beam. The first attempt to CW was succeeded and lasted 5 min. The LLRF need to be upgraded to keep the stability.
- ▶ The demo SRF linac with 25 MeV/10 mA/CW will be build in 2016 and coupled with granular target.
- ▶ Chinese Initiative ADS project (CIADS) will be approved soon. 250 MeV SRF proton linac, Granular target and 10 MWt subcritical LBE FR are chosen.






Summury



More details about SRF resonators for Chinese ADS

- ▶ Presentation WEBA01
by Dr. Feisi HE on Wednesday Morning

- ▶ Posters
THPB-015, TUPB097, TUPB017, THPB087, THPB101





Acknowledgements



Thanks for your attention

&

Linac Team of China ADS

Thanks for the helps

from LBNL, J-Lab, TRIUMF, ANL, MSU/FRIB, ORNL, FNAL,
RIKEN, CEA/Saclay, IPN/Orsay, IAP, KEK,

HIT, PKU, SINAP,.....

Welcome Collaboration!

