

Status of the SRF systems at HIE-ISOLDE

W. Venturini Delsolaro

L. Arnaudon, K. Artoos, C. Bertone, J.A. Bousquet, N. Delruelle, M. Elias,
J.A. Ferreira Somoza, F. Formenti, J. L. Grenard, Y. Kadi, G. Kautzmann,
Y. Leclercq, M. Mician, A. Miyazaki, E. Montesinos, V. Parma, G. J. Rosaz,
J. C. Gayde, K. M. Schirm, E. Siesling, A. R. M. Sublet, M. Therasse,
L. Valdarno, D. Valuch, L.R. Williams, P. Zhang

CERN, Geneva, Switzerland



SRF2015
17th International Conference on
RF Superconductivity
Whistler Conference Centre
September 13-18 2015




Contents

- HIE ISOLDE project roadmap
- Series production of Nb/Cu QWR
- First cryomodule assembly experience
- Cryomodule commissioning experience
- Summary and outlook


The HIE ISOLDE project at CERN

HIE-ISOLDE aims at boosting the energy of the Radioactive Ion Beams of REX-ISOLDE from 3 MeV/u up to 10 MeV/u ($A/q < 4.5$) by means of a SC linac




The HIE ISOLDE project at CERN


HIE-ISOLDE aims at boosting the energy of the Radioactive Ion Beams of REX-ISOLDE from 3 MeV/u up to 10 MeV/u ($A/q < 4.5$) by means of a SC linac




High β section, beam lines, experiments



High β section, beam lines, experiments



High β section, beam lines, experiments




High β section, beam lines, experiments







HIE ISOLDE roadmap for 2015

Cryogenics incident (burst disk rupture) Aug 12th

Tests on RF power limits





Series production of Nb/Cu QWR





Cavity tuning

influence variables	frequency shift (kHz)
295 K to 4.5 K and air to vacuum	+371 +/- 5
chemical etching 40'	-27 +/- 3
Nb coating	-7 +/- 5






Copper cavity substrates: quality issues




- Appearance of surface defects (looking like cracks) in the HAZ of the EB weld at the cavity top.
- Shrink fit and weld stopped at the supplier
- Investigations ongoing at CERN
- One cavity singled out for destructive analysis

Surface resistance vs. temperature gradient across T_c



QP3.2 after rinsing with new plate (ambient B-field)




Surface resistance vs. temperature gradient across T_c




Thermal gradient: $\Delta T = T_2 - T_1$




Vertical test performance (CM1 cavities)



HIE ISOLDE Cold Box installation



Cryogenics distribution system



Cryogenics distribution system



Cryomodule assembly: infrastructure



Cryomodule assembly: early stages



Final leak test without cavities



Cavity mounting




5 cavities



With tuners (and couplers)

TUPB106




Cryomodule transport




Shield opened for installation



CM1 installed






CM1 cool down



Survey and alignment

Delta Z (mm) over time during first cool down (0-->504H)




Static heat load at 4.5 K (boil-off test)

Distribution of heat into boil-off of liquid and structure warm-up;


Temperatures on Thermal Shield, Cavities/Solenoid, etc. constant during the test

Measurement results:

- Helium level ~10 l/h: ~7W
- Warm-up frame : ~2.5W




CM1 cavity test results




Combined powering of cavities and solenoid

- Cav 1
- Cav 2
- Cav 3
- Cav 4
- Cav 5



Solenoid current: 0A → 100A → 0A

Performance of LLRF system




The trouble with RF input lines

Observation: RF drifts when driving cavities at high power to initially assumed operational bandwidths
→ thermal effects in the power coupler

Potential showstopper...

- Dedicated test in vertical cryostat → permanent damage at 200 W
- Post mortem analysis
- Second test → still OK after 9 hours at 60 W
- Task force (simulations and experiments)
- Adapting LLRF loops to reduce bandwidth
- Now 3 Hz (requiring ~ 50 W at nominal) seems possible)



Summary and Outlook

- HIE-ISOLDE project made remarkable progress since last SRF
- All technical infrastructures deployed and operational
- Cavity production ongoing: issue with quality of copper substrates
- Five cavities were delivered on time for installation in a cryomodule.
- The first cryomodule assembly in clean room was successful
- Cryomodule commissioning results globally positive: the vacuum performance, static heat loads, alignment accuracy, performance of the superconducting elements, and that of the low level RF systems were satisfactory.

- A problem of thermal stability in the RF couplers/lines was identified
- Being addressed
- Beam commissioning starting now
- Plan to delivery of beam to the experiments this year.