

The BEPCII: Construction and Initial Commissioning

C. Zhang

On behalf of the BEPCII Team

Jan. 31, 2007, APAC2007

RRCAT, Indore, India



Image © 2007 NASA
© 2007 Europa Technologies

©2005 Google

Pointer 41°34'02.82" N 110°38'52.20" E

Streaming ||||| 100%

Eve alt 9792.95 mi

Performance of BEPC and Progress of BEPCII

The construction of the BEPCII has started since beginning of 2004. In the next APAC, APAC07, we should be able to report some results of BEPCII commissioning.



Summary

The BEPCII: Construction and Initial Commissioning



Jan. 31, 2007, APAC2007, RRCAT, Indore, India



General Description



Construction



Commissioning



Conclusion

The Milestones



January 2004

Construction started

May. 4, 2004

Dismount of 8 linac sections started

Dec. 1, 2004

Linac delivered e^- beams for BEPC

Mar. 19, 2005

First e^+ beam of 50mA obtained

July 4, 2005

BEPC ring dismount started

Mar. 2, 2006

BEPCII ring installation started

Nov. 13, 2006


BEPCII ring commissioning started

Nov. 18, 2006

First e^- beam stored in the ring

Dec. 25, 2006

Beams provided for SR users



(1) General Description

The BEPCII serves the purposes of both high energy physics experiments and synchrotron radiation applications.

Beam energy range	1–2 GeV
Optimized beam energy region	1.89GeV
Luminosity @ 1.89 GeV	$1 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$
Injection from linac	Full energy injection: $E_{inj}=1.55\text{--}1.89\text{GeV}$
Dedicated SR operation	250 mA @ 2.5 GeV

Main Parameters

Parameters		Unit	BEPCII	BEPC
Operation energy (E)		GeV	1.0–2.0	1.0–2.5
Injection energy (E_{inj})		GeV	1.55–1.89	1.3
Circumference (C)		m	237.5	240.4
β^* -function at IP (β_x^* / β_y^*)		cm	100/1.5	120/5
Tunes ($\nu_x / \nu_y / \nu_s$)			6.57/7.61/0.034	5.8/6.7/0.02
Hor. natural emittance (ε_{x0})		mm·mr	0.14 @1.89 GeV	0.39 @1.89 GeV
Damping time ($\tau_x / \tau_y / \tau_e$)			25/25/12.5 @1.89 GeV	28/28/14 @1.89 GeV
RF frequency (f_{rf})		MHz	499.8	199.533
RF voltage per ring (V_{rf})		MV	1.5	0.6–1.6
Bunch number (N_b)			93	2×1
Bunch spacing		m	2.4	240.4
Beam current	Colliding	mA	910 @1.89 GeV	~2×35 @1.89 GeV
	SR		250 @2.5GeV	130
Bunch length (cm) σ_l		cm	~1.5	~5
Impedance $ Z/n _0$		Ω	~ 0.2	~4
Crossing angle		mrad	±11	0
Vert. beam-beam param. ξ_y			0.04	0.04
Beam lifetime		hrs.	2.7	6–8
luminosity@1.89 GeV		$10^{31} \text{cm}^{-2} \text{s}^{-1}$	100	1

The luminosity strategy

DR: multi-bunch $k_{bmax} \sim 400$, $k_b = 1 \rightarrow 93$

Choose large ε_x & optimum
param.: $I_b = 9.75 \text{ mA}$, $\xi_y = 0.04$

$$L(\text{cm}^{-2}\text{s}^{-1}) = 2.17 \times 10^{34} (1 + R) \xi_y \frac{E(\text{GeV}) k_b I_b (\text{A})}{\beta_y^* (\text{cm})}$$

Micro- β : $\beta_y^* = 5 \text{ cm} \rightarrow 1.5 \text{ cm}$
SC insertion quads


Reduce impedance + SC RF
 $\sigma_z = 5 \text{ cm} \rightarrow < 1.5 \text{ cm}$

$$(L_{\text{BEPCII}} / L_{\text{BEPC}})_{\text{D.R.}} = (5.5 / 1.5) \times 93 \times 9.8 / 35 = 96$$

$$L_{\text{BEPC}} = 1.0 \times 10^{31} \text{ cm}^{-2}\text{s}^{-1} \rightarrow L_{\text{BEPCII}} = 1 \times 10^{33} \text{ cm}^{-2}\text{s}^{-1}$$



Detail machine physics issues refer to G. Xu, et al, Proc. of EPAC 2004, July 2004.

e^+e^- Colliders: Past, Present and Future




C. Biscari, Workshop on e^+e^- in 1-2 GeV Range, September 10-13, 2003, Italy

Three ring structure




BEPCII beamlines and experimental stations



(2) Construction

- **Injector Linac**
- **Storage Rings**
- **BESIII & BSRF**

2.1 The Injector Linac




- **Basic requirement:**
 - **Higher intensity: e^+ injection rate ≥ 50 mA/min.;**
 - **Full energy injection with $E=1.55 \sim 1.89$ GeV;**
- **To enhance the current and energy of the electron beam bombarding the target and to reduce the beam spot;**
- **To design and produce a new positron source and to improve its focusing;**
- **To increase the repetition rate from present 12.5 Hz to 50 Hz.**
- **To apply multi-bunch injection ($f_{RF}/f_{Linac}=7/40$);**

Measures to reach the goals

1) New e ⁻ Gun	High current ; low emittance
2) New e ⁺ Source	High e ⁺ yield; Large capture acceptance
3) New RF System with phasing loop	High RF power output; Stable phasing loops
4) New Beam Tuning Devices	Orbit correction; Optimum optics
5) Other System's Upgrade	Microwave system, Vacuum, Instrumentation, Control.

New Electron Gun

Parameters	Unit	BEPCII
Cathode		EIMAC Y796
Beam current	A	10
Pulse length	ns	1 (FWHM)
Emittance (norm.)	μm	14
Accelerating voltage	kV	120~200 Pulse / $3\mu\text{s}$
Heater volt. /current	V/A	6 ~ 8 / 5 ~ 7.5
Grid voltage	V	0~250
Grid pulse	V	-300 ~ -700
Bias voltage	V	+150 ~ +300
Operating Mode		1 or 2 Bunches
Repetition Rate	Hz	50



New Positron Source

A flux concentrator is employed to have a large e^+ acceptance:
 $L = 10 \text{ cm}$, $B = 5.3 \text{ T} \searrow 0.50 \text{ T}$, $\Phi = 7 \text{ mm} \rightarrow 52 \text{ mm}$.




New RF Power Source


50MW new klystrons

New modulators with high power 320 kV × 360 A.


High voltage stability $\leq \pm 0.15\%$





Microwave system



New Accelerating Structure (20 MV/m)




High power Wave Guide valve




SLED & New Detuning device


Phase control system



I/Q demodulator based PAD




IΦA unit




EPICS Based Control Software

To Phasing system server




Beam orbit stable in operation


Last 3 BPMs in the Linac jitter ≤ 0.1 mm (1σ)



BPM 14



BPM 15



BPM 16

Summary of the Linac commissioning

Parameters		Goal	Measured
Beam energy (GeV)		1.89	1.89
Beam current (mA)	e ⁺	40	61
	e ⁻	500	> 500
Repetition rate (Hz)		50	50
Emittance (1 σ) (mm·mrad)	e ⁺	0.4	0.4
	e ⁻	0.1	0.1
Energy spread (%)	e ⁺	± 0.50	± 0.4
	e ⁻	± 0.50	± 0.4

2.2 Storage Rings



🔒 RF System

🔒 Beam Diagnosis

🔒 Injection Kickers

🔒 Control System

🔒 Magnet System

🔒 Cryogenics

🔒 Power Supply

🔒 Interaction Region


🔒 Vacuum System

🔒 Installation

RF System



RF Frequency	f_{rf}	499.8 MHz
RF Voltage	V_{rf}	1.5 MV
Q Value		$>5 \times 10^8 @ 2MV$
Number of cavities	N_{rfc}	2×1
SR loss per turn @ 1.89 GeV	U_{rf}	123 keV/ring
Total RF loss @ 1.89 GeV	P_b	124 kW/ring
Power of RF transmitters	P_{rf}	2× 250 kW



Magnet System



Magnet type	Number
Dipole (Leff.=1.4135m)	40+1
Dipole (Leff.= 1.2277m)	2
Dipole (Leff.= 1.0339m)	2
Weak dipole (Leff.=1.0321m)	2
Weak dipole (Leff.=0.7453m)	2
Quadrupole	88+2
Old quadrupoles with modified coils	28
160Q quadrupole (Old)	6
Sextupole	72+1
Vertical corrector	48+1
Special vertical corrector	6
Quadrupole of the SR mode	1
Skew quadrupole	4+4
70B dipole (Old)	40+4
Octupole (Old)	2
Total	356




Power Supplies



P.S.	No.	Design Stability	Tested Stability
Q & S	165	1×10^{-4}	4×10^{-5}
OQ2,OQ3, IQ2, IQ3	16	1×10^{-4}	5×10^{-5}
B	4	1×10^{-4}	5×10^{-5}
BH,BV	144	1×10^{-4}	4×10^{-5}
T.Q	34	1×10^{-4}	4×10^{-5}
T.B	2	1×10^{-4}	4×10^{-5}
SC magnets	16	1×10^{-4}	1×10^{-4}
Q1a,Q1b,ISPB	3	1×10^{-4}	1×10^{-4}



Injection Kickers



Number of Kickers	4
Length	1.9m
Integral field	200Gs·m
Aperture	90mm×38mm
Good field region	±20mm
Field uniformity	±1%
The pulse repetition	50Hz
Stability of current	1%
Waveform	Half-sine wave
Pulse Width	600ns
Time jitter	<5ns
impedance	<0.025Ω



Vacuum System




- The design dynamic vacuum pressure are 8×10^{-9} Torr in the arc and 5×10^{-10} Torr in the IR.




- Antechambers are chosen for both e^+ and e^- rings.
- 80 arc chambers, 120 straight section chambers; 175 discrete photon absorbers 180 RF shielded bellows







- TiN coating for e^+ ring chambers to reduce SEY




Beam Diagnosis







- Beam Position Monitor
- Bunch Current Monitor
- SR monitor
- DCCT
- Transverse Feedback
- Tune measurement
- Beam Loss Monitor






Control System



Cryogenics



Interaction Region



Installation

	$\Delta x(\text{mm})$	$\Delta y(\text{mm})$	$\Delta z(\text{mm})$	$\theta_x(\text{mr})$	$\theta_y(\text{mr})$	$\theta_z(\text{mr})$
SC magnet	0.15	0.15	0.2	0.1	0.1	0.1
B	0.4	0.4	0.3	0.2	0.2	0.1
Q	0.15	0.15	0.5	0.5	0.5	0.2
S	0.2	0.2	0.5	0.5	0.5	0.5
BV, BH	0.5	0.5	1.0	1.0	1.0	0.5
RF	0.15	0.15	0.5	-	-	-
Kicker	0.3	0.3	1.0	1.0	1.0	0.5
Lambertson	0.3	0.3	1.0	1.0	1.0	0.5



Preasse



Putting the root screws on floor




air cushion



Aligning and adjusting

The installed outer ring in R3

2.3 BESIII and BSRF




BESIII Detector

Y.F.Wang, Inter. Journal
of Modern Physics A,
Vol.21(2006), 5371-5381.




BSRF

- Commissioning together with SR beam lines was carried out.
- Beams have been provided for SR users since Dec. 25,




BEPCII: a double-rings high luminosity e^-e^+ collider



(3) Commissioning

- The operation of the BEPC completed on July 4, 2005, dismount of the old ring started.
- After 16 months' hard work, the storage ring installation was finished in early November 2006 except the cryogenics of the magnets.
- It was decided to install conventional magnets in the IR to start storage ring commissioning and SR operation.
- In the meantime, improvement of the cryogenics system and measurement of the SC magnets are being carried out at the BESIII off-line position.

IR with conventional magnets



Some Results of the SR ring commissioning

Parameters	Unit	Measured	Design
Operation Energy	GeV	2.5	2.5
Injection energy	GeV	1.89	1.89
Circumference	m	241.130	241.127
RF voltage	MV	1.5	1.5~3.0
Tunes ($\nu_x/\nu_y/\nu_s$)		7.269/5.399/ 0.0242	7.270/5.370/ 0.0249
Beam emittance	nm·rad	100	
Bunch number		~100	200-300
Beam current	mA	200	250

[illegible]

When the first electron beam stored in the ring...




Hardware systems debug



- Power supply re-calibration with a larger current range;
- Misconnection of some corrector power supplies found and amended;
- Cables of the BPM's re-calibrated;
- Offsets of the BPM's were measured with beam based alignment;
- Some “bad” BPM's, judged by 3-button check, were disabled.

Orbit Correction


The orbit correction with transfer functions was performed. The residual rms orbit distortion after correction can be reduced to 0.42mm and 0.27mm on the horizontal and vertical planes, respectively



Twiss parameter measurement




Dispersion function measurement




Beam current and lifetime


- Maximum beam current reached 250 mA at 1.55 GeV and 1.89 GeV with no limit indicated.
- By improving the vacuum pressure with the accumulated beam dose, beam lifetime increases smoothly.




Joint commissioning & SR operation



SR user experiments, examples




A structure and function unknown protein



Sm423 – a protein in Serine degradation pathway




Sm424 – a protein in Serine degradation pathway



X-ray diffraction of BaRuO3 under high pressure

BEPCII Schedule



Concluding Remarks

- As a natural extension of the BEPC, the BEPCII is a double ring e^-e^+ collider with design luminosity of $1 \times 10^{33} \text{cm}^{-2} \text{s}^{-1}$ in 1-2.1 GeV and a SR source of 2.5 GeV, 250 mA.
- Significant progress has been made since the project started construction in the beginning of 2004;
- The success of the initial commissioning and early operation encourage us to go ahead;
- There is still a long way to go before taking about the full success.
- The success will of enable us for the future projects, such as CSNS, XFEL and ILC.
- The challenges and physical prospects of the BEPCII call for further cooperation Asia- & World-wide.

Thank You

Institute of High Energy Physics

Jan. 31, 2007, APAC2007

RRCAT, Indore, India



Image © 2007 NASA
© 2007 Europa Technologies

©2005 Google

Pointer: 41°34'02.82" N 110°38'52.20" E

Streaming ||||| 100%

Eve alt 9792.95 mi