

Low Energy RHIC electron Cooling (LEReC):

Cooling commissioning results of first RF-based electron cooler

A.V. Fedotov, Z. Altinbas, M. Blaskiewicz, M. Brennan, D. Bruno, C. Brutus, M. Costanzo, A. Drees, W. Fischer, J. Fite, M. Gaowei, D. Gassner, X. Gu, J. Halinski, K. Hamdi, L. Hammons, T. Hayes, R. Hulsart, P. Inacker, J. Jamilkowski, Y. Jing, J. Kewisch, P. Kankiya, D. Kayran, R. Lehn, C.J. Liaw, C. Liu, J. Ma, G. Mahler, M. Mapes, A. Marusic, K. Mernick, C. Mi, R. Michnoff, T. Miller, M. Minty, S. Nayak, L. Nguyen, M. Paniccia, I. Pinayev, S. Polizzo, V. Ptitsyn, T. Rao, G. Robert-Demolaize, T. Roser, J. Sandberg, V. Schoefer, C. Schultheiss, S. Seletskiy, F. Severino, T. Shrey, L. Smart, K. Smith, H. Song, A. Sukhanov, R. Than, P. Thieberger, S. Trabocchi, J. Tuozzolo, P. Wanderer, E. Wang, G. Wang, D. Weiss, B. Xiao, T. Xin, W. Xu, A. Zaltsman, H. Zhao, Z. Zhao

COOL19, Novosibirsk, Russia
September 23-27, 2019

BROOKHAVEN
NATIONAL LABORATORY



LEReC Project Overview

LEReC is world first electron cooler based on the RF acceleration of bunched electron beam


All key elements and experimental demonstrations required for this new approach were successfully achieved:

- ☐ **Building and commissioning of new state of the art electron accelerator ✓**
- ☐ **Produce electron bunches with beam quality suitable for cooling ✓**
- ☐ **RF acceleration and transport maintaining required beam quality ✓**
- ☐ **Achieve required beam parameters in cooling sections ✓**
- ☐ **Commissioning of bunched electron beam cooling ✓**
- ☐ **Commissioning of electron cooling in a collider ✓**


LEReC project timeline

May 2015:	LEReC project approved for construction
December 2016:	DC gun installed and successfully conditioned in RHIC tunnel
February 2017:	Gun test beamline installed
April-Aug., 2017:	Gun tests with beam
July-Dec., 2017:	Installation of full LEReC accelerator
Jan.-Feb., 2018:	Systems commissioning (RF, SRF, Cryogenics, Instrumentation, Controls, etc.)
March-Sept. 2018:	Commissioning of full LEReC accelerator with e-beam
September 2018:	All project Key Performance Parameters achieved
Oct.-Dec., 2018:	Scheduled upgrades and modifications
Jan.-Feb., 2019:	Restart operation with electron beam
March 2019:	Start commissioning with Au ion beams
April 2019:	First cooling demonstration. Cooling in both RHIC rings using e-bunches at 76kHz frequency.
May 2019:	Simultaneous cooling of all ion bunches with high-current 9MHz CW e-beam
June 2019:	Cooling optimization at 1.6MeV, cooling of beams in collisions (3.85GeV/n ions)
July 2019:	Cooling commissioned at higher electron energy of 2MeV (4.6GeV/n ions)

RHIC @ BNL, Long Island, New York




LEReC inside RHIC tunnel at Interaction Region @ 2 o'clock (IR2)



LEReC Accelerator

(100 meters of beamlines with the DC Gun, high-power fiber laser, 5 RF systems, including one SRF, many magnets and instrumentation)



LEReC: non-magnetized electron cooling

non-magnetized
friction force:

$$\vec{F} = -\frac{4\pi n_e e^4 Z^2}{m} \int \ln\left(\frac{\rho_{\max}}{\rho_{\min}}\right) \frac{\vec{V} - \vec{v}_e}{|\vec{V} - \vec{v}_e|^3} f(v_e) d^3 v_e$$

asymptotic for $v_{ion} < \Delta_e$:

- Non-magnetized cooling:

Very strong dependence on relative angles between electrons and ions.

- Requires strict control of both transverse angular spread and energy spread of electrons in the cooling section.

- LEReC: need to keep total contribution (including from emittance, space charge, remnant magnetic fields, etc.) below 150 μrad .

$$\vec{F} = -\frac{4\pi Z^2 e^4 n_e L}{m} \frac{\vec{v}_i}{\Delta_e^3}$$

$$\vec{F} = -\frac{4\pi Z^2 e^4 n_e L}{m} \frac{\vec{v}_i}{\beta^3 c^3 ((\gamma\theta)^2 + \sigma_p^2)^{3/2}}$$

Requirement on electron angles:
For $\gamma=4.1$: $\sigma_p=5\text{e-}4$; $\theta < 150 \mu\text{rad}$

LEReC electron beam parameters

Two energies commissioned ✓

Electron beam requirement for cooling			
Kinetic energy, MeV	1.6	2	2.6
Cooling section length, m	20	20	20
Electron bunch (704MHz) charge, pC	130	170	200
Effective charge used for cooling	100	130	150
Bunches per macrobunch (9 MHz)	30	30	24-30
Charge in macrobunch, nC	4	5	5-6
RMS normalized emittance, μm	< 2.5	< 2.5	< 2.5
Average current, mA	36	47	45-55
RMS energy spread	< 5e-4	< 5e-4	< 5e-4
RMS angular spread	<150 μrad	<150 μrad	<150 μrad

LEReC bunched electron beam cooling

- In order to be accelerated to high energy by the RF cavities electron beam has to be bunched.
- Bunches are generated by illuminating a photocathode inside the high-voltage Gun with green light laser (high-brightness in 3D: both emittances and energy spread). Electron beam properties resulting from acceleration of bunched beam are different from those obtained in standard DC beam coolers.
- The 704MHz high-power fiber laser produces required modulations to overlap ion bunches at 9MHz frequency with laser pulse temporal profile shaping using crystal stacking.
- RF gymnastics (several RF cavities) is employed to accelerate electron beam and to achieve energy spread required for cooling. Electron beams of required quality are delivered to cooling sections.
- Electron bunches overlap only small portion of ion bunch. All ion amplitudes are cooled as a result of synchrotron oscillations of ions.

LEReC beam structure in cooling section

Ions structure:

120 bunches

$f_{\text{rep}} = 120 \times 75.8347 \text{ kHz} = 9.1 \text{ MHz}$

$N_{\text{ion}} = 5e8$, $I_{\text{peak}} = 0.24 \text{ A}$


Rms length = 3.2 m

Electrons:


$f_{\text{SRF}} = 703.5 \text{ MHz}$

$Q_e = 100 \text{ pC}$, $I_{\text{peak}} = 0.4 \text{ A}$


Rms length = 3 cm



9 MHz bunch structure



Electron Macro-bunch



Electron beam transport

The use of RF-based approach requires special considerations:

Beam transport of electron bunches without significant degradation of emittance and energy spread, especially at low energies.

Impedance and wakefields from beam transport elements:

Accurate simulations of the wake fields including diagnostics elements showed that electron beam is very sensitive to the wake fields. Many instrumentation devices were redesigned to minimize effect of the wake fields. The dominant contribution comes from the RF cavities. The 704 MHz and 2.1GHz warm RF cavities had to be redesigned to minimize effects of the HOMs.

Longitudinal space charge:

Requires stretching electron beam bunches to keep energy spread growth to an acceptable level. Warm RF cavities are used for energy spread correction.

Transverse space charge:






Correction solenoids in the cooling section are used to keep transverse angular spread to a required level.

Strict control of electron angles in cooling sections:


Cooling sections are covered by several layers of Mu-metal shielding.

LEReC Critical Technical Systems


1. High-voltage photocathode electron gun
2. High-power fiber laser, transport and stabilization
3. Cathode production deposition and delivery systems
4. 704 MHz SRF Booster cavity
5. 2.1 GHz and 704 MHz warm RF cavities




LEReC construction
started in 2016




LEReC Gun test beamline (2017)



Full LEReC installation (October 2017)



LEReC cooling sections fully installed (2018)



Attainment of “cold” electron beam suitable for cooling

- LEReC is based on the state-of-the-art accelerator physics and technology:
- Photocathodes: production and sophisticated delivery systems
- High power fiber laser, transport and stabilization systems
- Laser beam shaping to produce electron bunches of required quality
- Operation of DC gun at high voltages (around 400kV) with high charge and high average current
- RF gymnastics using several RF cavities and stability control
- Energy stability and control
- Instrumentation and controls

Transverse phase-space measurements of electron beam

RF Diagnostic Beamline

COOLING
in Yellow RHIC ring

704 MHz Cu
Deflector Cavity

704 MHz
Cu Cavity

Transport
Beamline

9 MHz;
Cu Cav

Merger
Beamline

RHIC TRIPLET

Extraction beam
line

High-Power Beam
Dump

180°
Bending
Magnet

COOLING
in Blue RHIC ring


YELLOW

BLUE

Bunch charge 75 pC


Movable slit and downstream
beam profile monitors are
installed at the beginning of
each cooling section.

Achieved rms normalized emittances
in cooling sections $< 2 \mu\text{m}$
(requirement: $2.5 \mu\text{m}$)





Longitudinal phase-space measurement of electron beam

704MHz deflecting cavity





- First dogleg merger dipole is off
- Beam goes to RF diagnostic line
- 20 degree dipole produces dispersion
- 704MHz RF deflecting cavity produces time dependent vertical kick


1 macro-bunch of electrons (total charge 3nC)



6 macro-bunches, 3 nC each.




LEReC: First observation of electron cooling using bunched electron beam, April 5, 2019



Ion bunch #4 which is not being cooled

Ion bunch #2 is being cooled


Energy of electrons and ions matched




In 76kHz mode, subsequent electron macro-bunches have lower energy due to beam loading in RF cavities (can match energy/cool effectively single ion bunch).

First cooling in Blue RHIC Ring (April 19, 2019)


- After RHIC lattice for Au ions and good electron beam optics for Blue cooling section was established, cooling of ions in Blue RHIC Ring was achieved.








Longitudinal profiles of six ion bunches



Simultaneous cooling in both Yellow and Blue RHIC rings using the same electron beam (76kHz mode, 6 ion bunches: bunch #1 is being cooled; bunch #6 does not see electrons)





Longitudinal bunch profiles




High-current CW electron beam operation and cooling of many ions bunches simultaneously


- To proceed from cooling single ion bunch using 76kHz electron beam to cooling of many ion bunches required establishing high-current 9MHz electron beam operation through both cooling sections all the way to high-power beam dump.



Cooling of hadron beams under collisions (RHIC store with 111x111 Au ion bunches) @ 3.85GeV/n using 1.6MeV **high-current 9MHz CW electron beam**






Electron cooling in a collider:
Cooling of hadron beams in collisions



6-D cooling of a 111x111 bunch RHIC store at 3.85 GeV
(1.6 MeV electrons, 9 MHz CW current of 15mA).

July 2019: Electron accelerator was commissioned at one more energy of 2 MeV and cooling of ions at 4.6GeV/n was established

electron beam parameters



LEReC roadmap to cooling


- Production of 3-D high-brightness electron beams ✓
- RF acceleration and transport of electron bunches maintaining “cold” beam ✓
- Control of various contributions to electron angles in the cooling section to a very low level required for cooling ✓
- Energy matching of electron and ion beams ✓
- First electron cooling demonstration in longitudinal plane ✓
- Establishing cooling in 6-D ✓
- Matched electron and ion energy in both Yellow and Blue RHIC rings ✓
- Achieved cooling in both Yellow and Blue Rings simultaneously using the same electron beam ✓
- Demonstrated longitudinal and transverse cooling of several ion bunches (high-current 9MHz CW e-beam operation) simultaneously ✓
- Cooling ion bunches in collisions, in both Yellow and Blue RHIC rings using CW electron beam ✓

Observed issues and limitations


- With no magnetic field in the cooling sections, focusing of electrons by ions was significant. Adjusting the electron beam optics to take this into account was challenging.
- Different focusing on electron bunches distributed at different longitudinal slices of ion bunch.
- Using bunched electron beam for cooling at such a low energy led to emittance growth of ions due to modulated focusing from the electrons (called “heating”). Such heating effects were reduced, but not eliminated, by a proper choice of ion beta-function in the cooling section and of a working point. However, to cope with the heating effects, which had strong dependence on electron beam density, we had to operate at electron currents lower than design values.
- Ion lifetime limitations at low energy in RHIC: physical aperture, dynamics aperture, beam-beam, space charge and IBS.

Effects of electrons on ions: “heating” (March 2019)

- Even before cooling was established we observed strong “heating” effects of electrons on ions (which are space-charge beam-beam kicks from e-beam on ions).





Electrons and ions energies are NOT matched



- These “heating” effects were reduced by going to smaller ion beta-function in cooling section and by finding better working point in tune space.


Potential benefits from cooling

- Cooled bunch is kept shorter, more useful events within trigger window
- Minimize ion beam de-bunching and losses from the RF bucket
- Peak current significantly higher for cooled bunch
- Allows longer stores
- Transverse cooling can help with reduction of beta*



Summary

- World's first electron cooling of hadron beams based on RF acceleration of electron bunches was successfully demonstrated. Such cooling approach is new and opens the possibility of using this technique to high beam energies.
- Electron cooling using electron beam without any magnetization on the cathode or cooling section, “non-magnetized” cooling, was demonstrated (all previous coolers used magnetization on the cathode).
- First electron cooling in a collider (cooling of ion beams in collisions with various effects impacting beam lifetime)) was achieved by successfully cooling 111 ion bunches in both RHIC rings.
- Cooling was commissioned at electron energy of 1.6MeV (ion energy 3.85GeV/n) and at 2MeV (ion energy of 4.6GeV/n).
- The next step will be to maximize collision rates with cooling in next year's RHIC low-energy collisions.



Acknowledgement

LEReC project greatly benefits from help and expertise of many people from various groups of the Collider-Accelerator and other Departments of the BNL.

As well as FNAL, ANL, JLAB and Cornell University.

Thank you!

A. Fedotov et al., "First electron cooling of hadron beams using a bunched electron beam", NAPAC2019, Lansing, Michigan, USA, 2019

D. Kayran et al., "Commissioning of the electron accelerator LEReC for bunched beam cooling", NAPAC2019, Lansing, Michigan, USA, 2019

S. Seletskiy et al., "Precise beam velocity matching for the experimental demonstration of ion cooling with a bunched electron beam", NAPAC2019, Lansing, Michigan, USA, 2019

L. Nguyen et al., "Active pointing stabilization techniques applied to the Low Energy RHIC Electron Cooling laser transport at BNL", NAPAC2019, Lansing, Michigan, USA, 2019

P. Inacker-Mix et al., "Design of the 2-stage laser transport for the LEReC system", NAPAC2019, Lansing, Michigan, USA, 2019

D. Kayran et al., "First results from commissioning of low energy RHIC electron cooler (LEReC)", IPAC2019, Melbourne, Australia, 2019

M. Gaowei et al., "Bi-alkali Antimonide Photocathodes for LEReC", IPAC2019, Melbourne, Australia, 2019

D. Kayran et al., "LEReC Photocathode DC Gun Beam Test Results", IPAC18, Vancouver, Canada, 2018

D. Kayran et al., "First Results of Commissioning of DC Gun for LEReC", ERL17, CERN, Switzerland, 2017

S. Seletskiy et al., "Status of the BNL LEReC Machine Protection System", IBIC17, Grand Rapids, USA, 2017

T. Miller et al., "Low Field NMR Probe Commissioning for LEReC Spectrometer", IBIC17, Grand Rapids, USA, 2017

J. Kewisch et al., "Tracking of Electrons Created at Wrong RF Phases in LEReC", IPAC17, Copenhagen, Denmark, 2017

S. Seletskiy et al., "Dependence of LEReC energy spread on laser modulation", IPAC17, Copenhagen, Denmark, 2017

S. Seletskiy et al., "Alignment of Electron and Ion Beam trajectories in LEReC", IPAC17, Copenhagen, Denmark, 2017

Z. Zhao et al., "Generation of 180 W average green power from fiber laser", Optics Express 8138, Vol. 25, No. 7, 2017

A. Fedotov et al., "Accelerator Physics Design Requirements and Challenges of LEReC", NAPAC16, Chicago, USA, 2016

J. Kewisch et al., "Beam Optics for LEReC", NAPAC16, Chicago, USA, 2016

D. Kayran et al., "DC Photogun Test for LEReC", NAPAC16, Chicago, USA, 2016

S. Seletskiy et al., "Magnetic Shielding of LEReC Cooling Section", NAPAC16, Chicago, USA, 2016

S. Seletskiy et al., "Absolute Energy Measurement of LEReC Electron Beam", NAPAC16, Chicago, USA, 2016

M. Blaskiewicz, "Emittance Growth from Modulated Focusing in Bunched Beam Cooling", NAPAC16, Chicago, USA, 2016

T. Miller et al., "LEReC Instrumentation Design and Construction", IBIC16, Barcelona, Spain, 2016

Z. Sorrell et al., "Beam Position Monitors for LEReC", IBIC16, Barcelona, Spain, 2016

S. Seletskiy et al., "Conceptual Design of LEReC Fast MPS", IBIC16, Barcelona, Spain, 2016

S. Seletskiy et al., "Study of YAG Exposure Time for LEReC RF Diagnostic Beamline", IBIC16, Barcelona, Spain, 2016

J.C. Brutus et al., "Mechanical Design of Normal Conducting RF cavities of LEReC", IPAC16, Busan, Korea, 2016

F. Carlier et al., "Radiation Recombination Detection for LEReC", IPAC16, Busan, Korea, 2016

Binping Xiao et al., "RF design of Normal Conducting cavities for LEReC", IPAC16, Busan, Korea, 2016

Binping Xiao et al., "HOM Consideration of 704MHz and 2.1GHz cavities for LEReC", IPAC16, Busan, Korea, 2016

Details can be found
in recent LEReC
publications.