


# Commissioning Results of Beam Diagnostics for the PETRA III Light Source

K. Balewski et al.

# Outline

- PETRA III – Introduction
- Commissioning
  - Transfer line
  - Storage ring
- Commissioning of
  - Monitoring the position of BPMs
  - Temperature sensors
- Outlook
  - Emittance measurement

# PETRA III



## Parameters:

- circumference: **2304 m**
- energy: **6 GeV**
  
- emittance: **1 nmrad**
- emittance coup.: **1% (10 pmrad!)**
  
- current: **100 (200) mA**
- # bunches **40 / 960**
  
- straight sections: **9**
- undulators: **14**
- undulator length: **2, 5, 10 (20) m**
  
- supplement to X-FEL
- → **cost effective!**

## Damping wiggler sections



PETRA III:

# Conversion of the former storage ring PETRA II into a light source



**C=2304m !!!**



# Transferline - Diagnostics




# Transferline



First beam through transferline on 24.03

Optics about correct, i.e. measured profiles agree with theoretical within 10%


# Transfer line BPM's & scrapers



Detailed information on these BPMs  
→ F. Schmidt-Föhre MOPD20




25.05.2009

PETRA III Commissioning



Balewski - MPE

# Different BPM's in PETRA III



## BPM Readout electronic

Extensive tests of Libera Electron done:

- ✓ Slow orbit and TbT resolution
- ✓ Fast data readout for fast orbit feedback.
- ✓ Temperature dependence
- ✓ ...
  - Bunch pattern and current dependence (however, not so important for top-up operation)




=> LIBERA Brilliance  
(improved specs.)

240 pieces arrived after less than 1 year. Few rejected, minor problems




# Commissioning (1)

Beam to first half of the machine on April 3 and up to the new octant  
On April 7



BPM electronics working well right from the start (\*)




Figure shows the sum signal of BPM's



(\*) Detailed information on  
BPM electronic commissioning  
→ I. Krouptchenkov TUPD03



# Commissioning (2)

First turns on *April 12* after two quads with wrong polarity were identified and correctly powered and optics was locally changed to circumvent a problem with a quad that tripped because the cooling water was blocked



Beam was stored on *April 13*  
(one bunch with  $20 \mu\text{A}$  i.e. about  $10^9 \text{ e}^+$ )  
RF – phase right and  
orbit empirically corrected in the new octant

# Rough check of optics determination of integer Part of Tune




Fitted response agrees very well  
 In the horizontal plane with theory  
 Whereas there are phase errors in  
 The vertical plane close to the new  
 octant


# Optics ...

- tunes measured and set close to design  $Q_x \approx 0.2 & Q_y \approx 0.3$
- measured and corrected chromaticity
- changed the dipole field in old octants with respect to new octant (probably to much)

## Tune measurement via noise excitation




On Axis injection eff. Close to 100 %  
up to 200  $\mu$ A perpulse




# Accumulation on April 22

## Single bunch accumulation



Multibunch accumulation (40 bunches)  
After correction of kicker timing




# Protection of BPM's & electronics



- **BPM electronic:**
  - High Peak current (bunchlength 3.5 mm without wigglers)  
→ high peak Voltage  
potential danger for electronics  
→ limit single bunch current to  $\leq 1$  mA  
& attenuators equivalent to  $U_{peak} \leq 80$  V @ 3mm COD
- **BPM's: HOM heating ( $P_{trans} \leq 5W$ ;  $k_{loss} = 46$  V/nC)**
  - Calculation (transient heating)
$$I_{tot} \leq \sqrt{N} \cdot 3.6\text{ mA}$$
  - Temperature measurements at certain BPMs in preparation for next phase

## Transversal Multibunch Feedback

500 MHz  
 Stripline  
 BPM (2)





2 Kickers / Plane; BW>62.5MHz





The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)




2 Kickers / Plane; BW>62.5MHz





The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)




2 Kickers / Plane; BW>62.5MHz




The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)





2 Kickers / Plane; BW>62.5MHz





The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)



2 Kickers / Plane; BW>62.5MHz



RF Front-End,  
1 kHz - 62.5 MHz





Power Amplifier,  
9 kHz - 250 MHz  
4 \* 250 W




The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)



2 Kickers / Plane; BW>62.5MHz



Signal Processor  
Board 130 MS/s

RF Front-End,  
1 kHz - 62.5 MHz



FB FPGA DSP  
Elektronics



Power Amplifier,  
9 kHz - 250 MHz  
4 \* 250 W




The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

## Transversal Multibunch Feedback

500 MHz  
Stripline  
BPM (2)



2 Kickers / Plane; BW>62.5MHz



Signal Processor  
Board 130 MS/s

RF Front-End,  
1 kHz - 62.5 MHz



RF Frontend  
Elektronics

FB FPGA DSP  
Elektronics

LAN

Power Amplifier,  
9 kHz - 250 MHz  
4 \* 250 W



The required minimum bandwidth is 62.5MHz determined by the shortest distance between bunches being 8 ns. Upgrade to 2 ns (250 MHz) possible

# Multibunch feedback




'old' PII transverse feedback in  
Operation on April 27

Maximum current:  
20 mA (1/5 of design) in 40 bunches


Tune measurement with FB

$$H(\omega) = \frac{1}{\omega_0^2 - \omega^2}; \quad G(\omega) = i\omega\Gamma;$$

$$DS(\omega) = \frac{1}{\omega_0^2 - \omega^2 + i\omega\Gamma} \xi + \frac{\omega_0^2 - \omega^2}{\omega_0^2 - \omega^2 + i\omega\Gamma} \phi_{DN}$$




# Centre frequency




# Dispersion


## Horizontal dispersion




The distortion of the  $D_x$  is  
due to a wrong relation between  
The two dipol fields and kicks  
That produce dispersion



## Vertical dispersion



# Test of BBA



First test of BBA

Monitor NOR 55 Quad QA1 NOR 56

First picture:

raw data x  
raw data y

Second picture:

only sensitive BPM

Third picture:

calc. offset of NOR55

Forth picture:

with data of all other BPM's


$$x = (+0.42 \pm 0.02) \text{ mm ,}$$

$$y = (-0.12 \pm 0.02) \text{ mm}$$

# ORM Test

The ORM procedure has  
Been tested with a few  
Horizontal or vertical  
Corrector magnets  
Respectively.

The data is currently investigated




# Damping wiggler sections safe removal of radiation power

Up to 400 kW of SR-power has to be removed;  
12 absorbers installed and power has to be  
distributed correctly otherwise absorbers  
will be damaged




sensors control absorber temperature at critical  
positions




Regular cells in PETRA North



# Temperature sensors



# Temperature Sensors



Temperature thresholds  
For certain sensors

If temperature exceeds  
Threshold warning to  
Machine Protection System  
And if necessary beam is  
Dumped


Detailed information on MPS  
→ T. Lensch, M. Werner  
TUPD25

## HF-MoMo (Movement Monitor)


Near the undulators the movement of the BPMs (relative to ground) will be measured with a resolution of better 1  $\mu\text{m}$ . Different **encoder systems** were studied

- **Test of a commercial system in PETRA II failed:**  
**radiation problems, high failure rate.**

- Choice of in-house wire-systems HF-MoMo
- 145 MHz signal on  $\lambda/4$  antenna picked up by 4 stiplines. Readout BPM like, bandwidth 1Hz.
- Gap 8x8mm, linear 2x2 mm.



ioning




Balewski - MPE

## HF-MoMo (Movement Monitor)


Near the undulators the movement of the BPMs (relative to ground) will be measured with a resolution of better 1  $\mu\text{m}$ . Different **encoder systems** were studied

- **Test of a commercial system in PETRA II failed:**  
**radiation problems, high failure rate.**

- Choice of in-house wire-systems HF-MoMo
- 145 MHz signal on  $\lambda/4$  antenna picked up by 4 stiplines. Readout BPM like, bandwidth 1Hz.
- Gap 8x8mm, linear 2x2 mm.



ioning






Balewski - MPE

## HF-MoMo (Movement Monitor)


Near the undulators the movement of the BPMs (relative to ground) will be measured with a resolution of better 1  $\mu\text{m}$ . Different **encoder systems** were studied

- **Test of a commercial system in PETRA II failed:**  
**radiation problems, high failure rate.**

- Choice of in-house wire-systems HF-MoMo
- 145 MHz signal on  $\lambda/4$  antenna picked up by 4 stiplines. Readout BPM like, bandwidth 1Hz.
- Gap 8x8mm, linear 2x2 mm.



# HF- MOMO Measurements



# Emittance Diagnostics: X-ray Beamline

- principle

20 keV synchrotron radiation from bending magnet to image beam spot onto high resolution CCD camera system



- X-ray imaging optics

Imaging via 2 interchangeable x-ray optical systems


- ▶ Pinhole camera (standard operation)  
pinhole  $\varnothing$  20  $\mu\text{m}$ , resolution  $\approx$  20  $\mu\text{m}$
- ▶ Compound refractive lenses (high resolution)  
31 lenses, material: Be  
resolution  $\approx$  2  $\mu\text{m}$

- status

installation finished  
commissioning in next phase

25.05.2009

PETRA III Commissioning



# Emittance Diagnostics: X-ray Beamline

## ● principle

20 keV synchrotron radiation from bending magnet to image beam spot onto high resolution CCD camera system



## ● X-ray imaging optics

Imaging via 2 interchangeable x-ray optical systems

- ▶ Pinhole camera (standard operation)  
pinhole  $\varnothing 20 \mu\text{m}$ , resolution  $\approx 20 \mu\text{m}$
- ▶ Compound refractive lenses (high resolution)  
31 lenses, material: Be  
resolution  $\approx 2 \mu\text{m}$

## ● status

installation finished  
commissioning in next phase

25.05.2009

PETRA III Commissioning



# Emittance Diagnostics: X-ray Beamline

## ● principle

20 keV synchrotron radiation from bending magnet onto high resolution imaging system



## ● X-ray imaging

Imaging via 2 x-ray optical systems

- ▶ Pinhole camera:  
pinhole Ø 0.5 mm
- ▶ Compound lens:  
31 lenses, 100 nm resolution

## ● status

installation finished  
commissioning in next phase

25.05.2009



PETRA III Commissioning




# Bunch Length Diagnostics: optical Beamlne

## Principle

visible synchrotron radiation from bending magnet



## Streak Camera System



25.05.2009

PETRA III Commissioning

Balewski - MPE

28

# Bunch Length Diagnostics: optical Beamlne

## Principle

visible synchrotron radiation  
bending magnet



## Streak Camera




25.05.2009

PETRA III Commissioning

Balewski - MPE

28


# Laser Wire-Scanner



Laser-wire scanner optical setup at Petra SWL 32.  
Vertical and horizontal scans of the Laser versus  
the beam are possible

**Puls length 100 ps**  
**Scan within tens of seconds**

A sample of laser spot size measurement at focus. A knife-edge scan is differentiated to obtain a gaussian. The laser-wire diameter is below 10um which is verified by in-situ calibrations.



# Summary

- The first commissioning phase of PETRA III went smoothly and very fast.
  - No major problem was encountered.
  - Detailed investigation of the machine will be part of the next phase.
- 
- The success of the first phase is certainly due to sufficient diagnostics that worked well right from the beginning.
  - At this point also the support and commitment of those who took part in the commissioning is greatly acknowledged.

**Thank you  
for your attention**