

# Diamond Light Source: Overview and Status


*Richard P. Walker  
on behalf of the Diamond Machine Project Team*



- 1. Introduction**
- 2. Machine description**
- 3. Commissioning**
- 4. Status and future plan**


**Diamond is a new Medium Energy, 3<sup>rd</sup> Generation Light Source, to replace the SRS – the world's first purpose built high energy synchrotron radiation source (now 25 years old)**

**The largest accelerator project, and the largest scientific investment in the UK for over 30 years.**



mond

# Diamond – Main Parameters



nominal, non-zero dispersion lattice

Energy	3 GeV
Circumference	561.6 m
No. cells	24
Symmetry	6
Straight sections	6 x 8m, 18 x 5m
Insertion devices	4 x 8m, 18 x 5m
Beam current	300 mA ( <b>500 mA</b> )
Emittance (h, v)	2.7, 0.03 nm rad
Lifetime	> 10 h
Min. ID gap	7 mm ( <b>5 mm</b> )
Beam size (h, v)	80, 8 $\mu$ m
Beam divergence (h, v) (at centre of 5 m ID)	35, 3 $\mu$ rad



# Located at the Rutherford Appleton Laboratory, on the Harwell Science and Innovation Campus:



# Diamond Project Evolution

- 1993** Woolfson Review: SRS to be replaced by a new medium energy machine
- 1997** Feasibility Study (“Red Book”) published  
3 GeV, 16 cells, 345 m circumference, 14 nm rads
- 1998** Wellcome Trust joins as partner
- Mar. '00** Decision to build Diamond at Rutherford Appleton Lab.
- Oct. '00** 3 GeV, 24 cells, 560 m circumference design approved
- Apr. '02** Joint Venture Agreement signed (UK Govt./WellcomeTrust)  
Diamond Light Source Ltd. established  
Design Specification Report (“Green Book”) completed by CCLRC
- Jan. '07** Start of Operations

# The Diamond Machine

100 MeV Linac

3 GeV Booster

$C = 158.4 \text{ m}$

3 GeV Storage Ring

$C = 562.6 \text{ m}$

Experimental Hall  
and Beamlines


office  
building

technical  
plant

peripheral  
labs. and  
offices

future long  
beamlines


235 m







# Linac

- 100 MeV Linac of the DESY S-band Linear Collider Type II design, supplied "turn-key" by Accel Instruments.  
(DLS supplied diagnostics, vacuum and control system components, and beam analysis software)
- thermionic gun; short ( $< 1$  ns) and long pulse ( $0.1$ - $1$   $\mu$ s) modes
- 500 MHz sub-harmonic pre-buncher, 3 GHz primary buncher, 3 GHz final buncher
- two 5.2 m constant gradient accelerating sections fed by independent klystrons



# Booster

Energy	3 GeV
Circumference	158.4 m
Emittance	141 nm rad
Repetition rate	5 Hz
Lattice	FODO, missing dipole





# Storage Ring




Richard P. Walker

EPAC'06, Edinburgh, June 29<sup>th</sup> 2006



# Girders



Magnets and vacuum chambers mounted and pre-aligned on precisely machined girders, 3 per cell

Up to 6 m long and 17 T in weight.

mover system allows remote alignment possibility






# Power Supplies

## Standardisation

- minimum no. of different types
- all 1038 power supplies use the same (PSI type) digital controller and ADC cards.

## Maintainability and Reliability

- plug-in modules
- reduced component count
- redundancy of 24 V control power and power modules



**DSP-controller**  
incl. PWM generator





# RF System



**Supercon-  
ducting  
cavities (2)**





**IOT-based 300 kW  
amplifiers**

**Liquid He plant**




Richard P. Walker

**Both cavities conditioned above the nominal 2 MV accelerating voltage, meeting the specified  $Q_0$ :**



# Digital Beam Position Monitor Electronics


(Libera, integrated in EPICS)



**Resolution in 2 kHz Bandwidth:**  
 **$< 1 \mu\text{m}$  at  $> 10 \text{ mA}$**








**Turn-by-turn (1 MHz b.w.):**  
 **$\sim 100 \mu\text{m}$  at  $1 \text{ mA}$**

**Beam Current Dependence**  
 **$< 1 \mu\text{m}$  at  $60\text{-}300 \text{ mA}$**





provides many different data streams, simultaneously




EPAC'06, Edinburgh, June 29<sup>th</sup> 2006

# Phase I Insertion Devices





Beam-line	ID	Type	Status
I02	U23	In-vacuum	ready for vacuum assembly
I03	U21	In-vacuum	under bake-out
I04	U23	In-vacuum	<b>installed</b>
I06	HU64	APPLE-II	ready for installation
I15	SCW	Superconducting Multipole Wiggler	<b>installed</b>
I16	U27	In-vacuum	ready for vacuum assembly
I18	U27	In-vacuum	under assembly


# U23 trajectory and phase errors



$g = 5 \text{ mm}$





$g = 7 \text{ mm}$






# U23 field Integrals



— Vertical  
— Horizontal





Richard P. Walker



# Superconducting Wiggler

Field	3.5 T
Period	60 mm
No. full poles	45
Vertical aperture	10 mm



*SCW under test on the experimental hall floor*


6, Edinburgh, June 29<sup>th</sup> 2006



# ID Installation Status



5m long narrow gap vessel for APPLEII undulator



in-vacuum undulator



superconducting wiggler

Richard P. Walker



# Machine Commissioning: Linac



**Installation complete: Aug. 3<sup>rd</sup> 2005**

**1<sup>st</sup> beam from gun: Aug. 31<sup>st</sup> 2005**

**1<sup>st</sup> 100 MeV beam: Sep. 7<sup>th</sup> 2005**


**Acceptance test  
complete: mid-Oct. 2005**




Richard P. Walker



# Linac Diagnostics




effect of the sub-harmonic pre-buncher  
(wall current monitor and 10 GHz  
oscilloscope)




energy spread measurement

Richard P. Walker

EPAC'06, Edinburgh, June 29<sup>th</sup>



emittance measurement:




# Linac Performance

Parameter	Specification	Single bunch	Multi bunch
Energy [MeV]	> 100	103	103
x norm. emittance [ $\pi$ .mm.mrad]	< 50	18	16
y norm. emittance [ $\pi$ .mm.mrad]	< 50	27	11
Charge [nC]	> 1.5 / 3.0	2.1	4.8
Pulse width [ns]	< 1	~ 0.2 fwhm	~ 0.2 fwhm
Jitter [ps]	< 100	11	11
Energy variation [%]	< 0.25	0.05 rms, 0.21 full	0.05 rms, 0.16 full
Energy spread [%]	< 0.5	< 0.2	0.2

(Same at 1 Hz or 5 Hz)




# Booster Commissioning




**First beam in the Booster  
(100 MeV, no RF)**


**Dec. 21<sup>st</sup> 2005**



Burgh, June 29<sup>th</sup> 2006





**Feb. 13<sup>th</sup>:  
Beam surviving for  
200 ms between  
injections at 100 MeV  
(RF on)**



**1/e lifetime = 1 s**

## Closed orbit


within  $\pm 5$  mm,  
with no correctors  
powered




First orbit correction  
Feb. 17<sup>th</sup>

within  $\pm 1$  mm





**First acceleration to  
700 MeV, March 10<sup>th</sup>**



**First extraction at  
700 MeV, April 4<sup>th</sup>**

29<sup>th</sup> 2006




# Why 700 MeV ?

**Water cooling system  
(part of the Buildings  
contract) not available.**

**Temporary systems set up  
for Linac, Booster RF,  
Storage ring RF, but not  
initially for the magnets.**


# Booster optimisation (April '06)



2 mA typical, with ~ 70 % transfer efficiency from before injection to after extraction.




Tunes corrected through the ramp






# Optics measurements


Predicted  $\beta$ -beat from LOCO analysis  
within  $\pm 15\%$  Horiz.,  $\pm 10\%$  Vert.:




Measured response matrix:



dispersion measurement:




# Storage Ring: Phase I Commissioning (700 MeV)



**May 3<sup>rd</sup>/4<sup>th</sup>:**

**First beam in the  
storage ring –  
immediately after  
the septum**




May 4<sup>th</sup>/5<sup>th</sup>:

First turn !

Correctors off

low intensity due to two  
quadrupoles with inverted  
polarity





## Celebrating the First Turn! – 03:00 May 5<sup>th</sup> 2006





Richard P. Walker


EPAC'06, Edinburgh, June 29<sup>th</sup> 2006




May 5<sup>th</sup>/6<sup>th</sup>: 4 turns



**May 6<sup>th</sup>/7<sup>th</sup>: 600 turns  
(sextupoles off, RF off)**




**May 19<sup>th</sup>/20<sup>th</sup>: 2000 turns  
(sextupoles on, RF off)**







**May 20<sup>th</sup>/21<sup>st</sup>:**  
**106,764 turns !**



**May 21<sup>st</sup>/22<sup>nd</sup>:**  
**0.4 mA, 70% injection efficiency**




# First stored beam ! ...



**0.5 hour lifetime  
at 0.5 mA**

But initially the beam did not accumulate ...




- believed to be due to differences between the kicker pulse shapes (which were not tuned for operation at 700 MeV)

then after an "optimisation procedure" .....






**> 2 mA accumulated**




# First Synchrotron Light !

- from the visible Synchrotron Light Monitor

First use of the streak camera:




500 ps





synchrotron  
oscillations  
at injection

3.5 ms





# Response matrix measurement




tunes generally  
within 0.4-0.5 of the  
model


## Closed orbit correction

Best achieved:  $\sigma_x = 1.3$  mm,  $\sigma_y = 0.9$  mm

- reasonable given the uncorrected girder and BPM positional errors



## Vacuum: first observations of photo-stimulated desorption



Average base pressure  $5 \times 10^{-10}$  mbar


Dynamic pressure  $1.5 \times 10^{-9}$  at 2 mA

Consistent with desorption rate of  $10^{-3}$  molecules/photon  
(as expected for a pre-baked, stainless steel system)

diamond




# Booster 3 GeV Commissioning (June '06)




- Started 3 GeV trials on June 7<sup>th</sup>
- First beam to 3 GeV on June 9<sup>th</sup>

linear ramp of rf power




# Tunes



Tunes constant to  
 $\Delta Q_x = 0.07$ ,  
 $\Delta Q_y = 0.05$

- without  
corrections to the  
sinusoidal ramps


## Closed orbit



Closed orbit can be corrected during the ramp, but is not needed.


After 400 MeV stays constant, within  $\pm 3$  mm.

Vertical position (mm)





## Extracted Beam at 3 GeV




$$\sigma_x = 1.5 \text{ mm}$$

$$\sigma_y = 0.11 \text{ mm}$$


in agreement with  
theory (2% coupling)

Booster is now ready to inject into the storage ring at 3 GeV.

Stability has however deteriorated, and has been linked in part to mains frequency variations ....which are being investigated



It should however improve after the World Cup !



**First observation of the effect of a major sporting event on accelerator operation ?**

# Summary and Future Plan

- **Phase I storage ring commissioning at 700 MeV has been a success:**
  - all systems operational
  - beam stored and accumulated
  - optics in reasonable agreement with theory
- **Booster commissioned at 3 GeV – ready for the next stage**
- **Installation of IDs and FEs in progress**
- **Storage ring commissioning will resume in September, when water cooling is expected to be available.**
- **Beamline commissioning in parallel during October-December**
- **Start of Operational Phase - first external users, assisting with beamline optimisation - as original target: **January 2007****

# Thanks to the Machine Construction and Commissioning Teams,



Richard P. Walker

EPAC'06, Edinburgh, June 29<sup>th</sup> 2006





**& thank you for your attention.**

