

OVERVIEW OF THE STATUS OF THE SOLEIL PROJECT

Content

- SOLEIL main characteristics
- Specificities and innovative aspects
- Commissioning progress
- Conclusions

Jean-Marc FILHOL
on behalf of the SOLEIL team

Commissioning team : A Nadji, JC Besson, P Brunelle, L Cassinari, ME Courpie, C Daveran, JC Denard, P Gros, C Herbeaux, JF Lamarre, MP Level, P Lebasque, A Lestrade, A Loulergue, A Madur, P Marchand, L Nadolski, R Nagaoka, B Pottin, JB Pruvost, F Ribero, MA. Tordeux

Operator team : R Cuoq, A Bence, P DaSilva, X Deletoille, D Pereira, G Roux, S Petit

Magnetism and Insertion Device group

RF Group, Linac Group, Diagnostic group

Vacuum group

Alignment group

Mechanical and engineering group : JL Marlats et al

Electronics and Computer Groups : P Betinelli, A Buteau et al.

Infrastructure group : P Eymard, S Mzah et al.

Safety group

- Electron energy : 2.75 GeV
- Extended spectral range :
From UV (5 eV) up to hard X-Rays (15 KeV)
- 3rd generation => Many insertion device beamlines
21 straight sections available (29% of ring circ.)
- High brilliance (10^{20}) in the soft X-ray range :
=> small emittance and high intensity
- **Best achievable beam position stability**

22 Beamlines approved by the Council + 2 beamlines to be defined:

16 on insertion devices and 6 on bending magnets

Spectral range equally shared :

50% below 1.3 keV and 50% above

Phase 1: 11 beamlines being built =>open to external Users in 2007

6 on insertion devices and 3 on bending magnets + 2 IR

Phase 2: 7 beamlines open to external Users in 2008

5 on insertion devices and 2 on bending magnets

+ 4 beamlines on ID open to external Users in 2009

5 Straight sections still free + 15 bending magnet beamports !

Storage Ring parameters

Energy	2.75 GeV
Circumference	354 m
Number and length of straight sections	4 x 12 m 12 x 7 m 8 x 3.6 m
Horizontal emittance	3.7 10 ⁻⁹ m.rad
Vertical emittance	37 10 ⁻¹² m.rad
Energy spread	1.16×10 ⁻³
Multibunch mode	500 mA
Lifetime	18 h
8 bunch (30 ps every 148 ns)	90 mA
Lifetime (10% coupling)	18 h

Horizontal tune Q_x :	18.2
Vertical tune Q_z :	10.3
Natural Chromaticities ξ_x/ξ_z :	-53/-23
Momentum compaction α_1 / α_2 :	$4.4 \cdot 10^{-4} / 4.5 \cdot 10^{-3}$


RF Frequency:	352.202 MHz
Harmonic number (max number of bunches)	416
Maximum RF Voltage:	4.8 MV
Energy loss per turn (with ID's):	1200 keV
Total radiation power loss (at 500 mA):	600 kW

Storage Ring Optical functions

24 Straight sections:

4	Long:	12 m
12	Medium:	7 m
8	Short:	3 m

One of the 4 super-periods



Sizes and divergences at Source points

Horizontal emittance 3.7 nm.rad

	BetaX m	EtaX m	H Size SigmaX μm	H Divergence Sigma XP μrad	Effective Emittance H
Short straight	17,8	0,285	388	14,5	5,61 nm.rad
Medium straight	4,0	0,133	182	30,5	5,56 nm.rad
Long straight	10,1	0,200	281	19,2	5,40 nm.rad
Dipole 4°	0,38	0,021	43	107,0	

Vertical emittance 37 pm.rad (1% coupling)

	BetaZ m		V Size SigmaZ μm	V Divergence SigmaZP μrad
Short straight	1,75		8,1	4,6
Medium straight	1,77		8,1	4,6
Long straight	8,01		17,3	2,2
Dipole 4°	16,01		24,5	2,1

The requirement due to the vertical beam size is $\sigma/10 \sim 1\mu\text{m}$

⇒ Site and building aspects

⇒ Storage Ring Girder design

⇒ Keep constant the heat load on optical components:

=> Topping-up

➤ Linac

➤ Booster

➤ Storage Ring Injection equipments

Building were designed for optimum position stability :

All potential sources of vibrations in a separate technical building :

All pumps for different cooling circuits + supported on damping material
Compressor for the cryogenic source

Synchrotron building :

Storage Ring and Experimental Hall isolated from the other parts of the building

Exp. Hall : => Air temperature regulated at $21\text{ °C} \pm 1.0\text{ °C}$

Storage Ring Tunnel : => Air temperature regulated at $21\text{ °C} \pm 0.1\text{ °C}$

 => Water cooling circuit regulated at $21\text{ °C} \pm 0.1\text{ °C}$

External perturbations

The surface of the 2 adjacent roads will be smoothen during this summer

Buildings

Technical buildings


Synchrotron building

Restaurant

Central building



95 cm thick slabs laying on piles for Storage Ring and Exp. Hall





Slab settlement <math>< 50 \mu\text{m} / \text{year}</math>

Vibrations amplitude <math>< \pm 0.5 \mu\text{m}</math>

Synchrotron building : Experimental Hall




Vibrations measurements : Effect of the crane on the storage ring slab



Storage Ring :

- Specific design of the girders supporting the magnets
(1st eigen mode > 40 Hz)
- High resolution Beam Position Monitors (< 1 μm)
- Fast position feedback (1-100 Hz) implemented in 2007
- Minimize effects of ID gap changes (magnetic measurements)



280 focusing magnets :
● 160 Quadrupôles
● 120 Sextupôles

32 bending magnets
Sitting on 2 girders

Girder design :
First resonant frequency > 40 hz
Strongly clamped on the slab


Vibration measurements on SR girders

Measurements done by AVLS company




Experimental Modal Analysis

**1st mode on quadrupole girder
(transversal flexion) at 45 Hz !**




**2nd mode on quadrupole girder
(vertical flexion) at 56 Hz**



Vibration measurements on SR girders


Residual levels with all utilities ON (cooling, ventilation,..)

Displacement Spectral Density in $\mu\text{m}/\sqrt{\text{Hz}}$



with bulldozer + truck working on the site

Residual levels



Time Signals are very similar since there is no dynamic amplification in the 0-20 Hz range

Linac and Booster designed for topping-up operation

2.75 GeV BOOSTER


2 super periods
Circumference: 157 m

36 Dipoles :
 0.67 T / 2.17 m

44 Qpoles:
 10.3 T/m - 0.4 m

Emittance:
 110-150 nm.rad

**Power supplies
 cycling at 3 Hz**




LINAC

100 MeV
 3 Hz rep Rate

Output charge :
8 nC in 300 ns
 in multibunch mode
 (500 mA in SR)

1.5 nC in 3 pulses (2ns)
 in 8 bunch mode
 (90 mA in SR)

Choice of solid-state switches for all the pulsed power supplies



K2&K4 field integral identity <math> < 3.5 \cdot 10^{-3}</math>

THPLS100
P. Lebasque

3 HV modules in // based on fast IGBT => matched kickers, able to permit a very steady operation for Top-Up injection.

The PS's create 8 kV-5.6 kA pulses, width 6.5 μ s half sine, low jitter <math> < 0.5</math> ns.

Storage Ring Septum magnet


Eddy current septum magnet leakage field strongly reduced
=> Full sine excitation (150 μ s)
=> Optimised shielding screen

THPLS101
P. Lebasque

$I_{\text{leak}} < 4 \mu\text{T.m} \Rightarrow 10 \text{ ppm of main field integral (255 mT.m)}$




*SuperImphy shielding screen
around the stored beam chamber*




*The septum magnet with its
shielding screen*

Storage Ring



Storage Ring Vacuum system

Vacuum system for one typical cell




2 stainless steel
vacuum

5 stainless steel BPM-Bellows
modules with RF shield
(COMVAT/RIAL)

G coated Aluminium
drupole type vacuum
vessels with SS/Al flanges
(SDMS/SAES)

Storage Ring Vacuum system

Vacuum system for one typical cell



Together with the Straight Sections chambers,
~200 m of NEG coated Al chamber (56% of the ring)


SOLEIL = first SR Machine with extensive use of NEG coated AL vessels

Goals :


- Outgassing all vacuum parts
- Activation of NEG coating deposited on the quadrupole chambers

Method :

- Heating of the vacuum chambers up to 180°C
- Use of resistive heaters deposited on 1mm thick Kapton foil, glued onto the vessels




Storage Ring Vacuum system



Storage Ring Vacuum system

Partial pressures at the end of the bake-out



After bake-out, the total pressure measured in a cell is in the low 10^{-10} mbar range. Max pressure $\sim 4 \cdot 10^{-10}$ mbar is measured close to the crotch absorber

Storage Ring : Vacuum system

10 small aperture Insertion device chambers (L=5.5 m / h=10 mm) installed before injecting the first electrons ! (First facility to dare doing it !)



Storage Ring : magnets



Dipoles (38) : TESLA
Quadrupoles (160): DANFYSIK
Sextupoles (120) : SIGMAPHI

Storage Ring : magnetic measurements

Very careful metrology to reach excellent alignment



alignment of the Magnetic measurement bench

May 2004-Aug. 2005

Magnetic measurements of 326 electro-magnets : magnetic axis centering, field properties

rotating coil bench built to reach magnetic centering to $\pm 25 \mu\text{m}$ and tilt $\pm 0.1\text{mrad}$


THPLS007
P. Brunelle

Table 1

	Statistical analysis of measurements			
	Quadrupoles		Sextupoles	
	Mean Value	RMS value	Mean Value	RMS value
ΔX (microns)	1.5	8.4	-3	15
ΔZ (microns)	2.6	7.5	2	10
Tilt (mrad)	0.008	0.040	0.010	0.100

ANS Qpoles (magnetic centres) Altimetry Mar 06 with N3 optical level


rms: appr. 0.087mm



THPLS006
JC Besson

◆ Before alignment Mar06 ◻ After alignment Apr06 ● Smoothing May06

Design and construction of a **dedicated cryomodule with 2 SC cavities** so as to provide HOM free operation up to 500 mA. (Collab CEA/CERN/SOLEIL/ESRF)



- Prototype tested initially at CERN and ESRF (2000-2002)
- Completely refurbished
- Tested at CERN (Oct 05).
- Installed On the Ring (Nov 05).
- Cooled @ 4 K since May 10, 2006
- **RF conditioned since May 24, 2006 (150 kW/coupler)**

MOPCH142
P. Marchand



1st cryomodule will enable alone operation up to 300 mA.

A 2nd cryomodule is being built by ACCEL for operation at 500 mA (2nd half of 2007)

Motivation : No klystrons suitable to the power required at SOLEIL

➤ **Solid state amplifier : → 1st unit (40 kW) built for the Booster (2004)**




MOPCH142
P. Marchand

→ Decision to use this technology for the Storage Ring


Storage Ring RF amplifier

4 x 190 kW power amplifiers

4 x 47kW solid state amplifiers
724 modules



315 W @ 352 MHz
Gain > 13 dB
Efficiency ~60%



Storage Ring RF plant

4 x 190 kW power amplifiers



190 kW @ 352 MHz
Gain = 52 dB
Overall Efficiency (PS,..) ~50%

Full Cost (with PS and WG distribution)


Booster : 200 k€ for 40 kW => 5 € / W

Stor. Ring : 3 M€ for 750 kW => 4 € / W

Modularity = You just pay for the W you actually need

Storage Ring RF amplifiers

April 6th, 2006 : 180 kW from amplifier n°1




World record !

Highest RF power produced with transistors

April 7th , 2006: 180 kW from amplifier n°2

Cryogenic source (Air Liquide) in RF area **400 W @ 4K + 50 l/h liquid He production**



120 BPMs (LIBERA modules from I-Tec) featuring :

- sub micron resolution
- turn by turn capability (**worked nicely during commissioning**)

TUPCH008
JC Denard

2 DCCTs, 1 FCT (Bergoz)

1 visible light monitor, 1 pinhole camera, 1 streak camera

Tune monitors and striplines

H and V scrapers

Fast and slow beamloss monitors


SOLEIL first facility using TANGO at full scale

Collaboration ESRF/ELETTRA/SOLEIL/ALBA

- easy and efficient tools to control any equipment
- data archiving
- control of all equipments from the control room
- supervision done using “Global Screen” applications (developed by operators)
- All hardware installed (Crate with CPCI and boards, PLC's..)
- Machine commissioning : Matlab applications (**Matlab Middle Layer Toolkit...**)

THPCH109
A. Nadolski

Electromagnet Helical Undulator HU640



THPLS118
F. Briquez


DanFysik	HU640
Period	640 mm
Nbr of Periods	14
Length	10.0 m
Type	Electro-magnetic
Min. gap (mm)	19
Polarisation	Circ./Lin. adjustable
Bxmax	0.09 T
Bzmax	0.11 T
Photon Energy	5 – 40 eV

Vacuum chamber for HU640

- Al extruded up to 10 m long
- Water cooled
- NEG coated in 2 parts 5m long (SAES)
- Welded together (CINEL)



Electromagnet Helical Undulator HU256



THPLS118
F. Briquez


BINP/SOLEIL	3 x HU256
Period	256 mm
Nbr of Periods	12
Length	3.6 m
Type	Electro-magnetic
Minimum gap (mm)	15 (V) 50 (H)
Polarisation	Circ./Lin. H et V
Bxmax	0.275 T
Bzmax	0.400 T
Photon Energy	10 – 1000 eV

Apple-II Type Helical Undulator HU80

ELETTRA/SOLEIL	3 x HU80
Period	80 mm
Number of Periods	19
Length	1.65 m
Type	Apple-II
Minimum gap (mm)	15 to 250
Polarisation	Circ./Lin.
Bxmax	0.76 T
Bzmax	0.85 [1.0] T
Photon Energy	80 [35] – 1500 eV



THPLS118
F. Briquez



DANFYSIK/SOLEIL	3 x U20
Period	20 mm
Nbr of Periods	98
Length	2.0 m
Type	Hybrid In-Vacuum
Min. gap (mm)	5.5 to 30
Polarisation	Linear H
Bzmax	0.97 T
Photon Energy	3 – 18 keV

THPLS118
F. Briquez



Commissioning

Linac

Booster

Storage Ring



Linac installation completed by THALES in Spring 2005

Integrates 2 Accelerating sections donated by CERN

1st beam on July 2nd, 2005

Linac heart is beating !




Many experiments and tuning performed by THALES and SOLEIL.

Excellent performances (stability/reproducibility)

Final Acceptance pronounced on November 15th, 2005

Beam transmission



Gun

Buncher input: 85%

Section 1 output: 62%

After Energy analyzing slit: 53%


TUPCH112
A. Setty

4 pulses with a level's decrease: < 5 %



Characterization using TL1 diagnostics :

- => Emittance measurements
- => Energy dispersion



Emittance measurements results

Mode	Beam Charge	Horizontal π mm mrad	Vertical π mm mrad
Long Pulse	10.6 nC	47	52
Short Pulse (1)	0.55 nC	64	67
Short Pulse (4)	2.27 nC	67	78

THPLS010
MA Tordeux


(Specifications : ($\gamma\epsilon$ at 90 %) < 200 π .mm.mrad)

Booster


Arcs



RF Cavity
(LEP)



Injection



Extraction



Installation was completed in July 2005

1st beam in the Booster at 110 MeV




July 23rd 2005

Booster equipment are OK !




2 turns !



Beam stored !

Booster : 1st beam accelerated to 2.75 GeV

October 13th 2005
Efficiency 2.5%
(from TL1)




Injection at
110 MeV

2.75 GeV


Loss on
resonances

Fast increase of the acceleration efficiency




Booster : Power supplies tracking

4 power supplies (Bruker) ramped at 3 Hz : “Tracking” $\pm 0.2 \%$



Dipole 1 versus
Dipole 2
(2 x 560 A / 1000 V)




QF, QD
versus
Dipole 1


WEPLS118
P. Gros



Booster Efficiency ~ 90-95 %



Tunes kept within ± 0.05




Beam decelerated down to 140 MeV

THPLS008
A. Louergue

Booster : 1st extraction of 2.75 GeV beam

May 6th




Booster FCT

Transfer line
FCT1

Transfer line
FCT2

Storage Ring Commissioning

May 14, 2 am : THE VERY FIRST TURNS (9)
(without any trajectory correction)




The beam went through the 10 small aperture chambers !!

THPLS009
A. Nadjj

Start of radiation measurements (May 14, May 20, May 31)


Storage Ring Commissioning


1st beam storage (0.3 mA) on June 2nd at 2 am !



Storage Ring Commissioning

1st beam accumulation (8 mA) on June 4th at 3 am !






Continuous Injection during radiation controls




Results from the γ monitors interlocking the Linac.






Storage Ring Commissioning

Uncorrected closed orbit errors : rmsH = 2.31 mm, rmsV = 0.58 mm




After correction : rmsH = 0.38 mm, rmsV = 0.31 mm




Vacuum conditioning

Average pressure of Cell C07 normalised to current
vs
the beam dose



Vacuum conditioning

Average pressure of Cell C07 normalised to current
vs
the beam dose



C. Herbeaux


Few problems

- **Problem of reduced flow due to small resin balls contaminating the water cooling circuit due to a human mistake**
 - ⇒ Blocking of the filters on the magnets
 - ⇒ Blocking of the filters on some power supplies
 - ⇒ Blocking of the crotch cooling circuits

 - ⇒ Cleaning of the whole network during this summer

- **Problem of obstacle reducing the beam stay clear aperture**
 - ⇒ Bad mounting of 2 RF Finger assemblies (out of ~200)

 - ⇒ Will all be checked during this summer



Smooth and efficient start-up of the commissioning

- All diagnostics required were available on time
- The TANGO Machine control system worked nicely
- Excellent machine alignment
- Vacuum conditioning in good progress
- But present current limitations possibly due to Fast Ion instabilities ?
- Present performances are very promising

THPCH032
R. Nagaoka

Our present goal is to reach 100 mA usable by the beamlines

The delivery of photon beam for the commissioning of the beamlines will start in September 2006

The construction SOLEIL is completed.

SOLEIL has largely benefited from the Experience and expertise of the other labs.

We believe that SOLEIL has in return brought some significant contributions to the accelerator technologies

