

Current Status of a SC-ECRIS of the RAON Accelerator

Yonghwan Kim


Specifications of a SC-ECRIS for RAON accelerator

| | | |
|--|--------------------------|--|
| Magnet and magnetic field | SC Wire | NbTi |
| | Number of Solenoid Coils | 4 |
| | Hexapole Winding Type | Saddle |
| | B_{inj} (T) | >3.5 |
| | B_r (T) | 2 |
| | B_{ext} (T) | 2 |
| | B_{min} (T) | 0.4 ~ 0.8 |
| RF system | RF Frequency (GHz) | 28+10 |
| | RF power (kW) | 10+2 |
| Plasma chamber and beam extraction system | Chamber material | Al |
| | Plasma volume | About 8.5 Liter ID = 147 mm L = 500 mm |
| | Triode electrode system | ~ 25 kV |
| | Acceleration column | ~ 50 kV |

28GHz SC-ECRIS Development History and Plan



| Plan | 2013 | 2014 | 2015 | 2016 | 2017 | 2018 |
|--|------|------|------|------|------|------|
| Design and Fabrication | | | | | | |
| SC Magnet & Cryosystem design | | | | | | |
| Magnet fabrication | | | | | | |
| Cryosystem fabrication | | | | | | |
| plasma system design | | | | | | |
| plasma system fabrication | | | | | | |
| Install and test | | | | | | |
| SC Magnet individual test | | | | | | |
| SC Magnet whole system test | | | | | | |
| plasma system HV and vacuum test | | | | | | |
| initial beam commissioning | | | | | | |
| test facility building remodeling work | | | | | | |
| Disassemble and Maintenance | | | | | | |
| reassemble | | | | | | |
| beam commissioning | | | | | | |
| metal beam extraction | | | | | | |
| Transfer to main site | | | | | | |
| beam commissioning at main site | | | | | | |

Schematic View of ECRIS






Design of superconducting magnet




| | sol1 | sol2 | sol3 | sol4 | Hexapole |
|-------------------------------|------------|------------|------------|------------|--------------|
| Axial position of center [mm] | -250 | -76 | 65 | 250 | |
| Inner radius [mm] | 188 | 188 | 188 | 188 | 108 |
| (radial) Thickness [mm] | 67 | 45 | 58 | 67 | 50 |
| Width [mm] | 230 | 55 | 65 | 145 | |
| Conductor [mm] | 1.6 x 0.91 | 1.6 x 0.91 | 1.6 x 0.91 | 1.6 x 0.91 | 1.43 x 0.98 |
| Cu/NbTi ratio | 3.65 | 3.65 | 3.65 | 3.65 | 3 |
| Turns/coil | 9724 | 1435 | 2320 | 5670 | 1367 |
| Design Current (A) | 151.8 | -125.1 | -132 | 143.2 | 254 |
| Wire length (km) | 13.55 | 1.9 | 3.16 | 7.89 | 2.56 km/unit |




Fabrication of SC-coil with a Korean domestic company



Fabrication of SC-coil with a Korean domestic company





Cryostat assembly






Plasma chamber design and fabrication



- Chamber material : Aluminum
- Vacuum seal : do not use o-ring seal but metal seal if it is possible



Microwave injection & plasma generation part





Plasma facing electrode



Beam extraction part

Triode system



Plasma chamber



Installation History


- 2014. 05. 26



- 2015. 01



- 2015. 03




- 2016. 02




Installation History


- 2016.06



- 2016.08




Record of SC magnet test





- Test various ramp up sequences and ramp rates
- Sustain magnetic field for several hours

Commissioning test in 2015




Beam current measurement



Cryostat cooling capacity change


- Issue : Cooling capacity decreases during the experiments in 2015.




→ Modification to enhance the cryo-system performance
during the test facility building remodeling work

Modification of a cryo-system

- Screw structure is modified



- Change the heat transfer cable between cryo-cooler and SC coil current lead into thicker and wider one




Modification of a cryo-system

- Enlarge a surface area of a LHe condensing part




- After modification, cryostat cooling capacity was recovered over 6 W

Test layout of the ECRIS after reinstallation in 2016




Test layout of the ion source as a part of SCL Demo

ECRIS test layout



beam commissioning in 2016


| Parameters | value | Note |
|--------------------|---|------|
| Mag. Field | 60% for Solenoid, 70% for Hexapole | |
| Base pressure | 3.0×10^{-8} Torr | |
| Operating pressure | 1.0×10^{-7} Torr | |
| Operating gas | Oxygen | |
| RF power | 28 GHz 200 W → 250 W → 300 W → 400 W | |
| Applied potential | Plasma electrode : 12.5 kV Acceleration electrode : -1 kV → -2 kV Deceleration electrode : grounded | |
| Focusing solenoid | 170 A | |
| ESQ triplet | #1 : 1.0 kV #2 : 1.8 kV #3 : 0.9 kV | |
| ESQ doublet | #1 : 0.9 kV #2 : 0.3 kV | |
| Steerer | X : 0 A Y : 0 A | |



For O5+


Preparation for metal beam test

- Target beam : Bi which has many test data from other research group
- Sputtering rod with water cooling system
: melting point of Bi is 271.5°C



Preparation for metal beam test

- Test oven : a benchmark of other research groups. Made of Tungsten



- 1900°C was achieved with 1.1kW

Summary

1. We has built a 3rd generation SC-ECRIS since 2013
 2. We began a machine commissioning in 2015
 3. Our machine will supply a test beam for SCL demonstration of RISP through a beam commissioning
 4. Current status of our machine are as follows
 - 1) Cryo-cooling capacity of 6.3W is being sustained
 - 2) SC magnets are being operated stably at the 70% level of the design value
 - 3) Still doing Electrode conditioning :
: to get the stable operating condition with the potential difference between plasma electrode and acceleration electrode is 25kV
 - 4) Beam commissioning is being done to supply a O7+ beam of 10uA to RFQ
: this year's goal
 - 5) Metal beam test is being prepared parallelly
- I would like to thank to Dr. Nakagawa, Dr. Sun, and Dr. Thuillier who give me many valuable advices always.