# Redesign of the GANIL GTS ECRIS for 1+/n+ studies

V. Toivanen, P. Jardin, L. Maunoury and C. Michel

Grand Accélérateur National d'Ions Lourds (GANIL), Caen, France

10 September 2018



## Contents

- 1. Introduction and motivation
- 2. From ECRIS to CB: a new injection module
- 3. Ion optical simulations
- 4. Summary and conclusions



#### Motivation – Metal ion production

- Metal ion beams widely used (e.g. over half of GANIL beams), continued development important
- With conventional methods (ovens, sputtering, MIVOC) the global ionization efficiencies are low



#### Motivation – Metal ion production



C. Barué et al., in Proc. of 22<sup>nd</sup> Intl. Workshop on ECR Ion Sources, Busan, Korea, 2016

#### Motivation – Metal ion production

- Metal ion beams widely used (e.g. over half of GANIL beams), continued development important
- With conventional methods (ovens, sputtering, MIVOC) the global ionization efficiencies are low
- 1+/n+ method: efficiencies >50% have been demonstrated
  - Decreased material consumption and chamber contamination
  - Decoupling of metal ion production and multi-ionization process
- Challenges:
  - High intensity operation needs to be demonstrated
  - Very high efficiency production of the initial 1+ beams

Experimental work required to validate the potential of 1+/n+ method for metal ion production



#### Motivation – Support for SPIRAL1 Charge Breeder

- Recently commissioned at GANIL
  RIB facility SPIRAL1
- Operational machine in high radiation dose area
- Limited access, restricts the future charge breeder R&D at GANIL



Offline test stand desirable, results transferred to SPIRAL1 CB





# GTS 14.5 GHz ECRIS a future 1+/n+ R&D platform

 $\mathcal{O}_{\mathbf{X}}$ 

- <u>2017</u>: extraction upgrade, new center coil
  - Up to 3x more beam
- o 2018: new injection system
  - Double frequency operation
  - E.g. 8x more Xe<sup>30+</sup>
- O <u>Next:</u> operation + CB R&D
  - Quick transition between conventional ECRIS and 1+/n+ operation modes required

Dedicated injection systems for conventional and for 1+/n+ operation

Modifications required





# New injection system for 1+/n+ operation **Injection module (with 1+ source) GTS ECRIS GND** HV To overcome the plasma potential deceleration acceleration









1+ beam production and main ion optics

- 1. 1+ ion source
  - First: thermionic alkali ion source
  - Later other sources to expand capabilities
- 2. Puller electrode
- 3. Einzel lens







Beam manipulation and diagnostics

- 1. Horizontal steerer
- 2. Vertical steerer
- 3. 2-sided Faraday cup
- 4. Beam dump for pulsed operation







Microwave and gas injection, B field modification

- 1. WR62 wave guide
- 2. WRD750 wave guide
- 3. Gas injection pipe
- 4. ARMCO cylinder
- 5. Injection aperture electrode (ARMCO, can be biased)



1+ beam deceleration and injection into the plasma chamber

- 1. Grounded tube
- 2. ARMCO cylinder (V<sub>GTS</sub>)
- 3. ARMCO injection aperture electrode  $(V_{GTS}+V_{IAE})$

# Magnetic field



B field design and calculations performed with Radia software



#### • Simulation tools:

- *IBSimu* ion optical code, 3D geometry
- 3D magnetic field maps from Radia



- Simplified model for GTS plasma: fixed plasma potential, no particle interactions
- $\odot~$  Beam: 10  $\mu A$  of  $^{39}K^+$  with  $\epsilon_{4rms}$  = 20 mm mrad
- Main goal: verify transmission through the injection module
- <u>Secondary</u>: injection efficiency into the plasma chamber (only suggestive results possible due to simplified plasma model)





( $V_{plasma} = 10 V$ )











0.4

z (m)

0.5

0.6

0.7

0.1

0

0.2

0.3

**Beam dump** 

0.8

- Potential issue: ions extracted from plasma towards injection
- Simulation: 0.9 mA of extracted oxygen ions (1+ ... 8+)



Not expected to be a significant issue for operation



## Summary and conclusions

- The design to transform GTS into a charge breeder is ready
- The included features should provide good capabilities for charge breeder R&D
- The simulation results look promising no showstoppers expected
- Parts procurement on-going, installation and commissioning expected in 2019



#### **EXTRA SLIDES**



## Magnetic field

