SDUV-FEL Facility Progress

Dai Zhimin on behalf of SDUV-FEL team

2006.5.18



中國科学院上海永田物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

SDUV-FEL Facility Progress

Introduction

Simulation and Parameters

Status of main components



Introduction

- □ Shanghai Deep-Ultraviolet FEL (SDUV-FEL), an 80nm High Gain Harmonic Generation FEL test facility, since 2000.
- Being carried out by Shanghai Institute of Applied Physics in cooperation with
- Institute of High Energy Physics /IHEP
- NSRL, Univ. of Science and Technology of China
- Accelerator Lab. of Tsinghua University
- □ Fund partially supported by
- Chinese Academy of Sciences/CAS
- Ministry of Science and Technology of China/MOST
- National Natural Science Foundation of China/NSF
- □ Will be executed in phase | and phase ||
- **Expect to provide an experiment benchmark for X-ray FEL in future**



HGHG FEL in third harmonic case



中國科学院上海龙的物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

SDUV-FEL Layout (Phase-I)





SDUV-FEL Layout (phase II)





Current Schedule of SDUV-FEL

2002.1~2005.12	Construction and commissioning of a 100MeV Linac with grid gun as prototype of pre-injector of SSRF
2006.1~2006.9	Installation of 40MeV injector with photocathode RF gun
2006.9~2007.6	Commissioning of photocathode RF gun and 40MeV injector
2007.1~2007.12 (phase 1)	Installation of undulator system, seeding laser, and electron beam / laser diagnostic instruments; Begin on experiments of UV-FEL (262nm)
2008.1~2009.12 (in phase 2)	Upgrade Linac energy to 280MeV, and begin on experiments of DUV-FEL (88nm)



Simulation and Parameters

- HGHG FEL process was simulated by modified TDA3D and GENESIS
- □ SASE FEL process was simulated by GENESIS
- Start-to-end (from photocathod rf gun to end of undulator) simulations have been under way since 2002, by PARMELA,ELEGENT,GENESIS and modified TDA3D
- Study sensitivity of FEL parameters on beam emittance, peek current, energy spread and field errors of undulator
- Based on these simulations, parameters of SDUV FEL have been determined, as listed in the following



Main Parameters of SDUV-FEL

	Phase I	Phase II
FEL Parameters		
Wavelength (nm)	262	87
Output Power (MW)	~80	~140
Gain Length (m)	~0.7	~0.8
Electron Beam Parameters		
Energy (MeV)	~159	~276
Peak Current (A)	300	400
Emittance (mm-mrad)	6	4
Energy Spread (rms)	<0.1%	
Undulator Parameters		
Period (cm)	2.5	
Gap (cm)	1.0	
Length (m)	~9	



Simulation of SDUV-FEL

- 87nm SASE FEL
- 87nm HGHG FEL
- 262nm SASE FEL
- 262nm HGHG FEL



Optimization of SDUV-FEL

Power gain length as a function of Undulator period and beta function





Optimization of SDUV-FEL

Separated FODO lattice (undulator segments +quad.)



Choose Qd=4T/m and Qf=6T/m to obtain higher saturation power/shorter saturation length for 87nm SASE FEL





87nm SASE FEL



中國科学院上海走到物理研究所 SINAP Shanghai Institute of Applied Physics, Chinese Academy of Sciences

87nm HGHG FEL



SDUV-FEL(87nm) output power vs undulator length



262nm SASE FEL



262nm SASE FEL radiation pulse at four typical radiator positions

中國科学德上海走的物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

262nm SASE FEL



Sensitivity on electron beam parameters

Currently, the undulator system is only about 10m long, therefore, we study the sensitivity of output power at the exit of the undulator system on electron beam parameters.



262nm HGHG FEL



中國科等德上海走到物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

262nm HGHG FEL

Stability depending on DS and seed laser



中國科学院上海龙的物理研究所 Shanghai Institute of Applied Physics, Chinese Academy of Sciences

Status of main components

- Linac system: existing 100MeV linac (commissioned last year)
- Photocathode Gun (first one, fabricated and tested, second one being fabricated)
- Gun laser (installed and being commissioning)
- Undulator (first segment, fabricated and measured)
- BC1 (fabricated and measured)
- Beam Diagnostic (CTR being tested, YAG-pop-in being fabricated)



Existing 100MeV linac

100 MeV Linac has been successfully commissioned in 2005



100kV-ns grid gun and 15MeV buncher





Existing 100MeV Linac







Existing 100MeV Linac

Klystron modulator with high voltage pulse amplitude stability of 0.1% and top unflatness of 0.25% has been developed for SDUV FEL





Existing 100MeV Linac



Control room(Software based on EPICS)

Power supplies for focusing solenoids and magnets





Upgrade Linac to 160MeV for phase 1



100kV-ns grid gun and 15 MeV buncher of the existing 100MeV Linac will be replaced by a 40MeV injector consisting of photo-cathode rf gun and an accelerating section in 2006



30MW RF source for 40MeV injector

30MW RF source for 40MeV photo-cathode injector is being tested by collaboration with IHEP.





Photocathode RF Gun

- Main parameters: beam energy 4~5MeV bunch charge 1.0nc normalized emittance 3~6mm.mrad bunch length ~8ps repetitive rate 10~25Hz
- Design is based on the 1.6 cell s-band rf gun developed at BNL DUV FEL, including emittance compensating solenoid
- Use Magnesium (Mg) or Copper (Cu) photo-cathode
- Developed by Institute of High Energy Physics (IHEP) in collaboration with Tsinghua University
- Commissioning is expected to start in Sept. 2006



Photocathode RF Gun

1.6 cell s-band RF gun (IHEP)





Mg Photo-cathode with 12mm diameter(Tsinghua Univ.)



Laser system for RF gun

- Jaguar-QCW-1000 Laser (+FHG) and Synchronizer CLX-1100 (Switzerland Time-Bandwidth Products, Inc) has been delivery
- Commissioning since February 2006
- Main parameters

Laser medium Wavelength Pulse length Repetition frequency Energy/pulse Energy stability (p-p) Time stability Nd:YLF 1047nm/262nm 12ps/8ps 0~100Hz 1mJ/0.25mJ 1%rms 0.5ps rms



Laser for RF Gun





Laser for RF Gun



Energy stability of 262nm laser output



Beam profile of 262nm laser output

Beam pointing: 25urad

Bunch compressor I

BC1(four-dipoles magnetic chicane)



Main parameters•Beam energy100 MeV•Energy spread1%•Bunch length8~9/3~4ps•Compression ratio2~3•Bend angle (deg)7~14•Maximum field4000 Gs•R₅₆(Max.)-100 mm



Undulator System

Undulator (developed by NSRL) is under construction



The First segment has been fabricated and measured)

Main parameters			
Period length	25mm		
Gap	10mm		
Peak Field	0.6T		
Κ	1.4		
Type hybrid	hybrid/Nd-Fe-B		
Segment length	1512.5mm		
Space between			
segments	250mm		
Segment number	6		
First field integral	0.1T-mm		
Second field integral			
10T-mm*mm			



Undulator System

Undulator 3D Layout and deformation analysis by ANSYS code







Undulator Vacuum Chamber





Beam diagnostics for Phase 1

Distribution of diagnostic instruments for SDUV-FEL (Phase-I)





Pop-in Monitor in Undulator



- BNL-DUV-FEL type Pop-in monitors in undulator will be used for FEL lasing experiments
- Each pop-in monitor has two different inserting positions, which are used for two different purposes : in first position(in f.p.) electron beam is blocked by YAG crystal(Cerium doped),and to image electron beam; in second position(in s.p.) pop-in monitor will be inserted less so that a 45 degree mirror reflects FEL light to north side of undulator



Beam Position Measurement

✓ CBPM





5.712GHz



Beam bunch length measurement

(CTR developed by SINAP)





Beam bunch length measurement





Beam bunch length measurement

✓ SLAC - LOLA studying by IHEP



Vertical RF deflecting structure (one period) HFSS simulation





P